

99'er

COVERING THE TEXAS INSTRUMENTS
BRAND OF HOME COMPUTERS




HOME COMPUTER

magazine

February, 1983

\$3.50 in U.S.A.



Printers in the Home

- Two New TI Computers Unveiled
- Expanding Your System with Compact Peripherals
- The Voice of Parsec
- Learning with LOGO & ASPIC
- Speech Recognition for the Home Computer



TEXAS INSTRUMENTS



Scott, Foresman

Combining computers and classrooms...with confidence



"Scott, Foresman's expertise and commitment shows through in their microcomputer courseware...This is the way software should be; easy to use, effective and reliable..."

Dr. D. Thomas King, Assistant Director, St. Paul Public Schools

It takes more than knowledge to provide effective, useful computer products. It takes a commitment. A commitment to education—providing the skills and concepts students need to learn; a commitment to expertise—making materials useful to teachers; a commitment to simplicity—providing equip-

ment that's easy to use; a commitment to students and educators alike—resulting in friendly, effective, reliable computer products.

Discover the Scott, Foresman commitment. Send for our **FREE** catalog and compare.



Electronic Publishing Division

We teach students in ways you may have never imagined.



Scott, Foresman and Company

1900 East Lake Avenue • Glenview, Illinois 60025

Please send me a **FREE** Scott, Foresman Electronic Publishing catalog. I am interested in software for:

☐ School Management Applications ☐ Mathematics

☐ Reading ☐ Science ☐ Computer Literacy

☐ SPIN Microcomputer in use: _____

☐ I am interested in microcomputer equipment.

Please have a representative contact me.


Name _____ 99/2

Position _____

School _____

School Address _____

City/State/ZIP _____



ATTENTION, EARTHPEOPLE! AN IMPORTANT MESSAGE FROM MOONBEAM SOFTWARE ESPECIALLY FOR TI-99/4 (A) OWNERS!

Moonbeam Software will turn your computer into an arcade machine! Super-fast action games now ready to take over your controls! Dazzling full-color graphics! Explosive sound effects! All now available in TI-BASIC and/or Extended BASIC for the 16K console!

1) DEATH DRONES

Can you protect your nuclear reactor from the relentless Alien Drones? Will your city be reduced to rubble by devastating nuclear explosions? BASIC or X-BASIC, \$14.95

2) MOONVASION

Alien starfighters are attacking your moonbase! Can you aim and fire your Moon Launch fast enough? Will your squadron be destroyed? BASIC or X-BASIC, \$14.95

3) GARBAGE BELLY

Help the Garbage Belly gobble up ripe garbage in a field of garbage pails! But watch out! If you make him eat raw garbage, he will die! X-BASIC, \$19.95



4) STRIKE FORCE 99

Your planet is doomed! Destroy the Cryolian death ship before it unleashes its deadly death rays, annihilating your civilization! X-BASIC, \$19.95

5) MOONBEAM EXPRESS

Defend your cargo ship from enemy fighters on your supply mission to the outpost located deep in Quadrant 91 X-BASIC, \$19.95


6) ASTROMANIA

Pilot your fleet of photon-powered ships through the asteroid canons of Sulconon, the aerial attack squad of Caustress, the meteor belt of Trisod! Then face the unforgiving Zircon Droids! X-BASIC, \$19.95

Moonbeam Software is the key to unlocking the full potential of your TI-99/4(A) computer! All programs are available on either cassette or diskette! Attractively packaged in full-color boxes, each game includes both keyboard and joystick versions.

Ask for Moonbeam Software at your local retailer or use the coupon in this ad.

Dealer inquiries invited. Call Mr. Moon at (413) 586-6290.



MOONBEAM SOFTWARE

2 Bridge St., Northampton, MA 01060
Telephone (413) 586-6290

YES! I want to turn my TI-99/4(A) into an Arcade Machine! Please send me the following game(s):
(Please circle C for cassette or D for diskette versions)

<input type="checkbox"/> DEATH DRONES C D	\$14.95	GAMES \$
<input type="checkbox"/> MOONVASION C D	14.95	Mass. Res. Add 5%
<input type="checkbox"/> GARBAGE BELLY C D	19.95	Shipping & Handling 1.50
<input type="checkbox"/> STRIKE FORCE 99 C D	19.95	TOTAL \$
<input type="checkbox"/> MOONBEAM EXPRESS C D	19.95	<input type="checkbox"/> MIC <input type="checkbox"/> VISA Exp. Date
<input type="checkbox"/> ASTROMANIA C D	19.95	Card No.

Name _____ Signature _____

Street _____

City/State/Zip _____

TI-99/4(A) is a registered trademark of Texas Instruments.

© All games copyright 1982 Moonbeam Software.

OUTSIDE 99' EA



This Issue's Cover

All the comforts of home . . . This month's cover depicts a new "comfort" that your Home Computer system can offer—freedom from the drudgery of handwritten record keeping and tedious typing. With a printer, your computer can take over all kinds of time-consuming word processing tasks. After all, if your home is really your castle, you shouldn't be bothered with menial secretarial chores there. So make room in the spare corner, throw aside your obsolete writing implements, and roll out the "Data Welcome" mat. This labor-saving peripheral can indeed become your trusted scribe.

INSIDE 99'ER

As the invention of movable type changed the course of civilization, so has the availability of the printer radically altered the role of the Home Computer. The addition of this peripheral transforms your computer from an efficient file clerk to a top-notch secretary. This month, we look at a possible missing link in your Home Computer system—a small machine that can convert your vast storehouse of “soft” information into “hard copy.”

To find out if you really need a printer, or to help you decide what kind you want, you'll need a clear explanation of printer basics. *Who Needs a Printer?* describes the different kinds of printers, explains how they work, and points out the important features you *do* and *don't* need.

You're convinced—and you want that printer in time to print out your Valentine mailing list. But before you go shopping, do some comparing. *Printers on Review* carefully looks at five TI-compatible models, noting structural differences and comparing such factors as speed, quality of print, cost, and graphics.

Speaking of graphics, in *Chuck-A-Luck: Part 4* we will be completing our game-programming lesson with instructions for displaying the rolling dice. And keep your eye on those tumbling sprites. They are classic representations of the vector, according to this month's *LOGO Times* lead article. *Vectors in LOGO: Of Stars and Sprites* demonstrates how TI LOGO and sprites can help students understand the concept of vectors at an early age—well before college physics, when it is traditionally presented.

While you're in a mathematics (and graphics) mode, try your hand at *Daisies*, a program that demonstrates how LOGO can use trigonometric functions to graphically display the delicate petals of a richly recursive daisy.

Do trigonometric functions and vector analysis seem a bit heavy on the brain? Then maybe you need a gaming break. *Lifeline to Titan* may not, however, prove to be an especially relaxing interlude. It will require precise timing and careful maneuvering to land your spacecraft safely

on the rugged terrain of Saturn's largest moon.

For a truly relaxing break, why not turn to Professor Holl's latest pocket program, *Tower of Hanoi*? Professor Holl offers a new twist on an old game classic, carefully explaining this simple program so that even beginners can use it to test their TIBASIC programming and gaming skills.

Gaming skill is the subject in Part 2 of *The Joy of Adventuring*. Here you'll find concrete strategies for outwitting the dragons, warlocks, and other fiends who dog your steps as you run through these adventure games. Even if you fancy yourself a master of the adventure game genre, this piece can teach you a trick or two.

And fancy tricks for learning math are presented in *ASPiC: A Language for Teachers*. Two of the four *ASPiC* programs in the article use graphics to illustrate such concepts as "square numbers" and odd vs. even. The others are drill-type programs designed to familiarize students with long division and multiplication.

An already familiar voice speaks up in *Twenty Questions with the Voice of Parsec*. The young woman whose voice you hear on the *Parsec* game tells how it feels to have thousands of dedicated game players jumping to her commands...

And you are commanded to man your battle station in *Night Blockade*. Firing into the night, you must defend your battleship against an aggressive enemy you can't even see!

In the midst of the blinding explosions and deafening cannon fire, you catch something strange on your radar screen. Enemy reinforcements? No, the signals are coming from a friendly source. Looming on the horizon is a dazzling array of new audio-visual hardware, a mountain of luminescent display screens, and a whole passel of robots—it's the *Consumer Electronics Show*. Your *99'er Home Computer Magazine* correspondents were there to provide a detailed report on the latest in TI hardware, software, and peripherals. Proof positive that TI will never run out of exciting new ideas.

Until next month, have fun reading, learning, and RUNNING!




47. **Vectors in LOGO: of Stars and Sprites**
—By *Richard Bies*
49. **Daisies: Math Flowers With LOGO**
—By *Roger B. Kirchner*

Programming Conventions

KEY-IN REFERENCE


DO NOT WRITE IN THESE SPACES



Program as listed will completely fill available memory of TI-99/4A and cannot be RUN with disk controller (and possible RS232 interface) turned on; it must be SAVED and RUN from cassette. It may also possibly be SAVED and RUN from disk in Extended BASIC with the 32K memory peripheral if the last 2 character sets were not used.

End of Program or Article


**පාඨකයාගේ
ප්‍රශ්නාන්තරය**



SPECIAL FEATURE

Texas Instruments
at the
Winter
Consumer
Electronics
Show

41.



99'er VERSION

2 . 4 . 1 . XB AL MM EM

Volume no.
Issue no.
Version
1 = original program
2
= no. of update
11
11 Extended BASIC
Assembly Language
Min Memory Required
32K Expansion Memory Required

99'er

COVERING THE TEXAS INSTRUMENTS
BRAND OF HOME COMPUTERS



HOME COMPUTER magazine


February, 1983

Vol. 2, No. 4



9. Who Needs A Printer?
—By Charles M. Ehnliger


11. Printers on Review
—By W.K. Balthrop



22. Professor Hail's Pocket Programs:
Tower of Hanoi
—By S.T. Hail

56. ASPIC: A Language for Teachers
—By Andrew Berner
and Kathleen Martin

4. Inside 99'er
6. On Screen
7. Letters to the Editor
46. Debugs on Display
67. Index to Advertisers




FEATURES

- 25. The Joys of Adventuring—Part 2
—By Samuel D. Pincus
- 27. Chuck-A-Luck—Part 4
—By Samuel D. Pincus
- 35. Arcade Arbiter Review
- 40. Twenty Questions
With the Voice of Parsec

30. CAMEWARE BUFFET

Two program entrees for the
hungry game player.
• Lifeline to Titan—By Bill Bles
• Night Blockade—By Ants Reigo





COVERING THE TEXAS INSTRUMENTS
BRAND OF HOME COMPUTERS

99'er Home Computer Magazine is published monthly by Emerald Valley Publishing Co., P.O. Box 5537, Eugene, OR 97405. The editorial office is located at 1500 Valley River Drive, Suite 250, Eugene, OR 97401. (Tel. 503-485-8796). Subscription rates in U.S. and its possessions are \$25 for one year, \$45 for two years, and \$63 for three years. In Canada and Mexico add \$7 per year. Other foreign countries \$43 for one year surface mail. Inquire for air delivery. Single copy price in U.S. and its possessions is \$3.50, and \$4.00 in Canada and Mexico. Foreign subscription payment should be in United States funds drawn on a U.S. bank. Second-class postage paid at Eugene, OR 97401. POSTMASTER: Send address changes to **99'er Home Computer Magazine**, P.O. Box 5537, Eugene, OR 97405. Subscribers should send all correspondence about subscriptions to above address.

Address all editorial correspondence to the Editor at **99'er Home Computer Magazine**, 1500 Valley River Drive, Suite 250, Eugene, OR 97401. Unacceptable manuscripts will be returned if accompanied by sufficient first class postage and self-addressed envelope. Not responsible for lost manuscripts, photos, or program media. Opinions expressed by the authors are not necessarily those of **99'er Home Computer Magazine**. All mail directed to the "Letters to the Editor" column will be treated as unconditionally assigned for publication, copyright purposes, and use in any other publication or brochure, and are subject to **99'er Home Computer Magazine's** unrestricted right to edit and comment. **99'er Home Computer Magazine** assumes no liability for errors in articles or advertisements. Mention of products by trade name in editorial material or advertisements contained herein in no way constitutes endorsement of the product or products by **99'er Home Computer Magazine** or the publisher unless explicitly stated.

Each separate contribution to this issue and the issue as a collective work Copyright 1983 by Emerald Valley Publishing Co. All rights reserved. Copying done for other than personal or internal reference use without the permission of Emerald Valley Publishing Co. is prohibited. Requests for special permission or bulk orders should be addressed to the publisher.

99'er Home Computer Magazine, 99'er Magazine, Home Computer Magazine, and HCM are all trademarks of Emerald Valley Publishing Co.

Publisher/Editor-in-Chief
Gary M. Kaplan

Managing Editor
David G. Brader

Assistant Editors
Greg Roberts
Judy Sanoian

Technical Editors
William K. Balthrop
G.R. Michaels
Patricia Swift

Contributing Editors
Henry Gorman, Jr.
Walter Hego
Roger Kirchner
Samuel Pincus
Regena
Steve Schwartz
George Struble

Production Manager
Norman Winney, Jr.

Production & Design
Laredo
Corby Poticha
Carl Shaw
Jennifer Somers

Office Manager
Pat Kaplan

Circulation & Fulfillment
Irene Alderman
Mark Anderson


Jonnie Hernandez
Benjamin Kaplan
Coleen Nelson
Carol O'Brien

Clerical
Betty Gregory
Kathy Ricciuti

Accounting
Tasane Fry
Patana Ratanapreux

Typesetting
June Gaber
Julienne Laabs
Gil Sans

Advertising Manager
Linda Brundige
Tel. 503-485-8796



ON SCREEN

By Gary M. Kaplan
Publisher & Editor-in-Chief

The "\$500 Word Processor"—an impossible dream? It certainly used to look that way. Even as recently as last year, a computer with an 80-column display, letter-quality printer, and word-processing software cost at least several times that figure—and my targeted "dream price" for an affordable, complete word processor seemed light years away. But now I'm not so sure . . .

It will take quite some doing, of course, before any manufacturer can turn this dream into reality. A few obstacles still have to be overcome—an obvious one being the price of printers. But judging from how far we've come over the last two years—witness the rate at which home computers are being gobbled up by eager consumers—a new time frame is entirely possible: Technological breakthrough—fueled by typical mass-market production quantity—should result in an economy of scale that will drive component and assembly prices low enough to eventually reach the magic \$500 barrier. So what's the time frame? And who will achieve it first? I'm betting on Texas Instruments—and within 18 months!

Technology and manufacturing economy are, in fact, progressing so fast now that the old "rules" just don't apply anymore. There is no longer a clear-cut separation between low-cost "family computers" (of which the TI-99/4A is now clearly the industry leader) and the more expensive "business/professional machines" used mostly for word processing, spreadsheet, and database applications. Relatively inexpensive-yet-sophisticated software products such as Multiplan™, TI-Writer, and Personal Tax Plan, as well as TI's 99/4A Home Computer implementation of the p-System™ are examples of this convergence. The trend was very obvious at the Consumer Electronics Show (CES) in Las Vegas last month. There was a clear sign that hardware prices are plummeting, lower-cost peripherals are on


the way, and software is finally in abundance; for the first time, the consumer really has a choice in system configurations.

If 1982 was "The Year of the Home Computer," then 1983 will be "The Year of Software." The quantity of game software we saw and heard announced at the show was staggering. All I can say is, "Hold on tight to your joysticks—the arcade dam is about to break wide open . . ." Such well-known names as Walt Disney, 20th Century Fox, CBS, Thorn-EMI, Milton Bradley, and Parker Brothers will be producing software for game cartridges that will run on the TI-99/4A.

Starting with the March Issue, **99'er Home Computer Magazine** will begin regular coverage of the two new TI computers, the stackable line of compact peripherals, and the virtual flood of forthcoming software. The wealth of technical information and photographs that our team of editors obtained at the CES new-product debut (beyond what is revealed in this issue) will be presented in a series of articles over the next few months. This advance coverage will (we hope) prepare you for the time (in the first and second quarters, 1983) when the products actually appear on the shelves. And during the rest of the exciting year ahead, we will feature programs, useful applications, and tutorials on the new products. You can therefore expect to see a greatly expanded **99'er Home Computer Magazine**. And yes, as you have noticed, we did slightly change our name and logo. This new identity is necessitated by the increased product coverage, and makes our magazine's focus more easily recognizable on newsstands everywhere.

By the way, we're still looking for more technical writers, editors, and programmers to join our rapidly expanding operation here in Eugene, Oregon. If you've got the qualifications and are interested, please drop me a line.

99'er



LETTERS TO THE EDITOR

Dear Sir:

Happy to see you've gone monthly. Now I won't have to wait so long for my favorite magazine!

This letter is in response to one from Carol Bax from Lynnfield, MA in the November issue, who requested a program for putting a simple problem, as in her example "A+B=?", up into the middle of the screen.

Without having to resort to Extended BASIC or a long involved program in BASIC, I would like to submit this simple, eight-line program as a solution to the problem:

```
10 CALL CLEAR
20 INPUT "PROBLEM?":A$
30 CALL CLEAR
40 PRINT TAB(11);A$
50 FOR X=1 TO 10
60 PRINT
70 NEXT X
80 GOTO 20
```

Line 10 clears the program from the screen after the initial RUN.

Line 20 brings up the INPUT line and the cursor. In response, type in the problem and press ENTER.

The TAB in line 40 will move the copy to the approximate center of the screen, provided the copy is as short as her example.

The FOR-NEXT Loop in line 50, 60 and 70 tells the computer to print ten lines of nothing (blank lines), after the copy. This has the effect of scrolling the copy up to just about the center of the screen.

Line 80 puts the INPUT line back on the screen in preparation for the next problem while the first problem is still displayed.

You must use FCTN-4 (CLEAR) to exit the program.

Oops! I forgot line 30. This clears the old INPUT line and the typed-in copy from the screen, leaving only the problem, and the new INPUT line at the bottom of the screen.

I'm looking forward to the next issue of the 99'er!

Ted Whomsley
Anaheim, CA

Thanks, Ted, for a nice simple solution.

Dear Sir:

Why doesn't the new space game, Parsec, work on the 99/4 console? Why don't the advertisers who sell the module alert 99/4 owners of this shortcoming?

Javier Narvaez
State College, PA

Alas, Javier, Parsec will NOT work with the old TI-99/4 console because of an improvement in Video Display Processor (VDP) components. (The VDP type in the TI-99/4 was the TMS9918 while the TI-99/4A uses the new TMS9918A.) The horizontal scrolling of the planet's surface was programmed in the high-resolution graphics mode only found in the new VDP "chip." By the way just changing the VDP chip in the TI-99/4 will NOT make it compatible with Parsec because of special interrupt-driven capabilities of the 99/4A that were also used in the programming.

Dear Sir:

I just got the November 99'er. What can I say except "great." I've been starving for a monthly magazine worth a darn! I also enjoyed the joystick conversion routine by David Lewis, and the fix for Force 1. However there were a couple of things

missing. Line 1680 of the "fix" (pg. 7) should read: ON JZ GOTO 1730, 1690, 1730, 1700, 1730, 1710, 1730, 1720, 1730.

Also this necessitates changing Line 640 or the star-field won't move properly. Line 640 should read: IF JS=1 AND K=0 THEN 660 ELSE IF JS=0 AND S=0 THEN 660.

This passes control to 660 if there is no change in position of the gunsight and changes the star-field if there is.

All in all, not bad though!

Keep up the excellent work, guys.

Jim Lewis
Champaign, IL

Thanks, Jim, for showing us the error of our ways. We checked out your method and it works fine. Many readers sent in other corrections for this FORCE 1—joystick problem...

Dear Sir:

I am sending you a tape for the TI-99/4A computer. The first program is a drawing of "Papa Smurf" and the second program shows a ghost flying from a "Haunted House" to his grave. I would like to know how to add some sound effects and

Entering 99'er Programs

New readers should be aware that within the magazine's pages are found actual computer programs that you can put into your Home Computer and enjoy.

Make sure you have any special system components required by the program (i.e., the Speech Synthesizer, Extended BASIC cartridge, etc.). Then, using the console keyboard, you can type the printed magazine listing (character for character, and line by line) into the computer's memory.

Before entering the program, connect a cassette recorder to the computer. Make sure you have two blank cassette tapes. For each 10-20 lines you type in, use SAVE CS1 to save that program segment onto one of the tapes. Alternate between the two tapes each time you save the program. Be sure to rewind to the beginning of each tape before saving, so that you always record over and replace the shorter segment of program lines with the longer segment. By following this procedure, you'll always retain most of your work even if the lights go out or someone turns off the computer.

Double check your typing against the program listing for errors, and then have someone else check it. The most common errors are typing the letter "O" instead of the number "0" (zero)—they are not interchangeable to the computer. This is also true for the letters "I" and "L" and number "1" (one). (See "Key-In Reference" on p. 41)

Every time you make a correction to your program, SAVE CS1 and switch the tapes. Once all the errors are corrected, you will have a good copy of the program on the last tape. Before turning off the computer, put the other cassette tape in your recorder and once again SAVE CS1. Now, if one tape gets damaged, you won't have to enter the program listing via the keyboard all over again. Have fun and happy computing.

99'er


color. I have made several other drawing programs: Pac-man, Pink Panther, Woody Woodpecker, E.T., Bugs Bunny and others. I have also made up some games.

I am twelve years old and have had my computer since Christmas 1981. For my last birthday, I received Tunnels of Doom, Parsec and Extended BASIC. I am interested in trying the Adventure series.

I love getting the 99'er Magazine and have sent for back issues. I think it would be great to include some articles by kids who are using the computer and their problems with games and programming. I have made up eleven tapes of ideas myself. I would like to know what you think of my programs.

Mike Johnson
Schaumburg, IL

Well, Mike, you certainly understand TI BASIC statements CALL CHAR, CALL HCHAR, and CALL VCHAR very well. It must have taken a long time to figure out all the character definitions for the two line drawing programs you sent in! We used the Screen Dump for Mini-Memory (see November 99'er page 19) to print a copy of your Papa Smurf drawing on the TI-99/4 Impact Printer:



Now you can learn about sprites from your new Extended BASIC manual. Yes, we'd love to have articles from all our young 99'ers out there—especially with photos, showing you at your computers.

Dear Sir:

Your magazine is number one. I couldn't ask for a better written or more informative magazine. None of the other magazines hold a candle to the level of interest your 99'er produces in me. Please continue the excellent work. (When your billing dept. informs me of "Renewal Time," you can bet I will.)

Do you project either TI or some third party making up a card for the TI-Box that will allow use of the many APPLE programs?

Fred Deissinger
Jacksonville, NC

Fred, we are not aware of any BASIC language conversion cards for the TI-Box being available or even in the planning stages. By the way, you don't have to wait for our billing department to send a renewal notice to renew...


Dear Sir:

I would like to express that your magazine is absolutely the very best thing that has happened to TI-99/4A users. I am delighted that you are going on a monthly schedule. I also applaud your decision to go to larger print for the programs listed in the games section.

Doyle W. Davis
Lubbock, TX

I am glad you like the larger print for the programs, Doyle. It is always a hard decision to balance

Continued on p. 21



TI's Home Computer. Steve Jobs never gave you this much for your money.

We think the Apple™ is a good computer. But, for less than 1/3 the price* you can get a TI-99/4A Home Computer with this generation's microprocessor (the 16-bit 9900 family), built-in TI BASIC, 16-color capability, 5 octaves of music, 3-part harmony, numerous sound effects, and the ability to plug in RAM-saving Solid State Software™ ROM cartridges.

Plug-in ROM. Think about that for a minute.

*Based on manufacturers' suggested retail price for consoles.
**With Terminal Emulator II Cartridge.
†UCSD Pascal and UCSD p-System are trademarks of the Regents of the University of California.
Apple is a registered trademark of Apple Computer, Inc.

Since the operating system is also in ROM it means that the TI-99/4A's 16K RAM is fully usable. And, when you expand RAM to 52K, it too is fully usable.

With our Peripheral Expansion System you can plug in Memory Expansion, plus an RS-232 interface (with 2 serial and 1 parallel port), and a Disk Controller that runs three of our single-sided drives (or other peoples' double-sided drives). You can even add the UCSD p-System† by plugging in a p-Code Card.

We also have joysticks for games, a Speech Synthesizer with an unlimited

vocabulary**, phone coupler for data access, and a high quality 10-inch color monitor.

Now that's a lot of high-powered, sophisticated computer for the money. That's why, when you decide on a computer for the family, we just don't think you'll pick an Apple.

Creating useful products
and services for you.



TEXAS INSTRUMENTS

Copyright ©1981 Texas Instruments

Think of it—

This 4-MINUTE QUESTIONNAIRE CAN ACTUALLY IMPACT THE HOME COMPUTER REVOLUTION!!!

The 99'er Questionnaire

FOR ALL READERS


1. Are you presently a subscriber? ☐ Yes ☐ No
2. If not, do you intend to become one within the next 3 months? ☐ Yes ☐ No
3. If not a subscriber, where did you get your copy? ☐ Newsstand ☐ Supermarket ☐ Bookstore ☐ Airport ☐ Users group ☐ Computer store ☐ Chain/department store ☐ Borrowed from friend ☐ Other place
4. What category of articles do you enjoy the most? ☐ BASIC programming tutorials ☐ System tutorials ☐ Photo features & news items ☐ Game programs ☐ Education programs ☐ Utility programs ☐ Product reviews ☐ LOGO articles
5. How much total time do you spend with each issue? ☐ Less than 2 hours ☐ 2-4 hours ☐ 5-7 hours ☐ 8-10 hours ☐ 11-13 hours ☐ over 14 hours
6. How many other computer-related magazines do you currently read? ☐ None ☐ 1 ☐ 2-4 ☐ 5 or more
7. Are you ☐ Male ☐ Female ☐ Under 16 years of age ☐ 16-20 ☐ 21-25 ☐ 26-30 ☐ 31-35 ☐ 36-40 ☐ 41-50 ☐ over 50
8. Are you a student? ☐ Yes ☐ No
9. What is your annual household income? ☐ Under \$5000 ☐ \$5000-\$9999 ☐ \$10,000-\$14,999 ☐ \$15,000-\$19,999 ☐ \$20,000-\$24,999 ☐ \$25,000-\$30,000 ☐ over \$30,000
10. What is your ZIP code?

FOR READERS WHO DON'T YET HAVE A TI COMPUTER

1. Do you intend to buy a TI computer? ☐ No ☐ Yes (within 3 months) ☐ Yes (within 3-6 months) ☐ Yes (within 6-12 months)
2. Which do you think you'll purchase? ☐ TI-99/4A Home Computer ☐ TI-99/2 Basic Computer ☐ Compact Computer 40
3. What do you anticipate your primary use of a TI computer will be? ☐ Entertainment ☐ Education ☐ Computer literacy ☐ Household management ☐ Job-related homework ☐ Business ☐ Professional use

FOR PRESENT TEXAS INSTRUMENTS COMPUTER USERS

1. Which system(s) do you currently own? ☐ 99/4 ☐ 99/4A ☐ 99/2 ☐ CC-40
2. What was your primary reason for buying it? ☐ Entertainment ☐ Education ☐ Computer literacy ☐ Household management ☐ Job-related homework ☐ Business ☐ Professional use
3. What was your primary reason for buying the Texas Instruments brand? ☐ Company name/reputation ☐ Features for the money ☐ 16-bit microprocessor ☐ Convinced by friends/relatives ☐ Ease of use ☐ Prior use in course or "Advantage Club"
4. Which additional TI computer are you likely to purchase within the next 6 months? ☐ None ☐ 99/4A ☐ 99/2 ☐ CC-40
5. What peripherals do you currently use? ☐ Cassette recorder ☐ Disk controller & drive(s) ☐ Peripheral Expansion Box ☐ RS232 ☐ 32K Memory Expansion ☐ TV ☐ B/W monitor ☐ Color Monitor ☐ Speech Synthesizer ☐ Joysticks ☐ Printer ☐ Modem ☐ p-Code Card ☐ Hex-bus Adapter ☐ Wafertape Drive
6. Put a CIRCLE around the above peripheral you are most likely to buy within the next 6 months.
7. Mark all TI language software you own or plan to buy within 6 months. ☐ Extended BASIC ☐ 99/4A Editor/Assembler ☐ UCSD Pascal ☐ LOGO ☐ Forth ☐ Mini Memory ☐ Pilot ☐ CC-40 Editor/Assembler
8. How much money do you expect to spend within the next 12 months on your computer system?
 Software..... ☐ None ☐ less than \$30 ☐ \$30-50 ☐ \$51-100 ☐ \$101-250 ☐ over \$250
 Peripherals..... ☐ None ☐ less than \$50 ☐ \$50-100 ☐ \$101-250 ☐ \$251-500 ☐ over \$500
 Books..... ☐ None ☐ less than \$10 ☐ \$10-25 ☐ \$26-50 ☐ over \$50
 Blank tapes & disks..... ☐ None ☐ less than \$15 ☐ \$15-35 ☐ \$36-75 ☐ over \$75
 Furniture, dust covers, & accessories... ☐ None ☐ less than \$25 ☐ \$25-100 ☐ over \$100
9. How many software CARTRIDGES do you expect to purchase within the next 12 months?
☐ None ☐ 1-3 ☐ 4-7 ☐ 8-12 ☐ over 12
10. What % of the above CARTRIDGES will be for entertainment? ☐ 0% ☐ less than 25% ☐ 25-50% ☐ 51-75% ☐ 76-100%
11. Circle above what % of the CARTRIDGES will be for education.
12. Have you purchased from any of our advertisers in the magazine within the last 6 months?
☐ No ☐ Yes, Software ☐ Yes, Peripherals ☐ Yes, Books ☐ Yes, Blank tapes & disks ☐ Yes, Furniture, dust covers & accessories
13. About how much money have you spent on the above purchases?
☐ less than \$25 ☐ \$25-50 ☐ \$51-100 ☐ \$101-250 ☐ \$251-500 ☐ \$501-1000 ☐ over \$1000
14. On the average, about how many program listings in each issue do you key into your computer and use? ☐ None ☐ 1 ☐ 2 or 3 ☐ 4 or more



B.A.R.C.* BACK

*(Best Article—Reader's Choice)

Let us know what you like by voting
for your favorite article or program in this issue.
The winning author will receive
a bonus of \$100.00


Page	Article	Author
<input type="checkbox"/> 9	Who Needs a Printer?!	Ehninger
<input type="checkbox"/> 11	Printers on Review	Balthrop
<input type="checkbox"/> 22	Tower of Hanoi	Holl
<input type="checkbox"/> 25	Joys of Adventuring	Pincus
<input type="checkbox"/> 30	Lifeline to Titan	Bill Bies

Page	Article	Author
<input type="checkbox"/> 30	Night Blockade	Reigo
<input type="checkbox"/> 27	Chuck-A-Luck	Pincus
<input type="checkbox"/> 47	Vectors in LOGO	Richard Bies
<input type="checkbox"/> 49	Daisies	Kirchner
<input type="checkbox"/> 56	ASPIC	Berner and Martin

THANK YOU

Detach, fold and mail. See other side for instructions.

PLEASE HELP



Who Needs A Printer?!

By Charles M. Ehninger

408 Flaxseed Lane
Forth Worth, TX 76108

The latest printers have a wide range of features and capabilities and they offer you innumerable benefits. For example:

- Program listings and data reports are easier to read on paper than on display screens.
- "Hard copy" protects you against data losses caused by equipment failure or power outages.
- Payroll checks and mailing labels can be printed straight from your computer list.

If you still need convincing, consider this: Why are your eyes bloodshot, and your cuffs and shirttails scribbled upon with program line numbers, page references, file names, and other details?

Now—Who needs a printer?

The *printed* word is a tangible and dependable medium for information. Once information is down on paper, you can do a great deal with it: analyze it and make corrections, communicate with another person, or file it away—knowing it will be there when you need it, next week or next year.

Printed information also has character. You can feel its texture and weight. Whether it be newsprint, computer printout, or slick magazine stock, the paper itself contributes to the impression conveyed.

Finally the *printed* word has authority. Ideas, agreements, calculations, and descriptions become *documents* when printed. *Printed* words will not rearrange themselves, change meaning, or dissolve into gibberish. This cannot be said for oral communication (nor for some computer programs).

Adding a printer to your Home Computer system provides you with the benefits of the *printed* word. Information is transformed from bytes and pieces into a tangible document you can scrawl on, mail to friends, or rip into shreds. This article will focus on printers that are affordable, available, and intended for use with personal computers—the kind you will find at computer stores. We are not going to discuss printers that cost more than \$1000, build-it-yourself printers, laser printers, or ink-jet printers. Some of those excluded may be interesting to read about, but we must be practical.

That leaves us with two types of printers: (1) dot-matrix impact, and (2) daisy-wheel.

Choosing a Printer

The differences between printers are significant—perhaps more so than the differences between computers. Software can mask discrepancies between computers, but not between printers. Think of it this way: In selecting a printer, you are choosing a set of limitations. Sound negative? Well, nobody yet has invented the universal, all-purpose, unlimited printer—and if someone does, who'll be able to afford it? So choose your limitations carefully.

What is important to you? Decide on your top priority first.

- quality of printing type
- printer speed
- cost
- special capabilities such as graphics or plotting

There is a definite trade-off between speed and quality of printing. Rather than compromise, some manufacturers offer two modes in a single printer: one creates well-defined characters

but is relatively slow; the other is much faster, but less readable and appealing.

If you plan to use your printer for word processing—business letters, reports, manuscripts, newsletters, and other reading matter—quality of printing should be a top priority.

For data processing—lengthy accounting documents, inventories, program listings, and other high-volume material—you should get the fastest printer you can afford. A slow one can turn out to be a "printer's devil," tying up your computer and keeping you from your work.

For your personal record keeping, program development, and informal word processing, cost will probably be the primary factor.


When looking at printers, ask two questions:

1. Does it print dot-matrix or fully-formed characters?
2. Does it use plain or special paper?


What's a Dot Matrix

Dot-matrix characters are made up of dots. The amount of detail in each character is limited by the density of its matrix. (See Figure 1, below, for further explanation.)


Figure 1



5 by 7



5 by 8



9 by 9

A dot matrix is a pattern of dot positions. For example, a sheet of graph paper can be considered a very dense dot matrix. Dense means there are a lot of dot positions on it, allowing a great deal of detail in each character. The most common dot matrix is 5 by 7. That's 5 columns, each containing seven dot positions. Figure 1 above compares the letter "A" at three different dot densities. (5 by 7, 5 by 8, 9 by 9)

Most plain-paper printers transfer characters onto the page by striking an ink ribbon against the paper. For this reason they are called *impact* printers. Special-paper printers use other means such as heat, electrical current, or chemical action.

Dot-matrix impact printers are the most versatile and popular group. Most recent models have several character styles and sizes, including high-density matrices of up to 9 by 9. Some can even plot points and create high-resolution graphics.

Generally, dot-matrix characters are not as easy, nor as pleasing to read as fully-formed characters. However, some recent units have a letter-quality mode in which the dots overlap to approximate fully-formed characters. Dot-matrix printers are fast, ranging from 50 to 180 characters per second (cps), and range in price from under \$400 to well over \$2000. With their wide range of prices and capabilities, dot-matrix printers can be considered for almost any data processing, word-processing, or home use.


Daisy-Wheeling

Daisy-wheel printers produce fully-formed characters as clear and crisp as those of typewriters. Fully-formed characters, con-

Continued on p. 16



Texas Instruments Home Computer



295.95
—100.00

195.95

Our low price
Rebate from Texas Instruments

What a deal!

WHY SHOULD I BUY A TI HOME COMPUTER?

- **So you can learn the basics of BASIC.**
That's the built-in programming language that the 994/A speaks. And the Home Computer comes with two books; one to teach you BASIC from the very beginning and the other a complete reference guide.
- **You like to doodle and draw.**
TI-994A has easy-to-program high resolution graphics and 16 colors.
- **You love to sing and you want to program your own accompaniment.**
The TI Home Computer has 5 octaves and 3 voices. (It has a noise generator, too.)
- **You want a computer but you don't want to buy a lot of extra equipment right now...**
16K RAM + 26K ROM = 42K memory in the starting unit and all you need is your own black and white or color TV.
- **...However, you do want the assurance of being able to add on later.**
TI offers a complete line of peripherals and accessories as well as a seemingly endless line of software.
- **You'd like your kids to stay home more often.**
With the fanciest arcade and adventure games in town they'll NEVER want to leave.
- **You're an efficient and well organized person who likes to keep records and receipts in order.**
Lucky you! TI is hot on Home Management programs.
- **You want to learn to type...to spell...to play bridge...to teach your child to read...to get faster and better in math...**
What an educational value the Home Computer is! TI puts out exceptional educational software and more is coming all the time.

TI SUPPORTS HOME COMPUTER

WHY SHOULD I BUY IT AT DHEIN'S?

Because Dhein's prices are LOW-EVERY-DAY PRICES.

DHEIN'S carries everything TI makes for the TI Home Computer. It's one stop shopping for the best 3rd party software on the market.

And fast, convenient service to boot.

At Dhein's there's no hidden extra charge for VISA or Master Card.

And there's only a \$2.98 shipping and handling charge for ANY size order ANYWHERE in the continental U.S.A.

Where but at Dhein's can you get a FREE Computer Bulletin that has TI-99/4A news as well as programs that you can type in yourself?

Where else can you get a completely descriptive price list?

Where else can you get such careful attention and such good advice as when you call us?

If you haven't already done so, send for your Bulletin TODAY. Free for 1983.

----- COUPON --- MAIL TODAY -----

FREE Subscription to the COMPUTER BULLETIN

Name _____

Street _____ State _____

City _____ Zip _____

TI supports their Home Computer.
Dhein's supports their customers.

Because, at Dhein's, WE LOVE YOU

HAPPY VALENTINE'S DAY

Only \$2.98 shipping & handling in Continental U.S. Any size order. No extra charge for VISA or Master Charge.

Iowa residents add 3% sales tax.

The best combination of Price, Service and Quality is TRUE VALUE.

More than just a name, it is our way of doing business.

DHEIN'S



(319) 236-3861


7 W. Airline Hwy.
Waterloo, IA 50701

PRINTERS

On Review

By W.K. Balthrop

99'er Magazine Staff



If we were to review all the printers on today's market, we would end up writing a massive book, and by the time we were done, it would need complete revision.

As a practical overview, we have selected five models whose combined features will give you a good idea of what is available in printers at this time.

If you are a newcomer to the realm of printers, I suggest reading *Who Needs a Printer?!* by Charles Ehninger on page 9 of this issue. It will help you understand many of the terms used in the following reviews.

Gemini-10

The Gemini-10 by Star Micronics is an 80 column dot-matrix printer, with bidirectional logic-seeking head positioning, and speeds of up to 100 characters per second. The standard model comes with a parallel interface, 2.3K buffer, and dot-graphics. An RS232 interface with 4K buffer, and RS232 cable are available as options. The standard unit's suggested retail price is \$499.00.


Special Features

The Gemini-10 has some features usually found only on more expensive printers. There are 9 type-styles available. Most printers of the Gemini-10 price range include *normal*, *condensed*, *enlarged*, *emphasized*, and sometimes *double strike* as the only available fonts. But the Gemini-10 comes with all of these plus *elite*, *italics*, *super-scripts*, and *sub-scripts*. There are also 64 special and foreign characters, and 32 block and line drawing characters. Optional is a 2K user-programmable ROM (Read Only Memory) for a special set of 96 *proportional* characters. The *proportional* characters are of varying widths, like those in this text. For example a small "f" takes up 5 horizontal dot positions, while the letter "W" takes up 15 dot positions.

The standard type-styles available on the Gemini-10 are as follows:

NORMAL FONT
CONDENSED FONT
COND. / ENLARG
UNDERLINE
ITALICS
10 CHARACTERS
12 CHARACTERS PER
17 CHARACTERS PER INCH
EMPHASIZED MOD
DOUBLE STRIKE
SUPERSCRIPT FONT TYPE
SUBSCRIPT FONT TYPE
DOUBLE WIDE FITCH

Gemini-10 Printer



The Gemini-10 measures 15.2" x 12.4" x 5.3", and weighs 15.4 pounds. Both friction-feed and tractor-feed are standard. In addition to its ability to use single sheets and fan fold paper, the printer comes with a holder for roll paper. Access to the interior

of the printer is simple. Only two screws hold the two outer housings together. The only reason for opening the printer is to access the miniature slide switch set for the optional RS232 interface. All other miniature switch settings are exposed at the back of the printer. This greatly reduces the chance of accidental breakage or electrical shock, should you forget to turn off the power.

In order to connect the Gemini-10 to the TI-99/4A computer, you will need to alter the RS232 cable connecting the printer to the TI RS232 interface card. The wires to pins 11 and 20 must be interchanged on one end, or the computer will keep writing to the Gemini-10 even after the buffer is full—leading to lost data.

Graphics

The Gemini-10 lets you create graphics in three ways. The first is with a set of line drawing and block characters residing in the printer's memory. There are also two dot-graphics modes. Normal density dot-graphics can print up to 480 dots horizontally on one line. In the double-density mode, up to 960 dots can be printed on a single line.

Documentation

Because the Gemini-10 was recently introduced, we were able to get only the preliminary manuals. However, if these are any indication of the final product, users will not be disappointed.

PrintMate™ 99

The PrintMate 99 from Micro Peripherals, Inc. is an 80-column bidirectional dot-matrix printer, capable of printing up to 100 characters per second. The suggested retail price for the unit is \$695.00. [Note: MPI also makes a larger model, the PrintMate 150, which offers a wider carriage, larger buffers, higher speed, and down-loadable customized fonts. The 4 versions of this printer have suggested retail prices beginning at \$995.00.]

Special Features

The PrintMate 99 comes with a low-speed RS232 interface that has a maximum transmission rate of 1200 bps. An optional RS232 with speeds up to 9600 bps is also available.

Both friction-feed and tractor-feed come as standard equipment. In addition, there are three ways to feed paper into the printer. Fanfold paper can come in from the back of the printer, or it can feed up from the bottom through a special desk top with a slot. Roll paper can be fed from the back with an optional roll-handling bar. Single sheets can be fed into the optional tray at the front of the printer.

On the front are three push buttons and two indicator lights. Pushing the button marked *Select* puts the printer *on-line*—ready to accept data from the computer. The *TOF set* button will set the present position of the paper as the top of form. The *paper advance* button serves two functions: Pressing it quickly advances the paper one line; holding it down advances the paper to the top of the next page. The two indicators let you know when the power is on and when the printer is in on-line mode.

You can gain access to the control board for setting up the printer options by removing four screws from the bottom hous-

Continued on p. 14

WICO **COMMAND** **CONTROL™**

For The Games T.I. People Play

***The Only
Arcade
Controls For
Home Computers.***

They may buy a T.I. for some very serious reasons, but you can bet they have more on their minds. Like space games ... and chase games ... and all the other games that people play.

When they do, they'll want the best controls. That means arcade quality ... quality that can only be delivered by the world's largest manufacturer of controls for the commercial arcade. WICO makes Command Control for nine different home games and computers ... including Texas Instruments. Stock yours today.



Scotch *MARKETING* INC

P.O. BOX 1636 SSS DEPT MLM
Springfield, MO. 65805

WICO is a registered trademark of Wico Corporation. © 1982 Wico Corporation.

HUGE ELEK-TEK DISCOUNTS ON TI-99/4A Home Computer System



TI-99/4A Keyboard \$300.00


TEXAS INSTRUMENTS
INCORPORATED

Model	Name	Less \$100.00 manufacturer's rebate from TI.	Mfr. Sugg. Ret.	Elek-Tek Price
CONSOLE	TI-99/4A Home Computer (incl. RF Modulator)		525.00	300.00
PERIPHERALS				
PHD 1200	Peripheral Expansion Box		249.95	180.00
PHD 1220	RS-232 Card		174.95	130.00
PHD 1240	Disk Controller Card (One Disk Manager module packed with each Disk Controller)		249.95	180.00
PHD 1250	Expansion System Disk Drive (Disk Drive Controller required)		399.95	285.00
PHD 1260	Memory Expansion Card (32K RAM)		299.95	180.00
PHD 1270	P-Code Card (32K RAM Memory Expansion required)		249.95	180.00
PHD 1500	Solid State Speech™ Synthesizer		149.95	110.00
PHD 1600	Telephone Coupler (Modem)		224.95	163.00
PHD 2300	TI 99 Column Impact Printer		750.00	500.00
PHD 2300	VCR Controller		399.95	290.00
PHD 2400	P-Code Peripheral		399.95	290.00
PHA 2100	R.F. Modulator (TV Adapter)		49.95	38.00
PHA 4100	10" Color Monitor		399.95	320.00
OPTIONAL ACCESSORIES				
PHD 1100	Wired Remote Controllers (Pair)		34.95	28.00
PHA 1950	Thermal Paper (2 Pack)		9.95	8.00
PHA 2000	Dual Cassette Cable		14.95	12.00
PHA 2010	Monitor Cable		19.95	15.00
PHA 2020	Audio Adapter (Headphone Jack)		19.95	15.00
PHA 2310	Panasonic VCR Controller Cables		99.95	85.00
PHA 2320	Sony Video Controller Cables		99.95	85.00
PHA 2330	Pioneer Video Controller Cables		99.95	85.00
APPLICATION PROGRAMS				
Home Management/Personal Finance				
PHM 3006	Command Modules			
PHM 3007	Home Financial Decisions		29.95	24.00
PHM 3012	Household Budget Management (Data storage system is required)		39.95	32.00
PHM 3013	Securities Analysis		54.95	44.00
PHM 3016	Personal Record Keeping (Data storage system is recommended)		49.95	40.00
PHM 3022	Tax/Investment Record Keeping (Disk system is recommended)		69.95	56.00
PHM 3024	Personal Real Estate (Data storage system is recommended)		69.95	56.00
PHM 3044	Personal Report Generator (Data storage system is recommended)		49.95	40.00
PHM 3111	TI Writer (32K Memory Expansion required)		99.95	75.00
PHM 3113	Microsoft™ Multiplan™ (32K Memory Expansion required)		99.95	75.00
PHD 5001	Diskette		69.95	56.00
PHD 5003	Mailing List		19.95	16.00
PHD 5021	Personal Financial Aids		19.95	16.00
PHD 5022	Checkbook Manager		19.95	16.00
PHD 5024	Business Aids Library—Finance Management (Extended BASIC Command Module is required)		39.95	32.00
PHD 5027	Business Aids Library—Inventory Management (Personal Record Keeping or Statistics Command Module is required)		69.95	56.00
PHD 5029	Business Aids Library—Invoice Management (Personal Record Keeping or Statistics Command Module is required)		69.95	56.00
PHD 5038	Business Aids Library—Lease/Purchase Decisions		39.95	32.00
PHD 5038	Cassette		69.95	56.00
PHT 6003	Personal Financial Aids		14.95	12.00
PHT 6038	Business Aids Library—Lease/Purchase Decisions		59.95	45.00
Educational/Personal Enrichment				
Texas Instruments Packages				
PHM 3002	Early Learning Fun		29.95	24.00
PHM 3003	Beginning Grammar		29.95	24.00
PHM 3004	Number Magic		19.95	16.00
PHM 3005	Video Graphs		19.95	16.00
PHM 3008	Video Chess		69.95	56.00
PHM 3010	Physical Fitness		29.95	24.00
PHM 3020	Music Maker (Data storage system is recommended)		39.95	32.00
PHM 3021	Weight Control and Nutrition (Data storage system is recommended)		59.95	48.00
PHM 3040	TI LOGO™ (Memory Expansion is required)		129.95	75.00
PHM 3064	Touch Typing Tutor™ (Available for TI-99/4A only)		39.95	32.00
PHM 3109	TI LOGO™ II (32K Memory Expansion is required)		29.95	24.00
Scott, Foreman Reading and Math Packages (Developed by Scott, Foreman)				
PHM 3015	Early Reading (Solid State Speech™ Synthesizer is required)		54.95	44.00
PHM 3043	Reading Fun (Solid State Speech™ Synthesizer is recommended)		54.95	44.00
PHV 3046	Reading On		54.95	44.00
PHV 3047	Reading Roundup		54.95	44.00
PHV 3048	Reading Rally		54.95	44.00
PHV 3082	Reading Flight		54.95	44.00
PHM 3027	Addition and Subtraction I (Solid State Speech™ Synthesizer is recommended)		39.95	32.00
PHM 3028	Addition and Subtraction II (Solid State Speech™ Synthesizer is recommended)		39.95	32.00
PHM 3029	Multiplication I (Solid State Speech™ Synthesizer is recommended)		39.95	32.00
PHM 3048	Division I (Solid State Speech™ Synthesizer is recommended)		39.95	32.00
Scholastic Packages (Developed by Scholastic, Inc.)				
PHM 3059	Scholastic Spelling—Level 3 (Solid State Speech™ Synthesizer is required)		59.95	48.00
PHM 3060	Scholastic Spelling—Level 4 (Solid State Speech™ Synthesizer is required)		59.95	48.00
PHM 3061	Scholastic Spelling—Level 5 (Solid State Speech™ Synthesizer is required)		59.95	48.00
PHV 3062	Scholastic Spelling—Level 6 (Solid State Speech™ Synthesizer is required)		59.95	48.00
Addison-Wesley Computer Math Games (Developed by Addison-Wesley Publishing Co.)				
PHM 3083	Computer Math Games I		39.95	32.00
PHV 3088	Computer Math Games VI		39.95	32.00
Milliken Home Math Series—K thru 6th grade (Developed by Milliken Publishing Co.)				
PHM 3090	Addition		39.95	32.00
PHM 3091	Subtraction		39.95	32.00
PHV 3092	Multiplication		39.95	32.00
PHM 3093	Division		39.95	32.00
PHM 3094	Integers		39.95	32.00
PHM 3095	Fractions		39.95	32.00
PHM 3096	Decimals		39.95	32.00
PHM 3097	Percents		39.95	32.00
Texas Instruments Packages				
PHD 5007	Teach Yourself BASIC		34.95	28.00
PHD 5009	Music Skills Trainer		24.95	20.00
PHD 5011	Computer Music Box		19.95	16.00
PHD 5014	Market Simulation		19.95	16.00
PHD 5019	Teach Yourself Extended BASIC (Extended BASIC Command Module is required)		24.95	20.00
PHD 5020	Music Maker Demonstration (Music Maker Command Module is required)		14.95	12.00
PHD 5023	Basketball Statistics (Extended BASIC Command Module is required)		24.95	20.00
PHD 5026	Bridge Bidding I		24.95	20.00
PHD 5030	Speak & Spell™ Program (Solid State Speech™ Synthesizer is required)		24.95	24.00
PHD 5031	Speak & Math™ Program (Solid State Speech™ Synthesizer and Terminal Emulator I are required)		24.95	24.00
PHD 5039	Bridge Bidding II		24.95	24.00
PHD 5041	Bridge Bidding III		24.95	24.00
PHD 5042	Speller Writer (Terminal Emulator II Command Module and Solid State Speech™ Synthesizer are required)		24.95	24.00
PHD 5067	Beginner's BASIC Tutor		24.95	24.00
MECC Packages (Developed by Minnesota Educational Computing Consortium)				
PHD 5078	Metric and Counting™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5079	Elementary Economics™		24.95	24.00
PHD 5080	Elementary Math and Science™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5081	Astronomy™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5082	Word Beginnings™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5083	Exploring™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5084	Math Practice™ (Extended BASIC Command Module is required)		24.95	24.00
PHD 5085	Science Facts™ (Extended BASIC Command Module is required)		24.95	24.00

Model	Name	Mfr. Sugg. Ret.	Elek-Tek Price
APPLICATION PROGRAMS CONTINUED			
Education/Personal Enrichment Continued			
PHD 5086	Natural Science™ (Extended BASIC Command Module is required)	29.95	24.00
PHD 5087	Social Science™ (Extended BASIC Command Module is required)	29.95	24.00
PHD 5088	Teacher's Tool Box™ (Extended BASIC Command Module and printer are required)	29.95	24.00
PHD 8007	Cassette	29.95	24.00
PHD 8009	Teach Yourself BASIC	24.95	20.00
PHD 8011	Music Skills Trainer	24.95	20.00
PHD 8018	Computer Music Box	14.95	12.00
PHD 8019	Market Simulation	14.95	12.00
PHD 8026	Teach Yourself Extended BASIC (Extended BASIC Command Module is required)	19.95	16.00
PHD 8031	Bridge Bidding I	24.95	20.00
PHD 8032	Speak & Math™ Program (Solid State Speech™ Synthesizer and Terminal Emulator II are required)	24.95	20.00
PHD 8039	Bridge Bidding II	24.95	20.00
PHD 8041	Bridge Bidding III	24.95	20.00
PHD 8042	Speller Writer (Terminal Emulator II Command Module and Solid State Speech™ Synthesizer are required)	24.95	20.00
PHD 8067	Beginner's BASIC Tutor	24.95	20.00
Entertainment			
Texas Instruments Packages			
PHM 3009	Football	29.95	24.00
PHM 3018	Video Games	29.95	24.00
PHM 3023	Hunt the Wumpus	24.95	20.00
PHM 3024	Indoor Soccer	28.95	24.00
PHM 3025	Mind Changers	24.95	20.00
PHM 3030	A Maze-Ing	24.95	20.00
PHM 3032	Tombstone City 21st Century	39.95	32.00
PHM 3053	TI Invaders	39.95	32.00
PHM 3054	Car Wars	39.95	32.00
PHM 3057	Munch Man	39.95	32.00
PHM 30420	Tunnels of Doom (2 Diskette Games Included)	59.95	45.00
PHM 30421	Tunnels of Doom (2 Cassette Games Included)	59.95	45.00
PHM 3036	Alpinist™	39.95	32.00
PHM 3110	Crisis™ Trial	39.95	32.00
PHM 3112	Parsec™	39.95	32.00
Milton Bradley Packages (Developed by Milton Bradley Company)			
PHM 3031	The Attack™	39.95	32.00
PHM 3032	Blastoff™	24.95	20.00
PHM 3033	Blackjack and Poker™	24.95	20.00
PHM 3034	Hustle™	24.95	20.00
PHM 3036	Zero Zap™	19.95	16.00
PHM 3037	Hangman™	19.95	16.00
PHM 3038	Connect Four™	19.95	16.00
PHM 3038	Yahzee™	19.95	16.00
Adventure International Packages (Developed by Scott Adams)			
PHM 30410	Adventure (Private Adventure Diskette Game Included)	49.95	40.00
PHM 30411	Adventure (Private Adventure Cassette Game Included)	49.95	40.00
Gabriel Industries Packages (Developed by Gabriel Industries)			
PHM 3067	Online™ (Developed by Gabriel Industries)	39.95	32.00
Texas Instruments Packages			
PHD 5002	TI Trek (with optional speech)	14.95	12.00
PHD 5010	Mystery Melody	14.95	12.00
PHD 5015	Oldies But Goodies™ Games I	19.95	16.00
PHD 5017	Oldies But Goodies™ Games II	24.95	20.00
PHD 5025	Saturday Night Bingo (Solid State Speech™ Synthesizer is required)	29.95	24.00
PHD 5037	Draw Poker (Extended BASIC Command Modules is required)	24.95	20.00
PHD 5057	Tombstone City 21st Century (32K Memory Expansion and Extended BASIC Command Module are required)	19.95	16.00
PHD 5058	TI Invaders (32K Memory Expansion and Either Extended BASIC or Editor/Assembler Command Module are required)	19.95	16.00
PHD 5060	Munch Man (32K Memory Expansion and Either Extended BASIC or Editor/Assembler Command Module are required)	19.95	16.00
Adventure International Adventure Series (Developed by Scott Adams) (PHM 30410 required)			
PHD 5046	AdventurLand	29.95	24.00
PHD 5047	Mission Impossible	29.95	24.00
PHD 5048	Voodoo Castle	29.95	24.00
PHD 5049	The Count	29.95	24.00
PHD 5050	Strange Odyssey	29.95	24.00
PHD 5051	Mystery Fun House	29.95	24.00
PHD 5052	Pyramid of Doom	29.95	24.00
PHD 5053	Ghost Town	29.95	24.00
PHD 5054	Savage Island I & II	39.95	32.00
PHD 5056	Golden Voyage	29.95	24.00
Texas Instruments Packages			
PHD 6010	Mystery Melody	9.95	9.00
PHD 6015	Oldies But Goodies™ Games I	14.95	12.00
PHD 6017	Oldies But Goodies™ Games II	19.95	16.00
PHD 6025	Saturday Night Bingo (Solid State Speech™ Synthesizer is required)	24.95	20.00
PHD 6037	Draw Poker	19.95	16.00
Adventure International Adventure Series (Developed by Scott Adams) (PHM 30410 required)			
PHD 6046	AdventurLand	29.95	24.00
PHD 6047	Mission Impossible	29.95	24.00
PHD 6048	Voodoo Castle	29.95	24.00
PHD 6049	The Count	29.95	24.00
PHD 6050	Strange Odyssey	29.95	24.00
PHD 6051	Mystery Fun House	29.95	24.00
PHD 6052	Pyramid of Doom	29.95	24.00
PHD 6053	Ghost Town	29.95	24.00
PHD 6054	Savage Island I & II	39.95	32.00
PHD 6056	Golden Voyage	29.95	24.00
OTHER APPLICATION PROGRAMS			
Command Modules			
PHM 3001	Demonstration	69.95	58.00
PHM 3011	Speech Editor (Solid State Speech™ Synthesizer is required)	44.95	36.00
PHM 3014	Statistics (Data storage system is recommended)	44.95	36.00
PHM 3026	Extended BASIC	89.95	75.00
PHM 3035	Terminal Emulator	49.95	40.00
PHM 3036	Editor/Assembler	99.95	80.00
PHV 3058	Mini-Memory (4K)	99.95	80.00
PHV 3045D	SMU Electrical Engineering Library: (2 Diskettes included)	149.95	120.00
PHM 3045T	SMU Electrical Engineering Library: (10 Cassettes included)	149.95	120.00
Diskette			
PHD 5004	Programming Aids I	14.95	12.00
PHD 5005	Programming Aids II	24.95	20.00
PHD 5006	Yah Routine Library	29.95	24.00
PHD 5008	Electrical Engineering Library	29.95	24.00
PHD 5012	Programming Aids III	19.95	16.00
PHD 5013	Graphing Package	19.95	16.00
PHD 5016	Structural Engineering Library	29.95	24.00
PHD 5044	AC Circuit Analysis	24.95	24.00
PHD 5063	UCSD PASCAL™ Compiler (32K Memory Expansion and P-Code required)	124.95	100.00
PHD 5064	UCSD PASCAL™ Compiler (32K Memory Expansion and P-Code required)	99.95	80.00
PHD 5065	UCSD P System™ Editor/Assembler (32K Memory Expansion and P-Code required)	74.95	60.00
PHD 5068	P-Code (Required)	70.95	60.00
PHD 5074	Course Designer Authoring Package (Extended BASIC required and Video Controller optional)	199.95	150.00
PHD 5075	Text-To-Speech™ (Lingua™) (Solid State Speech™ Synthesizer, 32K Memory Expansion and Extended BASIC Command Module are required)	24.95	24.00
Cassette			
PHD 6034	Programming Aids I	9.95	9.00
PHD 6036	Yah Routine Library	24.95	20.00
PHD 6038	Electrical Engineering Library	24.95	20.00
PHD 6013	Graphing Package	14.95	12.00
PHD 6016	Structural Engineering Library	24.95	20.00
PHD 6044	AC Circuit Analysis	24.95	20.00
SOFTWARE LIBRARIES			
PHL 7001	The Home Financial Manager	139.95	100.00
PHL 7002	The Family Experianer	59.95	65.00
PHL 7003	The Elementary Educator	99.95	75.00
PHL 7004	The Music Educator	64.95	50.00
PHL 7005	The Super Programmer	119.95	90.00
PHL 7006	The Speaking Math Teacher	119.95	90.00
PHL 7007	The Speaking Reading Teacher	109.95	85.00
PHL 7008	The Speaking Scholastic Spelling Teacher	219.95	160.00
PHL 7009	The 11 Grade Game Series	119.95	90.00
PHL 7010	The Milton Bradley Game Series	119.95	90.00
PHL 7011	The Computer Introductory Package	119.95	90.00


The TI Home Computer Desk

Organize your system as you expand it with
"The Home Computer Desk"



With Peripheral Expansion Box

These are complete work stations with laminated surfaces.
The desk assembles without tools in minutes.



With Separate Peripherals

Choose from these three convenient sizes:

- 32 Desk - 32W x 24D, top shelf 32W x 12D - \$220
- 40 Desk - 40W x 24D, top shelf 40W x 12D - \$240
- 48 Desk - 48W x 24D, top shelf 48W x 12D - \$260
- Choice of colors - Honey teak or Walnut, with black legs.

Note: All top shelves are 36" from floor, and the work surface height is 26½ inches from floor.

All prices subject to change without notice. F.O.B. Dallas, TX

HCS HARDIN'S COMPUTER SOLUTIONS INC.

P.O. BOX 634/ RICHARDSON, TX 75080
834 N. GLENVILLE/RICHARDSON, TX 75081

(214) 699-8998


Printers On Review... from p.11

ing. The upper housing then lifts off. Inside you will find two miniature slide switch sets. These switches can be used to set up the low-speed RS232 interface, the form length, line spacing to 6 or 8 per inch, and one of four character densities as the default at power up.

Five character types are available:

PrintMate 99™ Printer

NORMAL TYPE
132 COLUMN
96 COLUMN
80 COLUMN-SERII
ENLARGE
TYPE



If you plan to use the standard low-speed RS232 interface, you will need to change the cable which comes with the printer. On one end of the cable is a 25-pin connector which mates to your TI RS232 interface card in the TI Peripheral Expansion Box. On the other end is a 13-pin connector which you will need to change. The wire connected to pin 10 will have to be removed and placed on pin 4. This will allow the printer to talk back to the computer, telling it when it's O.K. to send information. You may find the arrangement of the connector slightly confusing. It has a *single* row of 13 pins and its mate in the printer has *two* rows of 13 pins. The manual did not specify which set of pins you were to place the cable connector on. After considerable research, I discovered that you place it on the right row of pins (as you are facing the front of the printer) with cable pin #1 at the back.

Graphics

The PrintMate 99 is capable of printing dot-graphics with six of the 9 wires in the print head. Once the graphics mode is set, the patterns are printed with ASCII codes 64 through 127. Four densities are available: 50 dots per inch (dpi); 60 dpi; 75 dpi; and 82.5 dpi.

Documentation

The PrintMate 99 comes with a 60-page reference manual (ours, however, still referred to the older MPI 88) and an abbreviated 6-page reference manual. The manuals are easy to read and informative, except in explaining the hook-up of the RS232 cable. On the back of the 60-page manual is a reference card explaining switch settings and control characters.

TI 99/4 Impact Printer

Texas Instruments recently came out with a low-cost dot-matrix printer for the TI-99/4A Home Computer. This printer is a modified version of Epson's MX-80, and most programs designed for the latter will work with the TI machine. The unit's suggested retail price is \$750.00.

Special Features


In text mode the TI printer is capable of printing 80 characters per second, bidirectionally with logic seeking. In the dot-graphics mode, printing is unidirectional.

The RS232 interface with 2K buffer, RS232 cable, and dot-graphics comes standard—ready to use.


The TI printer is capable of print densities of 5, 8.25, 10, and 16.5 characters per inch, depending on the style of type being used. There are five basic type-styles.

TI 99/4 Impact Printer


NORMAL FONT
CONDENSED FONT
COND. / ENLARG
ENLARGED
EMPHASIZED FON
DOUBLE STRIKE



Continued on p. 19



GEMINI— FOR PRINTER VALUE THAT'S OUT OF THIS WORLD



Over thirty years of down-to-earth experience as a precision parts manufacturer has enabled Star to produce the Gemini series of dot matrix printers—a stellar combination of printer quality, flexibility, and reliability. And for a list price of nearly 25% less than the best selling competitor.

The Gemini 10 has a 10" carriage and the Gemini 15 a 15½" carriage. Plus, the Gemini 15 has the added capability of a bottom paper feed. In both models, Gemini quality means a print speed of 100 cps, high-resolution bit image and block graphics, and extra fast forms feed.

Gemini's flexibility is embodied in its diverse specialized printing capabilities such as super/sub script, underlining, back-spacing, double strike mode and emphasized print mode. Another extraordinary standard

feature is a 2.3K buffer. An additional 4 K is optional. That's twice the memory of leading, comparable printers. And Gemini is compatible with most software packages that support the leading printers.

Gemini reliability is more than just a promise. It's as concrete as a 180 day warranty (90 days for ribbon and print head), a mean time between failure rate of 5 million lines, a print head life of over 100 million characters, and a 100% duty cycle that allows the Gemini to print continuously. Plus, prompt, nationwide service is readily available.

So if you're looking for an incredibly high-quality, low-cost printer that's out of this world, look to the manufacturer with its feet on the ground—Star and the Gemini 10, Gemini 15 dot matrix printers.

star
micronics • inc

MAKING A NAME FOR OURSELVES

1120 Empire Central Place, Suite 216, Dallas, TX 75247
For more information, please call Bob Hazzard, Vice President, at (214) 631-8560.

FUTURA

S O F T W A R E

The very best in a totally integrated accounting system for your TI99/4A*

Accounts Payable	\$149.95
Accounts Receivable	\$149.95
Billing	\$149.95
General Ledger	\$149.95
Inventory Management	\$149.95
Mailing List	\$ 99.95
Word Processing	\$149.95

Exclusive Update Service insures against obsolescence of your FUTURA Software.

*Disk-based requiring Extended Basic, 32K Memory Expansion, RS232 interfaced printer.

FEBRUARY FEATURES

Cassette programs in TI Basic at \$19.95 each.

'COPTER CAPERS = Avoid many obstacles as you rescue victims from a burning building and deliver them to the waiting ambulance.

DEATH STATION* = Excellent text — only adventure game challenges you to find fuel at a deserted space station so that you may continue your journey.

MARS MARAUDER = Good navigation skills required as you try landing on Mars.

Cassettes in Extended Basic at \$19.95 each.


COSMIC DRIFT = Earth's only space colony depends on you for supplies. Can you deliver?

GETCHA! = They're out to 'getcha' and only with skill and cunning can this unarmed merchant make the aliens destroy each other.

*Also available in Extended Basic.

ORDERING INFORMATION: Payment to accompany order. Add \$1.50 for postage. Allow 10 days for delivery.

Write for complete listing of more than 60 programs for the TI99/4A Computer.



Ehninger Associates, Inc.

P.O. Box 5581
Fort Worth, Texas 76108
817/246-6536

Who Needs A Printer?!... from p.9

sist of solid lines. (The print you are reading in this article is fully formed.) The daisy-wheel printer gets its name from the print element which looks like a daisy with type at the tips of its elongated petals. The wheel rotates at high speed and a hammer strikes the appropriate character as it passes by. The print wheels are easily removable and are available in several styles and sizes.

Daisy-wheel printers are slower than dot-matrix printers—with speeds ranging from 12 to 55 cps. They also are usually much more expensive—from \$1500 to \$2000 and up. (Smith-Corona's recent entry into the daisy-wheel market is a superb exception. So is the specially modified Olivetti PRAXIS typewriter.) For top quality word processing, you can't beat a daisy-wheel printer.

Is It Computer Compatible?

You are almost ready for that shopping trip, but first you need to know about a little thing called an *interface*.

Before your computer can begin communicating with a printer, the two units must be connected. That seems obvious, but there's a lot more to it than simply connecting a bunch of wires. There are matters of voltage levels, timing, and protocol (which device says "hello" first). All of these items are handled by the *interface*.

There are two major interface types for computer-printer communications: serial and parallel. The RS-232 card (TI PIP1220) for the TI-99/4A accommodates both. [If you use a serial port on the RS-232 card, the parallel interface will be open for future peripherals you may want to connect, but you'll have to make sure the printer you buy also has an RS 232 interface installed—often an option at extra expense.—Ed.] Be sure to buy a cable specifically designed for the interface you select.

Evaluating Printers

Okay. You are in the computer store. You have determined what kind of printer you are interested in—one you know is compatible with your TI-99/4A. How do you compare one printer with another? We shall list the features to look for and offer some suggestions on weighing one against another.

Printer Speed

Printer *speed* is given in characters per second (cps) or lines per minute (lpm). Most printers in the personal computer market specify cps. Printers that output an entire line at once (or appear to do so) use lpm.

One 8½-by-11-inch page of double-spaced text contains approximately 1800 characters. A 30 cps printer does a page in one minute, or 30 pages in half an hour. A 150 cps printer does a page in 12 seconds, or 30 pages in six minutes. (But remember, when you are waiting for a printout, *apparent time* seems like twice the actual time!)

After you have determined the speed, look for features that make the most of that speed—or in computer lingo, increase the printer's *throughput*. Bi-directional printing is one example. The printer outputs one line from left to right, the next from right to left, then left to right, and so forth. This minimizes the time the print-head must move without actually putting the character on the page.

Logic seeking is another wrinkle in the speed game. It means that a printer can go directly to the first actual print position or the next line—not starting at the extreme left or right margin. Put the last two features together and you have a bidirectional, logic-seeking printer. If that doesn't impress your friends, nothing will.

In normal text, there is a lot of white space—paragraph indents, tabulations, double-spacing, and spacing at the top and bottom of pages. Some printers can *logically sum* the number of characters that produce blank spaces. For example, using logically-summed spaces, a printer will do a paragraph indent in one continuous motion, rather than going one space at a time. Using logically-summed line feeds, a printer can skip six lines in a continuous motion, rather than in six separate line advances.

Character Styles

Until recently, affordable printers could produce only upper case characters, but the lower case is now available on most units. Many offer a standard set defined by 96 character codes called ASCII (American Standard Code for Information Interchange). An increasing number of dot-matrix printers offer graphics and special characters.

Individual character styles vary widely and are subject to your own taste. However, one detail deserves attention here—*lower case descenders*. Descenders are the tails on the letters g, j, p, q, and y. Normally, these drop below the baseline of the other letters. But in many lower-density, dot-matrix printers the descenders are not "true," i.e., the letter is raised so the descender rests on the baseline. If you find this annoying, look for a printer with true descenders.

You should also consider the *character sizes* available on the printer. Measured in characters per inch (cpi), standard sizes are 10 (pica), 12 (elite), and 16.5 or 16.7 (condensed). Pica type is standard for data processing and general purposes. Elite is often used in business letters and legal documents. Condensed is useful when you want to pack many characters onto each line, for example, when you need to print 132-column tables on 8-inch lines. Many dot-matrix printers also offer extended characters (5 cpi, 2.5 cpi), which are nice for headings.

Proportional spacing is a useful feature for word processing. The pica, elite and condensed characters are all *monospaced*, meaning each character takes up the same space. With proportional spacing, however, the space used by each character is proportional to its shape. For example, the "i" requires less space than the "m." The text you are now reading is proportionally spaced. This spacing allows more characters per line but does not appear condensed, and is easier on the eyes. For tables, columnated reports, and program listings, monospacing is preferable.

Control Codes

In addition to printing characters, many printers perform a variety of functions under computer control. The most common and useful of these *control codes* are:

- Backspace (allows overstriking for boldface and special effects)
- Tabs (positions are fixed or set by the computer)
- Form feed (automatically advances the paper to the beginning of the next form)
- Separate functions for line feed and carriage return (for special effects and timesaving)
- Bell or tone signal (the only way some systems can get your attention)

Paper

What size paper can a printer handle? How many characters will fit on one line of that paper? Printers are often rated in columns per line; this is the same thing as characters per line. Can the printer accept page after page without your assistance, or do you need to feed it one sheet at a time? Ask these questions when shopping for a printer.

If you are looking at impact printers, you'll have more choices in terms of paper size and handling. For word processing, an 8½-inch-wide paper is standard. It allows 80 characters per line at 10 cpi. If the printer has a condensed mode, you can get 132 characters onto one 8-inch line. For data processing in an office environment, some people prefer printers able to handle paper up to 15 inches wide.


Three methods of *paper feed* are available: friction feed (as on typewriters), pin feed, and tractor feed. With friction feed, the paper is in sheets or on a roll. With pin and tractor feed, the paper is continuous and fanfolded, with holes along each margin. Pin-feed systems have guide pins on the ends of the platen; tractor-feed mechanisms are external and often more reliable than pin feed. Some dot-matrix impact printers are equipped with both friction and tractor feed. Many friction-feed daisy-wheel units have optional tractor attachments.

One problem with friction feed is paper alignment. During long runs using rolls or other continuous paper, the paper tends to creep to the left or right. Also there may be some vertical slip-page. This may be acceptable in most personal computer applications, but not in repetitive-forms printing where margins are critical.

User Communication

One last question: Does the printer talk back to the computer? For example, if it is out of paper or ribbon, will the printer stop to inform the computer of the problem? And when you replenish the paper or ribbon, will the printer continue without losing a

Continued on p. 64



NOT POLYOPTICS


Twelve great games for the TI 99/4(A). Specifically designed to take full advantage of the graphics and sound capabilities of TI BASIC.

- (1) **Advance.** Combines the best features of popular board games and then adds the action and unpredictability of the arcade. **\$13.00**
- (2) **Ant Wars.** A war simulation based on the insect world. An optional spider adds a third party to reckon with. **\$18.00**
- (3) **Cars & Carcasses II.** Your city has been invaded by draculæ, frankensteins, and space monsters, and you must run them down. **\$10.00**
- (4) **Crosses.** Markers are alternately placed on a grid, and the center piece of a cross captures it. Chain reactions sweep the board. **\$10.00**
- (5) **Hordes.** The ultimate game of world domination. On a screen map of the world armies and navies vie for control. **\$18.00**
- (6) **Khe Sanh.** Command a military base in Viet Nam during the Tet Offensive. Search and destroy, defoliate jungles, defend convoys. **\$18.00**
- (7) **Maze of Ariel.** A maze game with a difference. Use lantern and grenades to negotiate a continuously changing, dragon-infested maze. **\$13.00**
- (8) **Sengoku Jidai.** War game based on the period of the Shogun. From your castle stronghold reach out to conquer a world. **\$18.00**
- (9) **Ships!** Take three men-of-war and sail them into battle. With weather changes complicating the action, you must broadside the enemy. **\$15.00**
- (10) **Starship Pegasus.** Contact extra-terrestrial intelligence as you explore and conquer the stars. Complete with name and descriptions of the alien life forms. But watch out for Hyper-D Marauders! **\$18.00**
- (11) **Tickworld.** Eight hungry giant ticks are after you. You must capture them and put them in cages. **\$13.00**
- (12) **Winging It.** Flight simulator for the TI 99/4(A). Once you've mastered flying, three different games test your skill. **\$15.00**

OK. These games are all keyboard actuated, and you need no peripherals other than a cassette recorder. Mention this ad and receive an additional 10% off the above prices.



13721 Lynn Street #15
Woodbridge, Virginia 22191
(703) 491-5543



NAME _____
ADDRESS _____


Please circle the numbers of the programs you're ordering:

1 2 3 4 5 6 7 8 9 10 11 12 Subtotal: _____
Virginia residents add 4% sales tax. Discount: _____
Handling and shipping is free. Orders shipped the day of receipt. Support planetary exploration. Total: _____


LOGIX

One of the largest full line distributors
of **Texas Instruments 99/4A Home Computer**
Hardware, Software, Peripherals and
other T.I. Products.

Attention: T.I. Dealers!
Consider LOGIX as your pri-
mary or back up source of T.I.
Home Computer Products.



TEXAS INSTRUMENTS
INCORPORATED



Inventorying
the vast T.I. line
can be expensive. We'll
be your "warehouse", and
at no additional cost to you as
compared to buying direct from T.I.

Call for information on availability and ordering. Please have resale Tax Number ready
when calling. Sorry. No retail sales—we sell wholesale only to qualified dealers.

LOGIX

A Division of RTA Corp.

PO Box 4107, 991 Broadway, Albany, New York 12204 Call (518) 463-3251 Between 9 AM-5 PM EST
Telex 710 441-8299 OR In The States of VT, RI, PA, NJ, NH, CT, DE, and MA Call (800) 833-3420 Toll Free

Printers On Review... from p.14

The TI printer measures 4.2" x 14.7" x 12", and weighs 12 pounds. Access to the interior is a simple matter of loosening the four screws holding together the upper and lower housings. Inside are miniature slide switches that let you select form length, line spacing, character type, and several other options to become the default when the printer is powered up. You can also select any one of eight international character sets, and set up the RS232 interface.

Graphics

The TI 99/4 Impact Printer is capable of printing dot-graphics interspersed with text on the same line. Two dot-graphic resolutions are available. Normal-resolution graphics can print up to 480 dots horizontally on one line. Double-resolution graphics can print up to 960 dots per line.

Documentation

The manual for the TI printer is concise and easy to read. As a bonus, TI has included a number of program examples showing how to use each feature of the printer. The novice programmer will find it a valuable tool, as it is designed specifically for use with the TI-99/4A computer.

Microline 83A

The Microline 83A, from Okidata Corp. is a high-quality, wide-carriage printer. Its 136-column bidirectional logic-seeking dot-matrix print head moves along with an impressive print speed of 120 characters per second (cps). The suggested retail price is \$899.00.

Special Features

The 83A comes standard with a low-speed serial RS232 interface capable of transmission rates to 1200 bits per second (bps). An optional high-speed RS232 interface can be purchased separately for \$120.00, increasing transmission speed to as high as 9600 bps. Friction-feed and tractor-feed both come standard. The friction-feed lets you insert individual sheets, (letterheads or envelopes) whereas the tractor-feed ensures the smooth flow of continuous fanfold paper. It is extremely easy to switch between the two.

The 83A printer measures 14.21" x 12.91" x 5.24" and weighs 32 pounds. On the front of the printer is the control panel. Most control panels include a "form-feed," "line-feed," and "on-line" switch, but the 83A takes it a step further. It has a rotary 10-position switch to set the form length and another switch to set the paper's present position as the "top of form." This feature saves you from having to power down the printer just to set the "top of form."

Two paper feed paths are available. In addition to the normal feed path—from the back, through the print mechanism, and out the back again—paper can be fed up through the bottom of the printer. Of course a special table or desk top is needed, with a slot in the top for the paper to pass through.

There are four type-styles available with the 83A, each of them software selectable. The printer will always power up with "normal" type. Print densities are 5, 8.3, 10 and 16.5 characters per inch, depending on the type-style used. The 83A will print the following type-styles:

Microline 83A

NORMAL FON
CONDENSED FONT
ENLAR
COND. /
ENLARGED



Access to the control card is easily gained. First remove the tractor-feed system (about a ten-second operation). Under the top cover you will find two Phillips-head screws holding the upper housing to the lower housing. Once these are removed, the upper housing will lift off. You can then get to the two sets of miniature slide switches needed to set up the printer. The first is in the front, on the control panel. Use this one to set up any one of nine international character sets, plus a TRS-80 character set. The other set of switches, in the back of the printer on the control card, will let you set up the RS232 parameters.

Continued on p. 64

Utilities I

THIS is the one!

REPUBLIC SOFTWARE presents four valuable utility programs for the Texas Instruments Personal Computer—all at one low price. Whether you are a novice or an experienced programmer, this is the one you need to give your programs that professional touch.

UTILITIES I includes:

1. a disassembler that executes in Extended BASIC or in console BASIC if the Mini-Memory or Editor/Assembler is plugged in.
2. point-plotting routines that provide high-resolution plotting capability in console BASIC, Extended BASIC, and Assembly Language.
3. screen dump routines written in console BASIC, Extended BASIC, and Assembly Language for the TI 80 column printer and Epson printers with Grafrax or Grafrax +.
4. a speech utility to allow the speech synthesizer to speak any word in an Extended BASIC program—without having TI's Terminal Emulator II or Text-to-Speech programs.

All versions of each of these utilities are included on every UTILITIES I disk or cassette tape.

UTILITIES I is a quality product from **REPUBLIC SOFTWARE**—the folks who brought you **RING DESTROYER**.

See your Dealer or order direct from **REPUBLIC SOFTWARE**. **UTILITIES I** and **RING DESTROYER** are each available @ \$19.95. Please specify disk or cassette. All orders postpaid.

Phone (202) 978-3554 to place your order and we will reduce the price of your order by \$2.00 to pay for your call. VISA and Mastercard welcome.

Dealer inquiries invited.

REPUBLIC SOFTWARE

Republic Software, Inc.

P.O. Box 23042

L'Enfant Plaza

Washington, DC 20024



Unlimited Horizons Await You



Scotch MARKETING offers a multi-level marketing plan for computer software and related products for an ever-expanding selection of computers.

Now featuring FUTURA, SOFTECH, AGRITECH, MICRO-ED SOFTWARE, SCOTCHWRITER PRINTERS, WICO COMMAND CONTROL JOYSTICKS AND 3M PRODUCTS plus more.

- ★ Six categories of DEALERS
- ★ Six levels of PERSONAL bonus volume
- ★ Monthly, quarterly and yearly bonuses
- ★ No investment
- ★ No inventory
- ★ No bookkeeping
- ★ No servicing
- ★ No pickup or delivery
- ★ Monthly sales promotions
- ★ Vacation and leave of absence provisions.

Scotch MARKETING was publicly announced at TI FEST in San Francisco on October 22nd-25th, 1982. This **IS** the ground floor opportunity for you to participate in a newly formed, much sought after multi-level marketing corporation.

Tomorrow's Opportunity Today

SALES KIT (optional) \$16.95 (*Shipping included*)

To become an integral part of **the clan with a plan** contact your local authorized Scotch dealer or write



Scotch *MARKETING* INC

P.O. Box 1636 SSS DEPT MLM
Springfield, MO 65805

BeeJay FUNWARE

BLACKJACK - One or two players against the house. Follows all Vegas rules. Excellent graphics. Multiple decks. We know you will like this one!

BLACKJACK II(*) - Play blackjack with a friend - on the telephone! We are first with remote games for the 99/4A

CALENDAR - On what day of the week will your birthday fall in 2001? In 1,000,000? This program explains our gregorian calendar system and will draw a calendar for any month of any year, even BC! It highlights the holidays and you can add your own special dates - permanently! Another BJT original!

MINIGOLF - 18 holes of miniature golf for 1 or 2 players. 64 different greens. No 2 consecutive holes or games are the same. Challenging and fun!

MINIGOLF II(*) - Play golf with a friend - on the telephone! A fine use for your comm gear!

XORKLE - A six-dice game for up to 6 players. A unique challenge to your daring and judgment! Can you throw a triple? If you XORKLE you've blown your turn! A BeeJay Funware original.

XORKLE II(*) - Play XORKLE on 2 home computers over the phone! Up to three players at each location.

(*) requires RS232 interface, modem & a fellow 99'er similarly equipped. Each player must have a copy of the program (order two). All programs require Extended Basic. Multiple programs furnished on same tape or disk.

***** Prices *****
1 PROGRAM...\$12.95 2 PROGRAMS...\$16.95
4 PROGRAMS \$21.95 PLEASE ADD \$1.50 SHIPPING
Colorado residents please add 6.5% sales tax.

BeeJay FUNWARE

983 S. Ouray St.
Aurora, CO 80017 303-695-6213
SATISFACTION GUARANTEED

TEXAS INSTRUMENTS HOME COMPUTER

Retail price \$495. Your special BACH Company price is a low \$299.95. Less TI \$100 REBATE - \$199.95! Order today TOLL FREE 800-227-8292. In California call 415-969-6600.

TI Home Computer	299.95
Peripheral Expansion System	182.95
RS-232 Card	134.95
Disk Controller Card	192.95
Expansion System Disk Drive	297.95
Maxell MD1 Single Side 5-1/4" Floppy Disk (10) ..	29.10
Memory Expansion Card	228.95
P-Code Card	189.95
Pascal Development System	370.50
Solid State Speech Synthesizer	108.95
Telephone Coupler	158.95
TI-Impact Printer	559.00
10" Color Monitor	319.95

**TOLL FREE
800-227-8292**

**CALL FOR
FREE TI
SOFTWARE
LIST!**



The BACH Company
715 ENSIGN WAY, PALO ALTO, CA 94303

Letters . . . from p. 7

the amount of editorial content, in each issue, against the ease of reading the content.

Dear Sir:

I am totally impressed with your magazine! It not only enhances the TI-99/4A's fantastic capabilities, but it reconfirms what a smart decision I made to purchase this relatively unknown machine.

There is a software program that I cannot find anywhere and maybe you or your readers can assist me. It is a political software program. With all the political groups in America. I am amazed there is not one program available for individual candidates, county chairman, or state committees. There must be a huge market just waiting to be tapped.

Again, congratulations on such a balanced magazine. Texas Instruments 99/4A continues to achieve creditability and grow in demand in part because of your publication.

Robert W. Geddis
Hagaman, NY

Thanks, Bob, for the compliment. Maybe a reader out there in 99'er Land can tell us if such a program exists . . .

Dear Sir:

I have owned a TI-99/4A for well over a year, and I have been following the development of this computer since its inception. I have found that 99'er Magazine is by far the most informative reading of any of the computer magazines. I have devoured each issue, beginning on the way back from the mailbox. I am overjoyed to see that you have finally gone to a monthly publishing schedule.

When I originally typed in the FORCE 1 program, I made provisions for the use of joysticks, but the suggestion by David Lewis in your November issue looked so intriguing that I added your suggested changes to the program. Unfortunately, the addition will not work as published.

A problem exists that will allow no motion at all. Line 640 does not allow movement if the key status

is zero. The joystick routine does not return this value, so S remains set to zero. To solve this problem, change lines 1690, 1700, 1710, 1720 and 1730 as follows:

```
1690 K=88 : S=1 : RETURN
1700 K=83 : S=1 : RETURN
1710 K=68 : S=1 : RETURN
1720 K=69 : S=1 : RETURN
1730 K=0 : S=0 : RETURN
```

Besides these, there are errors on line number 1680. The ON JZ GOTO . . . statement has its last two arguments reversed. This results in no northward sensing. This statement also lacks an eighth value. This will cause an error if the joystick is moved to the northeast position. To correct both of these problems, re-enter line 1680 as follows:

```
1680 ON JZ GOTO 1730, 1690, 1730, 1700,
1730, 1710, 1730, 1720, 1730
```

After these changes, the FORCE 1 program will operate properly with joysticks as well as the arrow keys.


With the recent boom in TI sales, my dream of organizing a local user's group has materialized. We have named the group, appropriately enough, "The Daytona 99'ers." Each of our last two meetings have drawn about fifty people. If we keep getting this amount of new people every month, there is a great potential here. I would appreciate it if any TI users in the Daytona Beach, Florida area would contact us.

I have many ideas for articles for 99'er Magazine, and I would like you to send me Author's Guidelines. Once again . . . Keep Up The Good Work.

Ralph W. Fowler, III
The Daytona 99'ers
P.O. Box 4596
S. Daytona, FL 32019

Ralph. Thanks for your corrections. Good luck to all The Daytona 99'ers and we look forward to any articles you care to submit.

COMPUTER CASSETTES 100% ERROR-FREE



LENGTH	12 PACK	24 PACK
C-05	79¢	59¢
C-10	89¢	69¢
C-20	99¢	89¢

- Fully Guaranteed!
- World's Finest Media.
- Custom Storage Case, Add 26¢ Each.
- UPS Shipping, \$3.00 per pack

For Orders Only
1-800-528-6050
Ext. 3005

MICRO-80™ INC.
2665-T BUSBY ROAD
OAK HARBOR, WA 98277

Professor Holl's Pocket Programs

... and problems in programming

You are in an ancient temple at the center of the earth where three diamond needles bear eighty golden rings of graduated sizes. At the beginning of time the rings were all on one needle; but now the temple monks are transferring the rings, one at a time, from needle to needle, never setting a ring on a smaller ring. When they have moved all eighty rings to one of the other two needles, the world will end...

Possibly you have seen a children's toy along these lines—four or five disks of various colors and sizes, drilled to fit on three wooden pegs. The object is to start with the disks on one peg, and by moving one at a time—and never setting a disk on a smaller one—transfer the entire pile to another peg. If you don't have one of these in your closet, here is a pocket program of the puzzle for you and your friends.


When the program is run, four "rings" (they will actually look more like short bars) will appear on the left of the screen. There is room on the screen for three piles of rings. (To make the game pocket-sized, the pegs were left out.) To move a ring from one pile to another, press key 1, 2, or 3 to designate which pile (left, center, or right) to take the ring from, and then press 1, 2, or 3 to designate which pile to move the ring to. That's all there is to it.

The program works this way: rings are represented by the numerals 1, 3, 5, and 7. Peg (1), Peg (2), and Peg (3) are variables in which the presence of rings on the three pegs (or piles) are recorded. Thus in line 200, which is part of the initial setup portion of the program, Peg (1) is given the value 1.357 corresponding to the presence of all four rings on the first peg. The left-most numeral is the one on top.

At the beginning, pegs #2 and #3 are empty. When a ring is moved from one peg to another, the values of the "peg()" variables change accordingly. For example, if our first move is to place the top ring from peg #1 onto peg #2, then Peg (1) changes from 1.357 to 3.57 and Peg (2) changes from 0 to 1.

These changes are performed in line 450 (where the "size" of the ring being moved is figured out) and in lines 500 and 510 where the values of the "peg()"s are actually changed. "From" and "too" identify the pegs. They are given values when the keys 1, 2, or 3 are pressed. The three "top()" variables are strictly for the graphic display; they record the positions of the tops of the piles on the screen. Conveniently, the rings are 1, 3, 5, and 7 characters wide.

"Status" is used as part of the "call key" routine to tell the machine when a key has been released so that the program can go ahead. Now read through the program and see if you can follow what is happening.



Stacks

The piles of rings in this program are particularly graphic illustrations of the *stack*, a ubiquitous and very important idea in practically every kind of software. Like the rings in these piles, things stored on *software stacks* (subroutine return addresses, interrupts, whatever...) come off the stacks in reverse order to the way they went on. Because the items stored on our pegs are only single numerals, we are able to use a simple "trick"¹ to represent each of our three stacks. We just construct a number for each digit we want to represent. The TI-99/4 and 99/4A employ numbers accurate to 13 decimal places using a radix-100 representation, so we can push and pop numerals onto and off the left end of these with abandon, multiplying and dividing by 10 without fear of roundoff error.

Homework

Now that you understand how the program works, it's time to personalize it to make it *your* program. Here are some suggestions: Teach the machine to count the moves, recognize an end condition, and tell how many moves it took to get there. Add the pegs and color the rings. Expand the game to five rings.

Finally, if you make some estimates of how fast the monks are moving each golden ring, you can determine how much time the world has left. (You will need to know the fastest way to shift the rings.) If the holy men went modern and taught their TI-99/4 to move a ring every micro-second, would you be ready to sell your long term bonds at a discount?

¹If you find an application for this "trick" in a program of your own, you will be entitled to call it a "method." (A "method" is a trick used twice).

By S.T. Holl

Qtrs 327A, Yerba Buena Island
San Francisco, CA 94130

```

100 REM *****
110 REM * TOWER OF HANOI *
120 REM *****
130 REM 99'er VERSION 2.4.1
140 REM BY S. T. HOLL
150 REM
160 REM
170 DIM PEG(3),TOP(3)
180 CALL COLOR(7,1,1)
190 CALL COLOR(8,2,2)
200 PEG(1)=1.357
210 PEG(2)=0
220 PEG(3)=0
230 TOP(1)=10
240 TOP(2)=14
250 TOP(3)=14
260 CALL CLEAR
270 CALL HCHAR(10,6,88,1)
280 CALL HCHAR(11,5,88,3)
290 CALL HCHAR(12,4,88,5)
300 CALL HCHAR(13,3,88,7)
310 CALL KEY(3,FROM,STATUS)
320 IF STATUS=0 THEN 310
330 CALL KEY(3,DUMMY,STATUS)
340 IF STATUS=-1 THEN 330
350 FROM=FROM-48
360 CALL SOUND(100,110,3)
370 CALL KEY(3,TOO,STATUS)
380 IF STATUS=0 THEN 370
390 CALL KEY(3,DUMMY,STATUS)
400 IF STATUS=-1 THEN 390
410 TOO=TOO-48
420 CALL SOUND(100,262,2)
430 IF (FROM<1)+(FROM>3)+(TOO>3)+(TOO<1) THEN 310
440 IF (PEG(FROM)=0)+((PEG(TOO)<>0)*
  *(PEG(FROM)>PEG(TOO))) THEN 310
450 SIZE=INT(PEG(FROM))
460 TOP(TOO)=TOP(TOO)-1
470 CALL HCHAR(TOP(FROM),3+(FROM-1)*
  9+.5*(7-SIZE),87,SIZE)
480 TOP(FROM)=TOP(FROM)+1
490 CALL HCHAR(TOP(TOO),3+(TOO-1)*
  9+.5*(7-SIZE),88,SIZE)
500 PEG(FROM)=10*(PEG(FROM)-SIZE)
510 PEG(TOO)=.1*PEG(TOO)+SIZE
520 GOTO 310
  
```


THE "PROWRITER" IS HERE!!!

COMPARE



PROWRITER

120 CPS
Buffer - 3K included
63 LPM
Hi Resolution Graphics
Friction and Tractor
Serial and Parallel
Forward & Reverse Paper Feed
Bi Directional Print
1 Year Warranty

EPSON 80

80 CPS
Buffer - Optional 2K
46 LPM
Block Graphics
Friction - Extra
Serial Card - Extra
One Way Paper Feed
Bi Directional Print
90 Day Warranty

SPECIAL OFFER:

	OUR PRICE	SUGG. RETAIL
Prowriter 10"	\$669.00	845.00
TI-Pwriter Word Process. Program	included	32.00
Name-It Mail Merge and Form		
Letter Program	included	32.00
RS232 Cable*	included	35.95
* RS232 Required.	\$669.00	\$944.95

STAND ALONE PRICE:

Prowriter 10" (Par. & Ser.)	\$599.00
Prowriter 10" (Par. only)	499.00
Prowriter 15" (Par. & Ser.)	725.00
Prowriter 15" (Par. only)	695.00
RS232 Cable	35.95
TI-Pwriter word process. prog.	32.00
Name-It Mail Merge	32.00
Parallel Cables	35.95

or send to:

Call 513/232-7784

CINTRONICS 2284 DONNINGTON LN.
CINCINNATI, OHIO 45244

Cost of phone call will be rebated with purchase order.

Add 2% for shipping. Ohio residents add 5 1/2 % state sales tax.

FREE CABLE*! WITH THIS CRAIG CASSETTE PLAYER

\$54.99*
Mfr.'s Suggested List Price

PLUS \$ 3.50 SHIPPING

- 8 DELUXE FEATURES
- (1) AUTOMATIC SHUTOFF
 - (2) 3-DIGIT TAPE COUNTER
 - (3) PIANO-KEY OPERATION
 - (4) SLIDE-OUT HANDLE
 - (5) CONDENSER MICROPHONE
 - (6) TAPE-EJECT BUTTON
 - (7) LED BATTERY CONDITION/RECORD INDICATOR
 - (8) BUILT-IN AC ADAPTER

PLUS:
SPECIAL CIRCUITRY RECHARGES
THE MONEY-SAVING NICKEL-
CADMIUM BATTERIES (not incl.)

FULL ONE YEAR WARRANTY


**NOVA
DATA**

HAVE COMPUTER-
WE'LL CABLE

SEND CHECK OR MONEY ORDER ONLY TO:
NOVADATA SYSTEMS INCORPORATED
1104 SUMMIT AVENUE
PLANO, TEXAS 75074

TELEPHONE 214-423-6694

* TEXAS RESIDENTS ADD 5% SALES TAX ALLOW 3-4 WKS DELIVERY



* FREE
CABLE
TO RUN THIS
RECORDER ON A
TI 99/4 HOME
COMPUTER
(A \$14.95 VALUE)

Computer Peripheral Resources

5 1/4" Disk Drive Power Supplies

- Guaranteed in writing for 120 days.
- Cases accommodate all standard 5 1/4" drives.
- Over current and over voltage protection.
- Dealer inquiries invited.
- Call or write for quantity discounts.



- SPECIAL -
2 New Shugart Drives
1 Dual P/S H or V
1 Two Drive Cable
\$489.95

Dual Power Supplies

- Horizontal — 12x12x3 1/2 \$74.95
- Vertical — 7x12x6 \$74.95
- Open Frame — 7x2x3 w/o-case \$59.95
- Single Horiz. P/S —
6x12x3 1/2 \$44.95
- Custom 4' 2-Drive Cable \$21.00
- 4-Drive Cable \$32.00
- Dual Case, Horiz. or Vert.
(w/o P/S) \$24.95
- Single Case, Horiz. (w/o P/S) ... \$18.95
- Shugart 5 1/4 Disk Drive \$204.95
SA 405 — 6ms T-T, SS, SD or DD

Terms: Personal checks allow 14 days, COD, M.D., Certified Checks...Credit Cards add 3% Shipping and Handling: \$3.00 West and \$6.00 East states. All shipping USP surface other means extra.

Send to:

C.P.R.
P.O. Box 834,
Oak Harbor, WA 98277


or call...

(206) 679-4797



TEX-COMP™

TI USERS SUPPLY COMPANY
"YOUR LUBBOCK CONNECTION™"



TI-99/4 PRODUCTS AT PROFESSIONAL PRICES

ATTENTION TI-99/4 USERS: TEX-COMP HAS BEEN SUPPORTING THE ENTIRE 99/4 PRODUCT LINE TO PROFESSIONAL AND INDUSTRIAL ACCOUNTS. SINCE THE INTRODUCTION OF THE TI-99/4, NOW YOU CAN PURCHASE ALL YOUR TI-99/4 REQUIREMENTS FROM ONE SOURCE AT LOW "PROFESSIONALLY DISCOUNTED" PRICES ON THE ENTIRE 99/4 PRODUCT LINE. WE ARE A DIRECT TI NATIONAL ACCOUNT AND DEAL DIRECTLY WITH TI, ASSURING YOU THE BEST SERVICE, EARLIEST SHIPMENT AND LOWEST POSSIBLE PRICES.

**SEND FOR FREE ORDER KIT AND COMPLETE PRICE LIST
CONTAINS MONEY SAVING SPECIAL OFFERS AND NEW PRODUCT INFORMATION**

FREE SHIPPING ON SOFTWARE ORDERS OVER \$100. (PHD, PHM, PHT)

\$100. REBATE & FREE SPEECH EXTENDED TO APR. 15

TI-99/4 PRODUCT LINE

Your Cost

CONSOLE	
PHC 004A	TI-99/4A Home Computer..... 279.95
	Color TV RF Modulator (14.95 with computer)..... 14.95
	* Less 100.00 rebate direct from TI..... 100.00
	YOUR ACTUAL COST..... 194.90
PERIPHERALS	
PHP 1200	Peripheral Expansion System..... 178.95
PHP 1220	RS-232 Card..... 125.95
PHP 1240	Disk Controller Card* (One Disk Manager module packed with each Disk Controller)..... 178.95
PHP 1250	Expansion System Disk Drive (Disk Drive Controller required)..... 286.95
PHP 1260	Memory Expansion Card (32K RAM)..... 214.95
PHP 1270	P-Code Card (32K RAM Memory Expansion required)..... 178.95
PHP 1280	Pascal Development System — Includes P-Code Card (PHP 1270), UCSD Pascal* Compiler (PHD 5063), UCSD P-System* Assembler Linker (PHD 5064) and UCSD P-System* Editor Hier Utilities (PHD 5065) (32K Memory Expansion, Disk Drive and Controller are required)..... 357.95
PHP 1500	Solid State Speech™ Synthesizer..... 107.95
PHP 1600	Telephone Coupler (Modem) (RS-232 required)..... 160.95
PHP 1700	RS-232 Accessories Interface..... 180.95
PHP 1800	Disk Drive Controller* (One Disk Manager module packed with each Disk Controller)..... 214.95
PHP 1850	Disk Memory Drive (Disk Drive Controller required)..... 357.95
PHP 2500	TI Impact Printer..... 519.95
PHP 2700	Memory Expansion (32K RAM)..... 286.95
PHA 2100	RF Modulator (TV Adapter)..... 35.95
PHA 4100	10" Color Monitor..... 312.95
OPTIONAL ACCESSORIES	
PHP 1100	Wired Remote Controllers (Joysticks) (Pair)..... 25.95
PHA 2500	Dual Cassette Cable..... 10.95
APPLICATION PROGRAMS	
Home Management Personal Finance Command Modules	
PHM 3006	Home Financial Decisions..... 22.95
PHM 3007	Household Budget Management (Data storage system is recommended)..... 30.95
PHM 3012	Securities Analysis..... 41.95
PHM 3013	Personal Record Keeping (Data storage system is recommended)..... 38.85
PHM 3016	Tax Investment Record Keeping (Disk system is required)..... 53.95
PHM 3022	Personal Real Estate (Data storage system is recommended)..... 53.95
PHM 3044	Personal Record Generator (Data storage system is recommended and PHM 3113 is recommended)..... 38.95
PHM 3113	TI Writer (32K Memory Expansion, RS-232 Printer, Disk Drive and Controller are required) (Available for TI-99/4A only)..... 74.95


TEX-COMP USERS SUPPLY DIVISION

P.O. BOX 33084, GRANADA HILLS, CA 91344

(213) 873-4750

PHM 3113	Microsoft™ Multiplan (Disk Memory Expansion, Disk Drive and Controller are required) (RS-232 and Printer are recommended)..... 74.95
PHD 5001	Making Lists..... 53.95
PHD 5003	Personal Financial Aids..... 15.95
PHD 5021	Checkbook Manager..... 15.95
PHD 5077	Personal Tax Plan (Aardark Software Inc. (P-Code and 32K Memory Expansion are required) (RS-232 and Printer are recommended)..... 74.95
PHT 6003	Personal Financial Aids..... 11.95
PHT 6038	Business Aids Library (Lease Purchase Decisions (Printer is recommended)..... 45.95
Education Personal Enrichment Command Modules	
Texas Instruments Packages	
PHM 3002	Early Learning Fun..... 22.95
PHM 3003	Beginning Grammar..... 22.95
PHM 3004	Number Magic..... 15.95
PHM 3005	Video Graphs..... 15.95
PHM 3008	Video Chess..... 53.95
PHM 3010	Physical Fitness..... 22.95
PHM 3020	Music Maker (Data Storage System is recommended)..... 30.95
PHM 3021	Weight Control and Nutrition (Data Storage System is recommended)..... 46.95
PHM 3064	Touch Typing Tutor (Available for TI-99/4A only)..... 30.95
PHM 3109	TI Logo II (32K Memory Expansion is required)..... 69.95
PHM 3015	Early Reading (Solid State Speech Synthesizer is required)..... 41.95
PHM 3043	Reading Fun (Solid State Speech Synthesizer is recommended)..... 41.95
PHM 3046	Reading On..... 41.95
PHM 3047	Reading Roundup..... 41.95
PHM 3048	Reading Rally..... 41.95
PHM 3082	Reading Flight..... 41.95
PHM 3027	Addition and Subtraction I (Solid State Speech Synthesizer is recommended)..... 30.95
PHM 3028	Addition and Subtraction II (Solid State Speech Synthesizer is recommended)..... 30.95
PHM 3029	Multiplication I (Solid State Speech Synthesizer is recommended)..... 30.95
PHM 3049	Division I (Solid State Speech Synthesizer is recommended)..... 30.95
Entertainment Command Modules	
Texas Instruments Packages	
PHM 3009	Football..... 22.95
PHM 3018	Video Games I..... 22.95
PHM 3023	Hunt the Wumpus..... 19.95
PHM 3024	Indoor Soccer..... 20.95
PHM 3025	Mind Changers..... 19.95
PHM 3030	A-Maze-Ing..... 19.95
PHM 3052	Tombstone City 21st Century..... 30.95
PHM 3053	TI Invaders..... 30.95
PHM 3054	Car Wars..... 30.95
PHM 3057	Munch Man..... 30.95
PHM 3042D	Tunnels of Doom (2 Diskette Games Included)..... 43.95
PHM 3042T	Tunnels of Doom (2 Cassette Games Included)..... 43.95
PHM 3056	Alpiner..... 30.95
PHM 3110	Chisholm Trail..... 30.95
PHM 3112	Parsec..... 30.95
Milton Bradley Packages (Developed by Milton Bradley Company)	
PHM 3031	The Attack..... 30.95
PHM 3032	Blasio..... 19.95
PHM 3033	Blackjack and Poker II..... 19.95
PHM 3034	Huskie..... 19.95
PHM 3036	ZeroZap..... 15.95
PHM 3037	Hangman..... 15.95
PHM 3038	Connect Four..... 15.95
PHM 3039	Yahtzee..... 19.95
Adventure International Packages (Developed by Scott Adams)	
PHM 3041D	Adventure (P-Code Adventure Diskette Game Included)..... 37.95
PHM 3041T	Adventure (P-Code Adventure Cassette Game Included)..... 37.95
Gabriel Industries Packages (Developed by Gabriel Industries)	
PHM 3067	Orbiter (Developed by Gabriel Industries)..... 30.95
Adventure International Adventure Series (Developed by Scott Adams)	
PHM 6046	Adventureland..... 22.95
PHM 6047	Mission Impossible..... 22.95
PHM 6048	Voodoo Castle..... 22.95
PHM 6049	The Count..... 22.95
PHM 6050	Strange Odyssey..... 22.95
PHM 6051	Mystery Fun House..... 22.95
PHM 6052	Pyramid of Doom..... 22.95
PHM 6053	Ghost Town..... 22.95
PHM 6054	Savage Is and I & II..... 30.95
PHM 6055	Golden Voyage..... 22.95
Cassette	
Texas Instruments Packages	
PHM 6010	Mystery Melody..... 7.95
PHM 6015	Oldies But Goodies Games I..... 10.95
PHM 6017	Oldies But Goodies Games II..... 15.95
OTHER APPLICATION PROGRAMS Command Modules	
PHM 3011	Speech Editor (Solid State Speech Synthesizer is required)..... 35.95
PHM 3014	Statistics (Data storage system is recommended)..... 35.95
PHM 3026	Extended BASIC..... 74.95
PHM 3035	Terminal Emulator II..... 38.95
PHM 3055	Editor Assembler (Disk System and 32K RAM Memory Expansion required)..... 74.95
PHM 3058	Mini-Memory..... 74.95

POSTPAID TI 99/4A ACCESSORIES FROM TEX-COMP



**NEW — SIGNALMAN MARK III MODEM
FOR THE 99/4 and 99/4A—DIRECT CONNECT.
INTRODUCTORY OFFER—\$94.95 POSTPAID (Sug. list \$139.)
TEX-NET™ SPECIAL — TERMINAL EMULATOR II only \$34.95
When purchased with Mark II Modem.**

FOR USE WITH BELL MODULAR PHONES ONLY.

OPTIONAL 9 V BATTERY ELIMINATOR \$10.95 POSTPAID

SPECIAL OFFER

FREE Source/Tex-Net sign on and hour use with purchase


SPECIAL — 10

PREMIUM GRADE
HUB-REINFORCED
DISKETTES &
FREE PLASTIC
LIBRARY CASE

TI99/4A compatible

\$24.95 POSTPAID

NEW — DESK TOP PRINTER STAND BY DATUM



80 COL. \$14.95 POSTPAID
132 COL. \$16.95 POSTPAID

Vinyl coated steel
stands allows paper
storage under printer

SPECIAL — \$15.95 POSTPAID JOYSTICK ADAPTER — Allows two Atari wired Joy Sticks to be used with 99/4 or 99/4A.

only \$10.95 with any WICO or Tex-Comp Joystick.

NOTE — This item required with ALL WICO joy sticks or when using two Tex-Comp Super Joy Sticks (order with Atari wiring).

SPECIAL — 8 DATA QUALITY C-11



Cassettes (BASF) in
FREE Plastic
storage case

TI99/4A compatible

\$9.95 POSTPAID

WICO COMMAND CONTROL JOY STICKS

IMPORTANT—Joy
Sticks require TI
adapter \$10.95
with Joy Stick.

Joystick 15-9714 \$26.95
— Extra long arcade-style bat handle grip that moves smoothly and easily into all 8 standard positions
— Low-profile, heavy-duty plastic base

Famous Red Ball™ Joystick 15-9730 \$29.95
— Arcade-type bat handle that moves smoothly and easily into all 8 standard positions
— Low-profile, heavy-duty plastic base

The COMMAND CONTROL trackball \$57.95
— Feature injection-molded modular construction
— Phenolic ball provides unique 360 degree movement to an infinite number of positions, can also be used to vary the speed of on-screen objects
— Quick-action fire button next to the ball, for smooth, two-handed control
— Texas Instruments model #72-4580



Flip 'N' File TM For TI Modules and Cassettes


\$27.95
POSTPAID



Flip 'N' File TM For 5 1/4" Mini Disks

\$23.95
POSTPAID

SUPER JOY STICK! RATED #1



A commercial arcade
joy stick adapted for
use with your 99/4 or
99/4A. Increase your TI
invaders score. More
responsive action.

\$34.95 POSTPAID

TERMS: All prices F.O.B. Los Angeles. For fastest service use cashiers check or money order. Personal checks take at least ten days to clear. Add 3% shipping and handling (\$3.00 minimum). East of Mississippi 4 1/2 %. (Free shipping on all software orders over \$100. and on postpaid specials). Add 6 1/2 % S.T. for delivery in Calif. Prices and availability subject to change without notice. We reserve the right to limit quantities. Sorry no credit card purchases or collect calls, these costs increase your price.

Computer Gaming

The Joys of Adventuring Part 2

By Samuel D. Pincus

Contributing Editor

You are trapped in a maze and monsters threaten from every corner! The maze seems familiar, but you can't remember how you got out last time. That's right—you used a key. But you just dropped your key in another room. If only you could remember what you did last game, or where you put that key. If only you had a strategy for these adventure games, instead of stumbling through them at the mercy of the warlocks, vipers, or other powers that be . . .

Last month, in the first part of this article, I talked about adventuring in general, telling how to chart a course and avoid the snares that can crop up in these games. This final part offers six rules for strategies to help you win these "puzzle," and "sword and sorcery" games. Are you ready? Then let's go.


Rule 1—Make a Map!

Most adventures take place in major sites that are broken into 25-30 different locations (called *rooms* by adventurers). One can enter these rooms in either the obvious way (through a door or window) or through less common methods (chanting a spell or drinking a potion). In most (if not all) of the Scott Adams adventures, at least one of the doors is locked. In any case, the only way to keep track of your moves from room to room is to make a map and update it continually. Even if you think your memory is up to keeping track of the various locations, a map is good insurance against foolish mistakes. Remember, sometimes you will have to return to a room in order to complete the adventure. You may even have to go back to the starting point.

In addition, a really nasty adventure writer will include both *fly-traps* and *mazes*. In a real fly-trap room you are sure to die every time; but in the Scott Adams adventures, you will find yourself in fake fly-traps. This means that you may, indeed, die whenever you enter a particular location unless you have previously done something required of you. For example, in one BASIC adventure the only way I could get out of a room (through a locked rusty door) was to drink a strength potion. Had I not drunk it, the room would have been a fly-trap. A map is invaluable in remembering which rooms are dangerous.

In a maze, you always seem to return to the same location no matter which way you move. It can be confusing to move from room to room, all identical. A map helps you keep track of the maze.

Whenever you enter a room, update your map with the visible exits, the room contents, and anything else you think is important. List all contents, no matter how trivial they may seem. You can never tell when a glass, or a match, or an empty box will become very important later on.



Computer Gaming is a magazine for all game lovers—players, designers, and programmers of microcomputer games. Regular features include product reviews, letters to the editor, player strategy, a question and answer forum, a Hall of Fame for high scorers, tutorial articles on game design and programming, plus interviews with professionals in the world of computer gaming.


All submissions for *Pros on Programming* are governed by the same conditions and payment rate as manuscripts sent to other departments of 99'er Home Computer Magazine. Materials submitted for the features shown below are treated the same for Copyright purposes as *Letters to the Editor* in 99'er Home Computer Magazine (as explained in the Masthead): if chosen for publication, the material (except for 99'er Hall of Fame) will earn for its author a free computer game (either TI or third-party) and/or a one-year subscription to this magazine.

99'er Hall of Fame candidates with high scores in TI, third-party, or Computer Gaming games must completely describe the conditions under which their scores were achieved (i.e., skill level, keyboard or joystick use, screen number, partner participation, appearance of screen, etc.) Candidates may not be directly related to or affiliated with the programmer of the game or the publishing firm. No compensation will be provided to new inductees whose names are chosen to be immortalized—Fame is its own reward.


Adventure Registry



Joystick Jockey Q&A



Strategy Corner



Arcade Arbiter Review



Make sure you note where your exits took you. In the booklet that comes with the ADVENTURE Command Cartridge, Scott Adams presents some suggestions on map-making. Read his suggestions and try to follow them. Don't get discouraged if your first efforts look like a bowl of spaghetti. Just wait until the map looks too hard to follow and then redraw it. Even the most experienced adventurer has to redraw during his game. If you find a previously unknown exit from the room (a hidden passageway, for example), don't forget to add it to the map. Write down what you did to find the exit, and retrace your path.

Rule 2 – Save the Game!

All Scott Adams games allow you to save your game status—such as your current room location, inventory, and clothing. Use this feature after every 10 rooms or so. It will help you restart your adventure in case you do something foolish and get killed. Always save a game before doing anything that you know is dangerous (such as pushing a button). In some of the more difficult adventures, I have saved different game strategies, then started from the beginning with the idea of doing things in other ways.

Never get so engrossed in the game that you forget to save it. If you successfully negotiate a maze, and then get killed off, it is very frustrating to do it all over because you didn't type in SAVE GAME.

Rule 3 – Look, Look, Look!

Whenever you enter a room, its contents will usually be described to you in detail (unless you have been blinded during your adventure or the lights are out or.....). But don't rely on the descriptions alone. Examine everything (using the EXAMINE or LOOK command) in the room. Pay attention to every item in the room. Look at it. Move it. If it is a book or a piece of paper, read it! If the room has writing on the wall, read that too. And don't forget to examine pictures, rugs, or other items that are on the floor, walls, or even ceiling. Try to get as much information as possible.

If there is a container, such as a box or chest, open it and look inside. If something falls out, you will find it added to the description of the contents of the room. So if you open a chest and the adventure says "there's something there," look at the room contents to find out what it was. By the way, if something does fall out, that is no reason to stop examining the container. A writer of difficult adventures may have an unimportant item fall out first and leave the really important contents for last. Keep looking until you are told that there is nothing important left.

If you try to move a certain item, and it doesn't budge, it may mean the item isn't important. Just as likely, however, it only means that you don't have the skill or tool to move or get the object. For the moment, just put it on your list. A room that you stumble into later may contain just the thing you need to move the rock or lift the chain.

Rule 4 – Keep Track of Your Inventory!

Keep track of everything you carry. If you enter a room and see something you think

you may need, just tell the game to GET it. The only problem is that, as in real life, you can't carry everything. Sooner or later, you will have too much. You will have to DROP something to make room for a new item. This isn't hard, as long as you remember to DROP items after they have been used (for example, an empty gun or burnt-out match). In most adventures, an item is used only once. Sometimes, however, it may be needed later. Remember, you can never be sure of anything!

In sword and sorcery play, you must also keep track of your status. If you are wounded, your strength ebbs as you continue your journey. You may decide to fight a creature under the assumption that your strength is still high when in fact, you are bleeding to death!

Rule 5 – Keep Track of Objects!

Always update your map with the items you find in a room. If you take out an object, cross it off your map. If you then drop it in another room, relocate it on your map. It is embarrassing to forget where you dropped your gun when you need it to kill a rattlesnake.

Keep in mind that objects may change during a game. A lump of dirt, when washed, may reveal a crystal ball. A branch, when whittled, becomes a flute. Make sure you note how an object changed, what you did to change it, and where it is now. A change may be very subtle—a match burns out, a canteen is filled or emptied. Note even these slight changes.

Rule 6 – Try, Try, Try!

When you try something and find yourself stymied, don't give up! There is usually an alternative. First, try different commands. For example, you may say WET RAG and be told that the game doesn't understand. You may have to try POUR WATER in order to wet the rag. If you run out of commands, look for a different approach. You may have to pour the water into a pan and then say DUNK RAG. Of course, it may turn out that nothing will work—that you are indeed trying the impossible. Very often, however, you are just not using the right approach. For example, you may be traveling on a tree-lined path with exits to the north and south. After exploring these exits, you find that you can't get anywhere. Don't give up! Did you try to climb a tree? That may be your only way out.

Maybe you are sure that the treasure is in the room, but you can't see it. Did you dig for it? Just because you have gone over all the visible objects and obvious exits, don't think you have exhausted all the possibilities.

You are not limited to moving in just four directions. Up and down are also possible. In addition, a lot of adventures let you say things like GO PATH if you want to travel along a path or GO MOUNTAINS if that is what you see in the distance.

If you do find yourself in a real pickle (such as the maze I mentioned earlier), do not panic. Think it through. Act as though this were real life. How would you solve the problem then? In a maze, you could drop an object and then move. If the ob-

Continued on p. 50


PROS ON PROGRAMMING

Before me was the task I had been putting off from the beginning: to plan the graphics for the DICE-ROLL routine.

Because the program had been coded in TI BASIC all along, I coded this routine using HCHAR and VCHAR graphics. It occurred to me however, that the Extended BASIC graphics ability (i.e., sprites) would add a lot to this program. Then I saw that it could be done both ways.

The only problem was that I am not very graphics oriented. Oh, I do all right, but I am no world-beater at eye-boggling displays. That left me one option: I called for HELP!! and turned to my "Guru of Graphics," Ron Binkowski. You may have seen his name on some fine programs he wrote for *99'er Magazine*.

I asked Ron to develop a graphics routine to display dice rolling inside a Chuck-A-Luck wheel. About two weeks later, he called me back with the bad



news, "No dice" (pardon the pun, I just couldn't resist it). Rolling the dice was just too complicated for this program, but Ron did come up with an idea to move them graphically.

Starting to Roll

I reworked Ron's routine so that it could support both SPRITE graphics for inclusion in the Extended BASIC version and HCHAR graphics for TI BASIC. The design indicated that DICE_ROLL needed an initialize routine (to set up some variables) as well as the actual graphics roll itself. I added another module to display each player's name, cash balance, amount bet, and dice value bet.

The DICE-ROLL routine needed three new arrays. Each die can be thought of as a formation 3 pieces high and 3 pieces wide. Each character can have either a dot ("pip") or be blank. Since there are three dice and each needs 9 characters, we will have to keep track of the locations of 27 characters. The 9 characters for the first die will be numbered 1-9; for the 2nd die, 10-18; and 19-27 for the third die. The array called LOC_X keeps track of the "x" co-ordinates (the horizontal rows) of these characters while LOC_Y keeps track of the "y" co-ordinates (the columns). This means that both of these arrays must be DIMensioned with 27 entries.



Editor's Note: This four-part series is more than a game. It is a course in programming, covering many of the fine points of the art. Part 1 (Vol. 1, No. 4) gave some basic rules for designing games. Part 2 (Vol. 1, No. 5) laid out a coding plan for a "stripped down" version of the game. Part 3 (Vol. 1, No. 6) showed how to code in the complete program and how to debug it. In this final portion, Mr. Pincus shows how to add graphics using Extended BASIC. The complete Chuck-A-Luck Extended BASIC program is also included here.

Chuck-A-Luck

Part 4

By Samuel D. Pincus

Contributing Editor

The array called DICE_PIP tells whether characters are blank or have a pip for each possible value of the dice. Since there are six possible dice values, each to contain information on nine characters, we will need a two-dimensional array composed of 9 entries for each of 6 possible dice-values.


Arrays are Like Buildings

Remember our discussion about arrays? I said that you can envision an array as a building with a number of rooms on each floor. Well, in a two dimensional array, the first variable can be thought of as the floor number. The second number is the room on the floor. For example, you can think of DICE_PIP(2,4) as the value located in the 4th room of the second floor of a building called DICE_PIP. For our program it will contain the information about the 4th character (middle row on the left) needed to display a dice roll of a 2.

To make the display more interesting, Ron added 3 more dice values. He realized that, depending on how a die fell, the values of 2, 3, and 6 could be portrayed two different ways. The three extra "floors" in DICE_PIP are alternate displays for the values of 2, 3, and 6. This meant

the new arrays. Lines 20100-20200 are used to read in the data for DICE_PIP. Each DATA line (in 25000-25080) describes whether a character of a dice value is supposed to be blank (=0) or have a pip (=1). Each line gives the information needed for the 9 characters making up the dice value. Line 25090 is an extra DATA line. TI BASIC usually slows down when it reads the last DATA line in a program, but with an extra DATA statement, it never reads the last line, and never slows down.

In order to simulate the DISPLAY AT function, available only in Extended BASIC, I added a routine to the TI BASIC version in statements 4900-4930 to print whatever was in MSG\$ beginning at COL on the row contained in ROW. It runs much faster than the code given in TI's Programming Aids I software package, because it is restricted to a single row and does no preliminary editing of the message area. In lines 20300-20420, I added the codes to show where each of the 9 characters for each die are to be displayed. In the TI BASIC version, these are actual row and column numbers. In the Extended BASIC version, these contain the "dot row" and "dot column" values needed for sprites.



the DICE_PIP had to be DIMensioned as (9,9). I added this code as line 110. In addition, for the SPRITE version of the routine in Extended BASIC, Ron needed an array to keep track of particular pieces of the die, to determine if they were in position. He called this array LOC, and since there are 27 different pieces, I DIMensioned it at 27 in line 120.

I then added the code in lines 20010-20420 to fill in the data needed for

I then coded lines 2000-2370 to display the information about each player on the screen. The new code in 2600-3920 displays the three dice values graphically. Lines 2630-2740 give a 50-50 chance that a dice value of 2, 3, or 6 will be displayed in its alternate format. The 9 characters making up the die are then displayed in the loop in lines 2750-2990 in the TI BASIC

Continued on p. 51

PLATO WIDENS YOUR CHILD'S WORLD.

Announcing new educational courseware
for microcomputers to improve your child's
Basic Skills, High School Skills or Foreign Language vocabulary.



**NOW. PLATO Basic Skills.
NOW. PLATO High School Skills.
Both for use with TI 99/4A.***

Control Data and Texas Instruments are working together to make this nationally recognized PLATO courseware available via microcomputers.

Control Data's PLATO Basic Skills is a comprehensive curriculum designed to enhance the development of elementary and junior high Reading, Math and Grammar skills.

Control Data's PLATO High School Skills help high school level students master Reading, English, Math, Social Studies and Science. It has been used to assist students preparing for G.E.D. exams.

*For Basic and High School Skills pricing and order information, write: Texas Instruments, Education Department, Box 53, Lubbock, TX 79408.

WIDEN YOUR CHILD'S WORLD WITH THIS INTRODUCTORY OFFERING.

10 DAY MONEY-BACK GUARANTEE.

Now, until May 31, 1983, when ordering a lesson at \$45.00, you may order additional lessons for just \$35.00 each. (Additional disk is included with each lesson at no additional charge.)

Mail this form, or call toll-free 800/233-3784. (In California, call 800/233-3785.)

Apple® is a trademark of Apple Computer, Inc.
Atari® is a registered trademark of Atari, Inc.
TI® is a registered trademark of Texas Instruments.

Warranty available free from the Control Data Publishing Co., 4455 Eastgate Mall, San Diego, CA 92121.

BEFORE ORDERING: CHECK TO MAKE SURE YOUR EQUIPMENT MEETS THESE REQUIREMENTS.

	Apple II PLUS	Atari 800	TI 99/4A
Memory:	48K	48K	48K
No. of drives required:	1 disk and controller	1 disk and controller	1 disk and controller
Operating System:	D.O.S. 3.3	D.O.S. 2	PLATO Interpreter Cartridge*
Will display on any color or b/w monitor or TV compatible with your microcomputer listed.			

*PLATO Interpreter Cartridge may be ordered directly with the order form below. Only one per TI 99/4A machine is needed.

CONTROL DATA PUBLISHING CO., P.O. Box 261127, San Diego, CA 92126

SHIP TO: (Please Print)

Name _____

Address _____

City _____ State _____ Zip _____

☐ Payment enclosed (Check or money order only. Make payable to Control Data Publishing Co.).

☐ Mastercharge ☐ VISA ☐ American Express ☐ Diners Club

Card Number _____ Expiration Date _____

Your signature _____ Phone _____

INTRODUCTORY PRICES: One lesson \$45.00. Each additional lesson \$35.00.

Price for order: \$ _____

Calif. Residents: add 6%

sales tax: \$ _____

Add \$2 shipping and handling: \$ **2.00**

TOTAL PRICE: \$ _____

☐ Include PLATO Interpreter Cartridge for my TI 99/4A. Price \$50.00.

☐ Please send information on _____ lesson(s).

☐ Please send _____ copies of your courseware catalog.

Please complete the following: (Indicate computer for which you are ordering courseware.)

APPLE II PLUS ☐ ATARI 800 ☐ TI 99/4A ☐

Available on APPLE II PLUS only

Quantity	Title (see course description for skill level)
	Basic Number Facts
	Whole Numbers
	Decimals
	Fractions
	Physics—Elementary Mechanics
	French Vocabulary Builder
	German Vocabulary Builder
	Spanish Vocabulary Builder
	Computer Literacy Introduction

Allow 3-5 weeks for delivery

Quantity	Title (see course description for skill level)
	French—Travel Words
	German—Travel Words
	Spanish—Travel Words
	French—Shopping Words
	German—Shopping Words
	Spanish—Shopping Words
	French—Classroom Words
	German—Classroom Words
	Spanish—Classroom Words

Available March 30. Allow 3-5 weeks for delivery

If not completely satisfied, you may return all lesson material within 10 days of receipt for a refund. All orders subject to acceptance. This introductory offering expires May 31, 1983.

Control Data Publishing Company supplies this courseware under a personal license agreement rather than for sale. Customers obtain the right to possess and use PLATO courseware by paying the prices specified and agreeing to the terms and conditions of the license agreement contained in the package.

NN-2

Physics—Elementary Mechanics: Students are presented a physical problem, then learn "purchase" the missing information to answer it correctly. For senior high physics students.

French, German, Spanish Vocabulary Builders: Gives children a basic vocabulary of 500 words. Supplements introductory and refresher courses.

Computer Literacy—Introduction: For jr. or sr. high and vocational school students.

INTRODUCTORY OFFERING:

- *Single lesson, \$45.00
- *Additional lessons, \$35.00 ea.
- *Additional disk included with each lesson ordered at no extra charge
- *10 day money-back trial



SEND FOR PLATO COURSEWARE CATALOG

For a free copy of our PLATO catalog, or to order, mail reply card, call toll-free 800/233-3784, or write Control Data Publishing Co., P.O. Box 261127, San Diego, CA 92126. In California, call 800/233-3785.

CONTROL DATA
PUBLISHING

PLATO®
COMPUTER-BASED EDUCATION

NEW!* Nine lessons in Foreign Languages for use with Apple II Plus.

Three lessons each for French, Spanish and German. Each lesson uses a hangman or pyramid game to help children learn words most associated with defined activities. For junior or senior high students.

Travel Words: Children study French, Spanish or German words they need to know to buy train, plane or bus tickets, order in a restaurant, request medical assistance, read street signs, etc.

Shopping Words: Children study French, Spanish or German words they need to know to shop for food, clothing, etc.

Classroom Words: Children study the French, Spanish or

German words that are common to the school environment.

*Available March '80

Lessons Available For Apple II Plus, TI 99/4A and Atari 800.

Basic Number Facts: Practice in addition without carrying, subtraction without borrowing, and multiplication/division with single digits. For elementary students.

Whole Numbers: Practice in addition, subtraction, multiplication, division and mixed numbers. For elementary and junior high students.

Decimals: Practice locating decimal numbers on the number line. For elementary students.

Fractions: Same skill level and format as decimals.

Physics—Elementary Mechanics: Students are shown a physical problem, then must "purchase" the missing information to answer it correctly. For senior high physics students.

French, German, Spanish Vocabulary Builders: Gives children a basic vocabulary of 500 words. Supplements introductory and refresher courses.

Computer Literacy—Introduction: For jr. or sr. high and vocational school students.

INTRODUCTORY OFFERING:

- Single lesson, \$45.00
- Additional lessons, \$35.00 ea.
- Additional disk included with each lesson ordered at no extra charge
- 10 day money-back trial




SEND FOR PLATO COURSEWARE CATALOG

For a free copy of our PLATO catalog, or to order, mail reply card, call toll-free 800/233-3784, or write Control Data Publishing Co., P.O. Box 261127, San Diego, CA 92126. In California, call 800/233-3785.

GD
CONTROL DATA
PUBLISHING


PLATO®
COMPUTER-BASED EDUCATION



Lifeline to TITAN

By Bill Bies

217 Park Entrance Dr.
Pittsburgh, PA 15228



At long last, our resupply mission is almost completed. Over 25 months ago (it seems like 25 years) we left Earth for this desolate mining community on Titan, Saturn's largest and richest moon. I guess we should be thankful—our TI-NAV computer shaved three months off the trip by using the gravitational "slingshot" effect around Jupiter.

Unfortunately, like almost all mining communities, this one is located in the middle of the roughest mountain range on Titan, and landing here reminds one of playing Russian roulette . . .

I can make out the mountain range as we descend for our final approach. The landing site is now coming into view. They call that a landing site? It's not much more than a rocky ledge with a mountain to one side and a cliff to the other! If I can land this one, I'll be asking for a bonus. Oh well, here goes *everything* . . .

You can finish the story when you run this Extended BASIC program. A random landscape on the screen is created, and the object of the game is for you to maneuver your lander to the only flat part of the terrain.

There are three levels of difficulty—the higher levels providing a smaller pad to aim for. On the third level you barely have room for your lander.

You can maneuver your ship with either the keyboard or joystick #1. On the keyboard you use the S and D keys to rotate the lander, and V to fire your rockets. On the joystick you merely move the paddle left or right, and press the fire button for thrust.

Now that you're ready, put on your helmet and strap yourself in. There are some desperate miners down there, and you wouldn't want to "alienate" a Titan miner when he's hungry . . .

EXPLANATION OF THE PROGRAM *Lifeline to Titan*

Line Nos.			
100-160	REM statements.	810-960	Display title screen.
170-190	Check for expansion memory. If it's there, delete all sprite motion.	970-1040	Display instructions.
200-260	Initialize variables and set character colors.	1050-1490	Display landscape.
270-360	Define character patterns.	1500-1650	Display playing screen and messages.
370-420	Initialize arrays.	1660-1740	Ship explodes. End of game.
430-460	Set up title screen.	1750-1810	Input options for the next game.
470-480	Branch to set up playing screen.	1820-1850	Initialize variables to play the same game.
490-800	Main control loop.	1860-1980	Good landing.
		1990-2060	Do instant replay.
		2070-2130	Subroutine to play a sound.
		2140-2230	Subroutine to do explosion.
		2240-2280	Subroutine to stop sprites.

```

100 REM *****
110 REM * LIFE LINE TO TITAN *
120 REM *****
130 REM BY BILL BIES
140 REM 99'er VERSION 2.4.1XB
150 REM
160 REM
170 ON ERROR 210
180 RAM$="N"
190 CALL INIT :: CALL LOAD(-31878,0
1
200 RAM$="Y"
210 CALL CLEAR
220 RANDOMIZE
230 FOR SET=1 TO 14
240 CALL COLOR(SET,16,1)
250 NEXT SET
260 CALL SCREEN(9)

```

```

270 CALL CHAR(40,"B0402010080402010
102040810204080FF"&RPT$("0",28)
&"FF")
280 CALL CHAR(96,"0010102828447C820
0081818286898040004081828C83008
00020C34C8281010")
290 CALL CHAR(100,"000002BC48502020
0000807E4C3020400080605B4658608
04020304C7E800000")
300 CALL CHAR(104,"20205048BC020000
101028CB340C02000830C8281808040
00498682818180800")
310 CALL CHAR(108,"B27C442828101000
2019161418181000100C13141810200
0080814132C304000")
320 CALL CHAR(112,"04040A123D400000
02040C327E01000001061A621A06010
00000017E320C0402")

```

```

330 CALL CHAR(116,"0000403D120A0404
0040302C131408080020101814130C1
00010181814161920")
340 CALL CHAR(120,"001018181416194"
)
350 CALL CHAR(122,"0000040202000000
0000000404040000000000001008080
0000000000020202")
360 CALL CHAR(126,"00000000000206030
0000000080A06060000000000020202
00000000707010101")
370 DIM DIR(28,2),HGT(256),N$(3),RP
LY(25,3)
380 N$(1)="CADET" :: N$(2)="OFFICER
" :: N$(3)="VETERAN"
390 RESTORE 410 :: FOR CELL2=1 TO 2
:: FOR CELL1=1 TO 24

```

Continued on p. 38

Night Blockade



By Ants Reigo

161A Kenwood Ave.
Toronto, Ontario Canada M6C 2S6

Man your battle stations. **ENEMY ALERT!** It is a nice quiet evening on board your battleship, until an enemy task force tries to break the blockade you've set up. To make things worse, it's night—so you can't even see the enemy. All you have to guide you is the beeping of your radar scope. Suddenly you open fire on the intruders, and with each explosion the night sky lights up, giving you a better idea of what you're up against.

Night Blockade was written in an effort to come up with a fast-action game—one in which the entire keyboard is read as rows and columns on the screen, so that aiming your cannon is as simple as pressing a single key.

Playing the Game

When the menu screen appears, select the "NEW GAME" option. The screen will go black, and a small green radar scope will appear at the bottom of your screen. Enemy vessels show up on the radar scope, accompanied by a beep. Your objective is to direct the firing of your ship's cannons to destroy the enemy. To do this, press the space bar to put your cannons in firing mode. That mode will be confirmed by either "firing mode engages" (the 99/4A), or a magenta rectangle (the 99/4). Once in firing mode, you can press any key to fire a shot. Each shot fired will light up the screen, momentarily giving you the precise location of the ships. At first you are limited to six shots per round before having to reload. If enemy missiles strike your ship, they will knock out some of your guns and reduce the number of shots you can make without reloading. If you do not fire immediately after entering the firing mode, the computer will leave firing mode and return to radar scan.

The only way to win the game is to stay alive. There are, however, two ways to lose: If you let two ships get by you, or your fire power is reduced to zero, the game will end. A display shows you the number of ships you have sunk and your percentage of hits vs. misses, with the option of starting a new game.

If you wish to take a break in the middle of the game, press the ENTER key. It takes you back to the option page where you can resume play by selecting the CONTINUE option.

Note: If you have the 99/4, the letters in lines 2320, 2330, 2340 and 3340 should be changed to upper case.

EXPLANATION OF THE PROGRAM <i>Night Blockade</i>		
Line Nos.		
170-250	Sets appropriate keyboard flag for 99/4 and 99/4A.	950-1000
260-320	Displays instruction page while DATA statements are read and graphics characters defined.	1010-1020
330-350	Character definition data.	1030-1170
360-430	Sets of screen coordinates for row and column arrays.	
440	Radar scope correlates for target positions.	1180-1220
450	Initial values for new game.	1230-1260
460-570	Array reading and character definition.	1270-1510
580-600	Colors for graphics set.	1530-1810
610-660	Displays menu and branches to selection.	
670-690	Additional coordinates for ENTER on 99/4A and ENTER and period on 99/4.	1820-2110
700-720	Initialization for new game.	2120-2200
730	Turns Firing Mode Indicator off.	
740	Sets up screen.	2210-2250
750-1220	Main loop.	
760-800	Keeps track of shots, resets shot counter and checks for end of game.	2260-2390
810	Branches randomly to immediate missile launch.	2400-2590
820	Conditions for immediate missile launch.	2600-2750
830	Ship positions are incremented.	2760-2910
840	Conditions for delayed missile launch.	2920-3050
850-910	Branches randomly to missile launch by first or second ship or bypass of missile launch. Line 880 registers player reaction.	3060-3110
920	Draws scope.	3120-3430
930	Displays ships and blips.	
940	Produces radar scan.	3440-3910

Listing begins on p. 39

PRICE BREAKTHROUGH

Super Sale on New Disk Drives

Starting at \$ 199.95* complete!!
with Power Supply and Case.

single sided 40 track — dual sided 40 track

single sided 80 track — dual sided 80 track

for

**RADIO SHACK¹ — HEATH/ZENITH² — APPLE³
IBM/PC⁴ - TEXAS INSTRUMENTS⁵ & MOST OTHER COMPUTERS**

New!! Special Special - Call us!!

Featuring Drives for the TI-99/4A

**TOLL FREE ORDERING
1-800-343-8841**

**GENERAL and TECHNICAL
1-617-872-9090**

Diskettes of all sizes (Box of 10) starting at **\$15.95**
Dot Matrix Printers **\$Call**
Word Processing Printers starting at **\$999.95**
Printer Buffers 8K to 64K starting at **\$133.00**
Disk Drive Cases and Power Supplies . starting at **\$49.95**
Filler pieces for Basf slimline drives **\$4.98**

***Ask about our ~~Double Double~~ Warranty.**
Dealer inquiries invited.

SOFTWARE SUPPORT

One Framingham Centre, Framingham, MA 01701
(617) 872-9090

Hours: Mon. thru Sat. 10 am to 6 pm (E.S.T.)

TERMS:

M.C./Visa/Amex and personal
checks accepted at no extra charge.
C.O.D. Please add \$3.00.
Shipping: Please call for amount.

1 "TANDY CORPORATION
2 "ZENITH DATA SYSTEMS
3 "APPLE COMPUTER CORP.
4 "IBM CORPORATION
5 "TEXAS INSTRUMENTS

VOYAGER ASSEMBLY LANGUAGE

Your Galaxy is threatened by The Nebulons, an Alien Force from The Veil Nebula. Take command of the most advanced Starfighter available to defend your Star System. Use the Joystick to maneuver your Ship and fire Lasers.

Spectacular graphics and sound effects are made possible with this Assembly Language Game. Aliens approach you in 3-D as you try to destroy them. Laser Blasts recede into the distance when fired. Your view is from the Pilot's Seat.

More Software Available
FREE CATALOG

Price: \$30.00 ppd.

Requires Joysticks, Extended Ram,
Disk System and Extended Basic.

HEADWIND SOFTWARE

6347 LAKESHORE
DALLAS, TEXAS 75214
214 / 824-0223



**"Fifteen men on the dead man's chest
Yo-Ho-Ho, and a bottle of Rum."**

Your five man diving team has found the lost treasure of Blackbeard the pirate! Unfortunately it is at the bottom of a shark infested sea and it is protected by two giant Octopuses!!

***** **Warning** *****

The sharks haven't been fed since the last time someone played this game and they love to eat divers!!!

Automatic multi-level game with free plays. Beautiful full color graphics and special sound effects. Written in Extended Basic.

Cassette-G06C-14.95 Disk-G06D-17.95
CA residence Add 6% State Tax
1st class shipping/handling-1.50



Free Game Brochure Available

MILLERS GRAPHICS

1475 W. CYPRESS AVE. • SAN DIMAS, CA 91773
(714) 599-1431

WIZARD'S DOMINION

99/4

A Fantasy Adventure

99/4A



The Voritka Ogres are on the prowl. Only the Wizard's Apprentice, the Evil Wizard, the Hero and the Evil Prince have enough courage to defeat them and rule Wavoria. Inside the caverns of The Wizard's Dominion lay gold, adventure and magical powers.

- 3-D Perspective
- Magical Powers Galore
- Superb Graphics
- Complex Battles
- Ages 12 to Adult
- Many levels to Conquer

Extended Basic Language

All this for only!! \$19.95 cassette \$21.95 disk

Announcing New Games!!

Let your computer take you on exciting adventures. Go to strange new lands...go back in time...visit a haunted house...solve the puzzles and mysteries. Get ready for hours of adventuring fun as you play the new Tlventures by Scott Morgan.

- HAUNTED HOUSE
- AQUA BASE
- STONE AGE
- THE FOUR VEDAS
- FUN HOUSE
- MINER '49 ER

Extended Basic Language only \$14.95 each cassette!

ENTRAPMENT (An Arcade Game You Can Beat)

Now you can bring the speed and fun of video arcade games home at a reasonable price. Entrapment is written in assembly language for fast moving excitement. Either the Extended Basic, Mini-Memory or the Editor/Assembler module are required. Memory expansion and disk system also required. Joysticks optional.

only \$19.95 disk!

Many other programs in Basic & Extended Basic available.

Write for more information.

Complete instructions included. To save C.O.D. charges, send check or money order plus \$1.50 shipping/handling. MN residents add 5% sales tax.



**AMERICAN SOFTWARE
DESIGN & DISTRIBUTION CO.**
P.O. BOX 46
COTTAGE GROVE, MN 55016-0046

FFF Software Presents . . .

SHUTTLE COMMAND

Earth is threatened by thousands of Russian Attack Military Satellites (RAMS). The United States readies the space shuttle Enterprise to combat the menace and selects you as its commander.

Your view is from the cockpit and you see the RAMS approach (in 3-D) from deep space. Your mission is to destroy them before they destroy Earth - or you!

The producers of the now-classic TI-ASTEROIDS bring you a new and challenging space game. Joysticks are optional, but recommended, for this exciting Extended BASIC program which features 1 or 2 player capability, 12 skill levels and great graphic effects.

Available for only \$17.50 on cassette or diskette

Also Available . . .

TI-ASTEROIDS

See what the Experts are saying:

"TI-ASTEROIDS is by far the best space game we have seen programmed for the 99/4 in an [Extended] BASIC Language."

Charles LaFara, President
International 99/4(A) Users Group
Newsletter (Vol. 1, No. 7)

"I was impressed to see what could be done in Extended BASIC . . . by such firms as FFF Software (Trenton, NJ) with their TI-ASTEROIDS game . . ."

Gary M. Kaplan, Editor
99'er Magazine (Vol. 1, No. 4)

Available for \$17.50 on cassette or diskette
or for only \$10.00 if purchased
together with SHUTTLE COMMAND.

TO ORDER WRITE:

FFF SOFTWARE

P. O. Box 4169

Trenton, NJ 08610

DHEIN'S MEANS ONE—STOP—SHOPPING

FOR THE BEST 3RD PARTY SOFTWARE

3RD PARTY ENTERTAINMENT American Software

Wizard's Dominion — Extended Basic

AMT001 Cassette
AMD001 Disk

Land on Mars

AMT002 Cassette
AMD002 Disk

Meteor Shower — Extended Basic

AMT003 Cassette
AMD003 Disk

Bomb Squad — Extended Basic

AMT004 Cassette
AMD004 Disk

Mr. Frog — Extended Basic

AMT005 Cassette
AMD005 Disk

3-D Maze — Extended Basic

AMT006 Cassette
AMD006 Disk

Ski

AMT007 Cassette
AMD007 Disk

Laser Shield

AMT008 Cassette
AMD008 Disk

Space Battle 2056

AMT009 Cassette
AMD009 Disk

Barnyard Fun

AMT010 Cassette
AMD010 Disk

Auto Maintenance — Extended Basic

AMD011 Disk only

007:Aqua Base — Extended Basic

AMT012 Cassette only

Haunted House — Extended Basic

AMT013 Cassette
AMD013 Disk

Miner 49'er — Extended Basic

AMT014 Cassette
AMD014 Disk

The Four Vedas — Extended Basic

AMT015 Cassette
AMD015 Disk

Fun House — Extended Basic

AMT016 Cassette
AMD016 Disk

Stone Age — Extended Basic

AMT017 Cassette
AMD017 Disk

Game Pack 1

Includes Land on Mars, Ski, Laser Shield and Space Battle.

AMT017 Cassette

Game Pack 2 — Extended Basic

Includes Wizard's Dominion, Meteor Shower and Bomb Squad.

AMT018 Cassette

Entrapment

Either Extended Basic, Mini-Memory, or Editor/Assembler Module required. Disk system also required. Joysticks optional. Note: X-Basic version written in Assembly; loads with X-Basic. Please specify which version is wanted.

AMD020 X-Basic version

AMD021 Assembly

Extended Software

All programs require Extended Basic.

TI-Pwriter

EXT001 Cassette
EXD001 Disk

Name It

EXT002 Cassette
EXD002 Disk

5 Game Pack

Includes all five games below.

EXT003 Cassette
EXD003 Disk

Froggy — Extended Basic required.

EXT004 Cassette
EXT004 Disk

Baseball/Gorfia Pestulitis

EXT005 Cassette
EXD005 Disk

Hangman/Tic-Tac-Toe

EXT006 Cassette
EXT006 Disk

Norton Software

All programs are in Extended Basic. Programs on disk require the Memory Expansion Unit.

Graphics Package

NST001 Cassette
NSD001 Disk

Music Synthesizer

NST002 Cassette
NSD002 Disk

Lunar Lander

NST003 Cassette
NSD003 Disk

Tank

NST004 Cassette
NSD004 Disk

3-D Star Trek

NST005 Cassette
NSD005 Disk

Attack-Man

NST006 Cassette
NSD006 Disk

Cross Country Car Rally

NST007 Cassette
NSD007 Disk

Super Frogger

NST008 Cassette
NSD008 Disk

Not-Polyoptics

Starship Pegasus

NPT001 Cassette

Winging It

NPT002 Cassette

Sengoku Jidai

NPT003 Cassette

Ships!

NPT004 Cassette

Khe Sanh

NPT005 Cassette

Ant Wars

NPT006 Cassette

Hordes

NPT007 Cassette

Crosses

NPT008 Cassette

Maze of Ariel

NPT009 Cassette

Tickworld

NPT010 Cassette

Cars & Carcasses II

NPT011 Cassette

Advance

NPT012 Cassette

Republic Software

Ring Destroyer

Requires Extended Basic and Joysticks.

RST001 Tape

RSD001 Disk

Software Exchange Group

Space Games — Extended Basic required.

Includes Alien Attack, Invade the Empire and X-Wing Pilot.

SET001 Cassette

Assortment Package

Includes Video Bowling, Monster Match and 3D Tic Tac Toe.

SET002 Cassette

Atlantic City

Includes Slot Machine, Black Jack and Shimmy.

SET003 Cassette

**Write for FREE
descriptive bulletin.**

Only \$2.98 shipping & handling in Continental U.S. Any size order. No extra charge for VISA or Master Charge.

Iowa residents add 3% sales tax.

DHEIN'S



(319) 236-3861

7 W. Airline Hwy.
Waterloo, IA 50701

Why did the chicken cross the road? Most computer games give you the stock reply: "to get to the other side." But the new *Chicken* game program from Tomputer Software has a much more sensible answer: "... to eat all the chicken feed lying on the highway."

This game is superior to the other "chicken crossing the road" games I've seen. Not only are there good graphics and speed, but you can also move the chicken in eight directions—not just up and down. Pushing the fire button on the joystick will make the chicken quickly jump out of the way of a speeding car or motorcycle.


But what makes this game different is that it combines the standard "chicken" game with some elements of *Pac-man/Munchman*: You are trying to avoid the traffic along this multi-lane highway while at the same time trying to gobble up 10 pieces of corn so you'll progress to the next level of difficulty. Each new level gives you the chance of accumulating more points, but you'll also be facing a greater number of vehicles. And since there are 12 pieces of corn scattered around at each level, you'll have to use some strategy in deciding which

ones you can safely eat without being run over.

You start the game with three chickens. At first, the road is very easy to cross. By the time you reach the third level, the highway is bustling with traffic. Make the right moves and you'll be rewarded with bonus

chickens—move too slow and your goose is cooked!

Chicken from Tomputer Software is definitely a game where it pays to eat and run. And \$7.96 is "chickenfeed" for a game of this caliber.



The Chicken

Reviewed By Steve Schwartz

Games Review Editor

Author: Tom Perkowitz
 Program Type: Arcade "Chicken Crossing the Road"
 Language: Extended BASIC
 Distributor: Tomputer Software
 1550 Montgomery Drive
 Deerfield, IL 60015
 Price: \$7.96 cassette

Froggy

Reviewed By Steve Schwartz

Games Review Editor

Author: A. Green and J. Couto
 Program type: Arcade Frog Jump
 Language: Extended BASIC
 Distributor: Extended Software Company
 11987 Cedar Creek Drive
 Cincinnati, OH 45240
 Price: \$9.95, cassette or disk

Home computer games don't have to be exact copies of arcade games to be good. A fitting example is *Froggy*, a new program patterned after the very popular *Frogger* arcade game—but with a challenge quite different from the quarter-eating original.

You start with five of the little beasts, one of which is ready to start jumping from the bottom of the screen across a multi-lane highway bustling with traffic. With either keyboard or joystick, this phase of the game is a snap. Score 5 points for each successful forward (upward) hop.

It gets tougher at the top half of the screen. Here you have to jump your pet from one moving log to the next—six of them altogether—until you get all the way to the top of the screen. Score 50 points for each successful jump and rack up a bonus of 100 points for making it all the way.

If you are talented enough to get all five of your frogs across (a truly amphibious landing) you'll be rewarded with another five frogs—something I've been able to accomplish only once. Since the logs are moving at different speeds and in different directions, it takes steady nerves

and precise timing to jump at just the right time. If you miss the log, the little fly-breath will jump into the river and swim away. A hit from a car and your frog will croak. (Sorry, but I couldn't resist it). Either way, you lose!

Unlike the arcade original, you can stay on a log as it wraps around the screen, making it a bit easier to play, but in *Froggy* there's only one log per row. As I said earlier, the challenge is different from *Frogger*.

This is a colorful and action-packed game, sure to delight young and old, and it has lasting play value. The action would be faster with a few more cold-blooded cars in each lane—perhaps more sound effects such as honking horns—but I'm satisfied with *Froggy*, and am eager to see what Extended Software Company will do with my other arcade favorites.



32K Memory Expansion

for TI99/4A



Only
\$159⁹⁵

MLS 32K Memory features:

- Low Cost-High Speed Memory Expansion without added cost of expansion box.
- 6 Month Limited Warranty
- Fully Compatible with daisy chain systems and all TI99 Software.

Model I: Use without expansion box at end of daisy chain.

Model V: Same as Model I except allows use of expansion box. (Add \$15.00 for Model V.)

Send for free brochure.

Please enclose check or money order (specify model). Mail to:

Hi-Tech Systems

2337 Bonanza Court
 South Jordan, Utah 84065

TRIATHLON TECHNOLOGY by CASIO

Finally... a sportswatch with features developed specifically for one of the most physically demanding sporting events ever.

Engineered for adventure. This incredible timepiece insures precision accuracy throughout the triathlon challenge. Watertight to withstand the long-distance swim—Pace control to improve your bicycling and running performance.


The TRIATHLON WATCH is spot-on accurate to within 1/100th of a second while timing events up to 24 hours. Timer, daily and hourly alarm, and calendar functions come standard. The TRIATHLON WATCH. High-technology AND bullet-proof performance. Get yours today from The BACH Company. **\$29.95**

ORDER TOLL FREE

800-227-8292

The BACH Company

715 Ensign Way, Palo Alto, CA 94303
 415-494-1995



99'er BOOKSTORE

**BASIC COMPUTER
PROGRAMS
IN SCIENCE AND
ENGINEERING**

Beginner's Guide for the UCSD Pascal System

CHILDREN, COMPUTERS,
AND POWERFUL IDEAS

SEYMOUR PAPERT



MINDSTORMS: CHILDREN, COMPUTERS AND POWERFUL IDEAS

By Seymour Papert.
The definitive work on the philosophy behind LOGO. excerpted in the Vol. 1 issue of this magazine.

Hardcover, \$13.95
1980, 230 pages, 6 x 9

BASIC COMPUTER PROGRAMS FOR BUSINESS : VOL. 1

By Charles D. Sternberg.
Each program is documented with a description of its functions and operation, a listing in BASIC, a symbol table, sample data, and one or more samples.

Volume 1 contains over 35 programs covering: budgets, depreciation, cash flow, property comparisons, accounts payable, order entry, warehouse locations, inventory turnover analysis, job routing, resource allocation, production scheduling, etc.

volume 1, paper, \$12.95
1980, 384 pages, 7 x 10

BEGINNER'S GUIDE FOR THE UCSD PASCAL SYSTEM

By Kenneth Bowles.
This highly informative book is written by the originator of the UCSD Pascal System. It is designed as an orientation guide for learning to use the UCSD Pascal System, and features tutorial examples of programming tasks in the form of self-study quiz programs. Once familiar with the system you will find the guide an invaluable reference tool for creating advanced applications.

paper, \$12.95
1980, 204 pages, 6 x 9

BASIC Computer Programs for the Home



BASIC COMPUTER PROGRAMS FOR THE HOME

By Charles D. Sternberg.
An invaluable book containing over 75 practical home application programs that will be helpful to the novice or experienced owner in increasing the usefulness of any home computer. Each program is documented with a description of its functions and operation, a listing in BASIC, a symbol table, sample data, and one or more samples.

paper, \$11.95
1979, 336 pages, 7 x 10

GAME PLAYING WITH BASIC

By Donald D. Spencer.
Enjoy the challenge of competition with your computer. Amuse yourself with such games and puzzles as 3-D Tic-tac-toe, Nim, Roulette, Magic Squares, the 15 Puzzle, Baccarat, Knight's Magic Tour, and many others. The writing is nontechnical, allowing almost anyone to understand computerized game playing.


paper, \$11.50
1977, 176 pages, 6 x 9, illus.

BASIC COMPUTER PROGRAMS IN SCIENCE AND ENGINEERING

By Jules H. Gilder.
Save time and money with this collection of 114 ready-to-run BASIC programs for the hobbyist and engineer. There are programs to do such statistical operations as means, standard deviation averages, curve-fitting, and interpolation. There are programs that design antennas, filters, attenuators, matching networks, plotting, and histogram programs.

paper, \$11.95
1980, 160 pages, 6 x 9, illus.

TI BASIC INTRODUCTION TO TI BASIC



PRACTICAL BASIC PROGRAMS

Edited by Lon Poole.
Here is a new collection of 40 programs you can easily key in and use on most microcomputers. Each program does something useful. *Practical BASIC Programs* is especially useful in small business applications. It solves problems in finance, management decision, mathematics and statistics. It requires no prior programming knowledge. Each program is thoroughly documented. The book contains sample runs, practical problems, BASIC source listings, and an easy to follow narrative to help you realize the potential uses of each program.

paper, \$16.50
1980, 200 pages, 8 1/2 x 11

INTRODUCTION TO TI BASIC

By D. Inman, R. Zamora, and R. Albrecht.
This comprehensive work will teach you all about computers and BASIC for use with the Texas Instruments Home Computer. Even if you've never worked with a computer, you can now teach yourself how to use, program and enjoy the TI Home Computer with this entertaining, and easy-to-read work. The authors have carefully constructed this introduction so that you will soon be writing BASIC programs and exploiting all of the excellent features of the TI machines. Its 14 chapters and Appendices cover all of the essential programming statements and machine features.

paper, \$12.95
1980, 384 pages, 7 x 10

INTRODUCTION TO PASCAL (INCLUDING UCSD PASCAL)

By Rodnay Zaks.
This is the first book on Pascal that can be used by persons who have never programmed before, but more generally it is a simple and comprehensive introduction to standard and UCSD Pascal for anyone—beginner to experienced programmer—who wants to learn the language rapidly. The logical progression and graduated exercises—designed to provide practice as well as test skill and comprehension—enable the reader to begin writing simple programs almost immediately.

paper, \$16.95
1981, 440 pages, 7 x 9

BEAT THE ODDS: MICRO- COMPUTER SIMULATIONS OF CASINO GAMES

By Hans Sagan.
Here's an extremely useful programming guide that provides realistic simulations of five popular Casino games: Trente-et-Quarante (Thirty and Forty), Roulette, Chemin-de-Fer, Craps, and Blackjack. Each of the five chapters has the same structure. It begins with a computer run, displaying facets of the programs, followed by an explanation of the objectives and the physical execution of the game. Acceptable bets and how to place them are discussed and systems and/or strategies laid out. Finally, the computer program is developed and various modifications of the program are detailed.

paper, \$9.95
1980, 128 pages, 6 x 9

Use the order card in the back of this magazine, or itemize your order on a separate piece of paper and mail to:
99'er Magazine/Book Dept., P.O. Box 5537, Eugene, Oregon 97405. Be sure to include check or detailed credit card information. No C.O.D. orders accepted. Add \$1.50 postage & handling for 1 book, \$2.00 for 2 books, or \$2.50 for 3 or more books. Please allow 4-6 weeks for delivery.
If there is a question regarding your order please write to Customer Service at the above address.
PRICES SUBJECT TO CHANGE WITHOUT NOTICE.

THE PERFECT TEXAS INSTRUMENTS TRADEOFF.


Trade in your current Texas Instruments TI-99/4 Peripheral Accessories to the BACH Company and we'll give you credit towards the New TI Expansion Box and its peripherals.

Or, buy preowned, reconditioned TI-99/4 Peripheral Accessories at a Big savings from the BACH Company. Then, when you're ready,

trade them in for credit towards the Expansion Box System of peripherals.

In either case, be sure to CALL TOLL FREE 800-227-8292. And in California call 415-969-6601 or 415-494-1995 for prices and more

information about this exciting NEW TradeOff to improve your Texas Instruments Computer System.



THE BACH COMPANY

715 ENSIGN WAY, PALO ALTO, CALIFORNIA 94303

Pewterware PRESENTS

UP PERISCOPE

in EXTENDED BASIC


Depth — 60

Speed — 6

Course — 320

Bearing — 310

Range — 3,000



You are the skipper of the USS Porpoise on patrol in the Western Pacific. "Final Bearing Mark — 310 degrees." "Final Range Mark — 3,000 yards." "Fire One!" "Fire Two!" You watch through the periscope just long enough to see two torpedo wakes converge on a 10,000 ton tanker and send it to 'Davy Jones Locker.' "Take 'er deep; right full rudder; rig for depth charge." The destroyer escort has already started looking for you. Written by a 20 year submarine Vet.

UP PERISCOPE \$15 postpaid
(Extended BASIC Only)

Also available (in BASIC):

PEWTERWARE

P. O. Box 503

Gulf Breeze, FL 32561

Dealer Inquiries Invited

Bluegrass Sweepstakes

Challenge Poker

Decathlon

Match Wits

Each \$10 postpaid

TEX-SOFT™ PRESENTS

Beanstalk™ Adventure

Now for the TI-99/4 and TI-99/4A an adventure game based on the classic fairy tale Jack and the Beanstalk where you become the lead character and your moves control your destiny and even may change the course of history.

(The giant might get you)

This is one of a series of quality programs being written or reprogrammed for the 99/4 and 99/4A computers by TEX-SOFT, the TI 99/4A software affiliate of TEX-COMP Users Supply Division.

Send check or Money Order To:
TEX-SOFT Software
P.O. Box 33084
Granada Hills, CA 91344

Minimum Configuration Required.

1. 99/4 or 99/4A console.
2. 1 Disk Drive and Controller. *
3. 32 K Memory Expansion.
4. Extended Basic Module.

*Not available on cassette

\$17.95

Including shipping & handling

Reprogrammed for the 99/4A by George F. Stellen
1985 Calvert Engineering, Inc. TEX-SOFT Division

Send for our free Order Kit — discounts on the entire TI-99/4A product line

DISK DRIVES

FOR YOUR **TI 99/4A**

40 TRACK DRIVE \$239

These are complete drives with power supply & enclosure

DISK DRIVE CABLE \$29.95

(with purchase of drive)

There is a 15 DAY FREE TRIAL ON DRIVES. Warranty 120 days. Add \$5.00 per drive for shipping in Cont. US. UPS COD charge \$1.50.

ORDER NOW!

Write or call. Toll free lines are for ORDERS ONLY! If you need technical information or service call 214/337-4346. We accept VISA/MASTERCARD and COD orders by phone. COD orders will be cash, certified check or money order only. If you order by mail allow 2 weeks for personal checks to clear. Texas residents add 5% tax. All stock items are shipped within 24 hours. We do not charge your credit card until the day we ship.

CALL TOLL FREE

(800) 824-7888, Operator 24

California dial (800) 852-7777, Operator 24. Alaska & Hawaii dial (800) 824-7919, Operator 24.

TOLL FREE LINES FOR ORDERS ONLY

Technical information & service call (214) 337-4346

AEROCOMP

Redbird Airport, Bldg. 8

P.O. Box 24829

Dallas, TX 75224

Eastbench Software Products

Quality software for the
TI-99/4 home computer

INCOME & EXPENSE REPORT FOR NON-PROFIT ORGANIZATIONS (\$36.95)

Provides an income/expense accounting system for a non-profit organization, using the fund accounting method. Up to 100 income and expense categories can be allocated to a maximum of 10 funds. Offers numerous benefits for organizations using manual bookkeeping systems.

STATEMENT ANALYSIS (\$36.95) Data from up to 16 corporate financial statements can be accumulated and stored for reference or modification. Various analyses can be performed; financial ratios and statistics can be derived and fit to various trend curves.

SMALL BUSINESS ACCOUNTS PAYABLE (\$33.95) Creates and maintains a list of open and paid accounts payable containing the following data: vendor number, vendor name, unpaid balance, number for cost allocation, discount expiration date, discount percentage, invoice due date, date of last payment and open, paid, and partially paid status indicator.

BLACKJACK STRATEGY (\$21.95) Allows the serious student of blackjack to analyze various strategies of play and betting in order to improve winnings in actual play. This is not a game but rather a tool which enables the user to experiment with a variety of blackjack strategies.

XBASIC, disk or cassette.

Numerous other programs for astronomy, mathematics and home finance available. For a FREE CATALOG write to:

Eastbench Software Products
1290 Cliffside Drive
Logan, Utah 84321
(801) 753-1084

LEARN TO FLY!



The Dow-4 Gazelle is a simulation of a 4-place, single-engine, high performance aircraft, which will provide fun and challenge as you learn to fly. A high quality program written by a professional programmer/analyst who is also an experienced instrument-rated pilot, the Gazelle is a real-time simulation which responds rapidly to the controls (within one second on the average).

On your screen you see the instrument panel, which has 10 dials with moving pointers and 11 indicator lights. The plane is flown with the joystick, while the keyboard is used to control power, flaps, fuel, etc.

The manual contains 30 pages of text, a glossary, and seven full page figures. It introduces you to the art of flying and leads you, a step at a time, from novice to professional. Learn to take-off, land, navigate, fly instrument approaches, and more. If you get into trouble, you can freeze the action in case you need time to assess your situation. Sound effects add to realism.

This program pushes the TI-99/4(A) to its limits. For both 99/4 and 99/4A, Does not require anything other than a joystick and cassette recorder.

Send \$30.00 to:
John T. Dow
6360 Caton
Pittsburgh, PA 15217

WESTERN-WARE

99/4-99/4A Software

- Accounting
- Financial
- Graphing
- Statistics
- Entertainment

FREE

Brochure and Price List

WESTERN WARE INC.

P.O. Box 53042
Lubbock, Tx. 79453

TITAN... from p.30

```

400 READ CELL :: DIR(CELL1,CELL2)=C
    ELL :: NEXT CELL1 :: NEXT CELL2
410 DATA -3,-3,-3,-3,-2,-1,0,1,2,3,
    3,3,3,3,3,3,2,1,0,-1,-2,-3,-3,-
    3
420 DATA 0,1,2,3,3,3,3,3,3,2,1,0,
    -1,-2,-3,-3,-3,-3,-3,-3,-3,-2,-
    1
430 CALL DELSPRITE(ALL)
440 IF RAM$="N" THEN 460
450 CALL INIT :: CALL LOAD(-31878,1
    )
460 GOSUB 810
470 GOSUB 1050
480 GOSUB 1500
490 REM MAIN CONTROL LOOP
500 CALL KEY(1,A,B):: CALL JOYST(1,
    C,D)
510 CALL POSITION(1,Y,X)
520 IF X+4>256 THEN 660
530 IF Y+8>HGT(X+4)+2 AND Y<192 THE
    N 1660
540 IF A=2 OR C=-4 THEN PNT=PNT-1
550 IF A=3 OR C=4 THEN PNT=PNT+1
560 IF PNT=25 THEN PNT=1 ELSE IF PN
    T=0 THEN PNT=24
570 CALL PATTERN(1,95+PNT)
580 IF RDO=1 THEN 620
590 DISPLAY AT(23,7)SIZE(4):INT(XV)
600 DISPLAY AT(23,21)SIZE(4):INT(-Y
    V)
610 DISPLAY AT(24,20):FUEL
620 CALL POSITION(1,Y,X)
630 RPLY(PST,1)=Y :: RPLY(PST,2)=X
    :: RPLY(PST,3)=PNT+95 :: IF PST
    =25 THEN PST=1 ELSE PST=PST+1
640 IF X+4>256 THEN 660
650 IF Y+8>HGT(X+4)+2 AND Y<192 THE
    N 1660
660 YV=YV+1+1.5*((1/(4-DIF))/2)
670 CALL KEY(1,A,B):: IF A=13 OR A=
    18 THEN 680 ELSE 750
680 IF FUEL=0 THEN DISPLAY AT(22,1)
    : "FUEL SUPPLY IS GONE" :: GOTO
    750
690 XV=XV+DIR(PNT,2)
700 YV=YV+DIR(PNT,1)
710 FUEL=FUEL-1
720 IF FUEL=10 THEN DISPLAY AT(22,1
    ) : "FUEL RUNNING LOW" :: CALL BE
    EP
730 IF FUEL=20 THEN DISPLAY AT(22,1
    ) : "WATCH YOUR FUEL SUPPLY" :: C
    ALL BEEP
740 CALL SOUND(-800,125,28,-7,15)
750 IF ABS(XV)>254 OR ABS(YV)>254 T
    HEN 780
760 CALL MOTION(1,YV/(2-DIF*.25),X
    V/(2-DIF*.25))
770 GOTO 500
    
```

Psychometric
An eight part mental health inventory
Measures which psychological areas (below)
may need further testing:

- PERSONALITY FACTORS
- LIFESTYLE STRESS
- FEAR
- ANXIETY
- MARRIAGE, FAMILY
RELATIONSHIPS
- JOB OR OCCUPATIONAL
DEPRESSION
- NON-FAMILY PERSONAL
RELATIONSHIPS

Offered only as an aid to individual self-awareness; this program does not provide any psychiatric treatment, is not a substitute for professional psychological counseling, nor is it intended as such.

Available only on cassette,
runs on 99/4 or 99/4A

Program with instructions for
interpretation \$8.95

Send cash, check, or money order. Shipped
prepaid anywhere in the U. S. California
residents add 6% state sales tax.

Pablo Diablo,
The legendary evil kiteflier
P. O. Box 4863
Santa Clara, CA 95054
SOURCE ID TCV774

```

780 XV=XV-DIR(PNT,2)
790 YV=YV-DIR(PNT,1)
800 GOTO 500
810 REM TITLE SCREEN
820 CALL CLEAR
830 DISPLAY AT(1,1): "LIFE LINE TO T
    ITAN"
840 DISPLAY AT(3,1): "SELECT YOUR LE
    VEL"
850 DISPLAY AT(5,1): " 1 CADET": " 2
    OFFICER": " 3 VETERAN"
860 DISPLAY AT(9,1): "PRESS ""AID""
    FOR RULES"
870 CALL BEEP
880 CALL JOYST(1,A,B)
890 IF A=0 AND B=0 THEN 920
900 DIF=2-B*.25
910 GOTO 950
920 CALL KEY(0,C,D)
930 IF C=1 THEN 970
940 IF C>48 AND C<54 THEN DIF=C-48
    ELSE 880
950 CALL HCHAR(4+DIF,3,102)
960 RETURN
970 REM INSTRUCTIONS
980 DISPLAY AT(3,1): "YOU ARE PILOTI
    NG A CARGO": "LANDER.YOUR MISSIO
    N IS TO": "TOUCH DOWN ON THE FLA
    T"
990 DISPLAY AT(6,1): "SURFACE USING
    A MINIMUM OF FUEL."
1000 DISPLAY AT(9,1): "YOU MAY USE S
    & D TO ROTATE YOUR LANDER AND
    V TO THRUST,OR JOYSTICK #1.DO
    N'T THRUST"
1010 DISPLAY AT(12,1): "TOO OFTEN-YO
    U'LL RUN OUT OF FUEL.TRY NOT T
    O HIT ANY MOUNTAINS!"
1020 DISPLAY AT(17,1): "PRESS ANY KE
    Y TO GO BACK."
1030 CALL KEY(0,A,B)
1040 IF B<0 THEN 820 ELSE 1030
1050 CALL HCHAR(2,1,32,736)
1060 DISPLAY AT(1,20):N*(DIF)
1070 DISPLAY AT(2,1): "PLEASE WAIT."
1080 LNDSP=INT(25*RND+3)
1090 ROW=INT((10-DIF)*RND+10-DIF)+(
    4-DIF)*1.5
1100 IF ROW>19 THEN 1090
1110 COL=0 :: DOT=1 :: X=1
1120 COL=COL+1
1130 IF COL=33 THEN RETURN
1140 IF COL=LNDSP THEN 1410
1150 OLS=SLP
1160 IF INT(5*RND+1)<DIF THEN 1190
1170 SLP=INT(3*RND-1)
1180 IF SLP=0 THEN 1170
1190 IF SLP=1 THEN 1210 ELSE 1310
1200 GOTO 1120
1210 IF ROW<6 THEN 1310
1220 IF OLS=1 THEN ROW=ROW-1
    
```

Continued on p. 62

DON'T BE A 28-COLUMN WEAKLING!!

Do other computers kick sand in your face because of your puny 28-column display? Well, no longer! Our **DISPLAY ENHANCEMENT PACKAGE** lets you use the 40-column display hardware you didn't know you had!

- 40 x 24 display format
- Multi-screen memory
- Forward and backward scrolling
- Split screen (part fixed and part scrolled)
- Improved display control from the keyboard
- Works with any 99/4 or 99/4A

\$24.95 POSTPAID

Reqs. Memory Expansion, Disk, X-BASIC or ED/ASM
(Cassette version coming soon)
Software developers—write for sublicense agreement

ALSO

SMASH — The program optimizer, requires X-BASIC
Disk \$24.95

Send check or write for more information to:

OAK TREE SYSTEMS
3922 Valentine Road
Whitmore Lake, MI 48189



The only complete processor that **does not** require ram expansion. (Not a typewriter emulator needing extra-cost options). Automatically collects, combines, formats, justifies, paginates, and prints any mix of files. (Address, text, form, etc.)

Fast, powerful editing, processing, & cataloging. Requires: Extended Basic Module, Printer (EPSON, IDS, TI, SC, etc.) & disk drive or cassette. Versions: I = 99/4, II = 99/4A, III = 99/4A + 32K EXP. \$59.95 + CA TAX.

SATISFACTION OR MONEY BACK. Request free info or borrow our VHS VIDEOTAPE!
TEXTIGER, 24433 Hawthorne Blvd.
Torrance, CA 90505. (213) 378-9286



TI-99/4 TI-99/4A

DIRECT WRITER II

our popular original version of this easy to use **WORD PROCESSOR** has been upgraded to match the flexibility of some **DOT-MATRIX** printers while becoming even more convenient for the **DAISY-WHEEL** printer owners.

FEATURES:

"LIVE" EDITING - NO RE-TYPING
32 TO 132 CHARACTERS/LINE
TRUE UPPER & LOWER CASE -
EVEN ON THE 99/4
DISPLAYED ADJUSTABLE
TABULATION

MIX TEXT SIZES WITHIN A LINE:
(printers with GRAFTRAX plus only)

small normal **LARGE**
SUPERScript SUBScript *ITALICS* **DBL STRIKE**

UNDERLINING DOES NOT REQUIRE
BACKSPACING

STORED FILE VIEWING OPTION
PAGINATION OPTION, AUTO STRING
SEARCH/REPLACE ALSO WORKS
WITH PRINTERS NOT HAVING
FORM-FEED FAST, SINGLE-COPY
PRINTOUT OF TEXT OPTION VARIA-
BLE LEFT-HAND MARGIN, AUTO-
CENTER TEXT FULLY SOFTWARE-
GUARDED TO PREVENT TEXT LOSS.
COMPLETE WITH DETAILED
INSTRUCTION BOOK
REQUIRES EXTENDED BASIC,
MEMORY EXPANSION AND DISK
DRIVE SYSTEM.

\$66

MORSE CODE PGM SET

two professional programs which will teach and test you beyond qualification for an FCC license. User controlled tone and speed. Also excellent for classroom testing applications. only basic required, cassette or disk.

\$22

OTHER SOFTWARE AVAILABLE

SEND FOR FREE

CATALOG

OR INQUIRE AT YOUR
LOCAL DEALER

FOR PURCHASES MAIL CHECK OR
MONEY ORDER TO:

**DYNAMIC DATA AND
DEVICES**

**P.O. BOX 912
STAFFORD, TEXAS 77477
(713) 343-0033**

ADD \$2.00 FOR POSTAGE AND HANDLING
TEXAS RESIDENTS ADD 4% SALES TAX

BLOCKADE... from p.31

```
100 REM *****
110 REM * NIGHT BLOCKADE *
120 REM *****
130 REM BY ANTS REIGO
140 REM 99'ER VERSION 2.4.1
150 REM
160 REM
170 CALL CLEAR
180 PRINT "IS THIS RUNNING ON ": :
    1) 99/4A OR 2) 99/4 ?": : : "PRE
    SS (1) OR (2)": :
190 CALL KEY(O,K,S)
200 IF S=0 THEN 190
210 IF (K<49)+(K>50) THEN 190
220 IF K=49 THEN 250
230 KBD=0
240 GOTO 270
250 KBD=5
260 REM ***SCREEN FILL
270 CALL CLEAR
280 DIS=1
290 GOSUB 2830
300 DIS=0
310 TOTSHT=0
320 DIM GRF(14),GRF$(14),SCP(32),R(
    159),CL(159)
330 DATA 136,2996593EFF185492,63,08
    01AA0400558201,33,0000C0FCF8,34
    ,04063FFFFF,35,04063FFFFF,36,04
    063FFFFF,37
340 DATA 04063FFFFF,38,000000FF7F,3
    9,0000000F07,40,0000000301,41,0
    00000001
350 DATA 159,0,158,0000007E7E,42,FF
    FFFFFFFF
360 DATA 3,7,3,31,3,11,3,13,3,15,3,
    19,3,30,3,23,3,25,3,21,3,27,11,
    26,5,26,11,29,5,27,3,26,3,8
370 DATA 3,10,3,12,3,14,3,16,3,18,3
    ,20,3,22,3,24,8,25,8,26,11,25,3
    ,28,11,28,3,29,3,9,8,7,11,16
380 DATA 11,10,8,11,5,10,8,13,8,15,
    8,17,5,20,8,19,8,21,8,23,11,22,
    11,19,5,22,5,24,5,6,5,12
390 DATA 8,9,5,14,5,18,11,13,5,8,11
    ,7,5,16,11,4,3,5,11,3,3,6,3,17,
    3,28,11,31,8,8,11,17,11,11
400 DATA 8,12,5,11,8,14,8,16,8,18,5
    ,21,8,20,8,22,8,24,11,23,11,20,
    5,23,5,25,5,7,5,13,8,10
410 DATA 5,15,5,19,11,14,5,9,11,8,5
    ,17,11,5,8,15,8,9,8,17,5,4,3,8,
    11,27,8,3,11,18,11,12,8,5,5
420 DATA 5,8,6,8,7,8,27,5,28,8,28,8
    ,29,8,30,11,24,11,21,5,29,5,30,
    5,3,5,6,8,4,5,7,5,27,11,15
430 DATA 5,4,11,9,5,8,11,6,11,30,8,
    31,3,29,3,23,3,25
440 DATA 12,12,13,13,14,14,15,15,15
    ,16,16,16,17,17,17,18,18,19,19,
    19,20,20,21,21
```


```
450 DATA 3,3,3,3,11,8,5,3,21,19,17,
    15,0,0,0,6,0
460 FOR X=1 TO 14
470 READ GRF(X),GRF$(X)
480 CALL CHAR(GRF(X),GRF$(X))
490 NEXT X
500 RESTORE 360
510 FOR X=33 TO 159
520 READ R(X),CL(X)
530 NEXT X
540 RESTORE 440
550 FOR X=5 TO 28
560 READ SCP(X)
570 NEXT X
580 CALL CLEAR
590 CALL COLOR(4,11,1)
600 CALL COLOR(5,12,1)
610 CALL SCREEN(2)
620 IF TOTSHT=0 THEN 650
630 GOSUB 2930
640 ON SLXN GOTO 670,740,1520,2770
650 TOTSHT=1
660 GOTO 630
670 IF KBD=0 THEN 3070
680 R(13)=8
690 CL(13)=27
700 REM ***INITIAL VALUES
710 RESTORE 450
720 READ A,B,C,D,T1,T2,T3,T4,SCP1,S
    CP2,SCP3,SCP4,TOTAL,ESC,SHOTS,L
    IM,MIS
730 CALL COLOR(14,10,1)
740 GOSUB 2270
750 GOSUB 2460
760 RANDOMIZE
770 TOTSHT=TOTSHT+SHOTS
780 SHOTS=0
790 REM ***TEST FOR END
800 IF (LIM<1)+(ESC>1) THEN 3450
810 ON INT(RND*2)+1 GOTO 820,830
820 IF (TOTAL>10)*(MIS>0)+(TOTAL>12
    )*(MIS=0) THEN 850 ELSE 830
830 GOSUB 1540
840 IF (TOTAL>5)*(MIS=0)+(TOTAL>20)
    *(MIS>0) THEN 850 ELSE 920
850 ON INT(RND*4)+1 GOTO 860,920,88
    0,920
860 GOSUB 3690
870 GOTO 900
880 GOSUB 3520
890 REM ***DEFENSE CHECK
900 CALL KEY(O,KM,SM)
910 GOTO 3130
920 GOSUB 2610
930 GOSUB 1830
940 GOSUB 2660
950 CALL KEY(KBD,K,S)
960 IF S<>0 THEN 980
970 GOTO 750
980 IF K=32 THEN 1010
990 IF K=13 THEN 610
```

Continued on p. 59

Twenty Questions

with the

Voice of Parsec



An Interview with Aubrée Anderson

HCM It was your voice that was used as the model for the speech synthesis on the Parsec space game. How were you picked to do the recording?

AA Well, actually a friend of mine was supposed to be doing the game; that was Bob Hendren. We just met each other at the first of the week. We got to talking and he mentioned that I had a nice smooth voice. A lot of girls have a pretty high voice, but mine was fairly low, and he asked if I would be interested; that was about it.

HCM Did they tell you why they were looking for a female voice?

AA It was supposed to sound more like a computer, loosely based on the idea that on *Star Trek* there's always a female voice; and they thought that maybe people would relate to it better.

HCM What about the characteristics of your voice? Why was your voice chosen for modeling the synthesis?

AA I don't understand all of it, but the computer has to have a voice within a certain range so that it can pick it up and then reproduce it later. The other girl's voice, for some reason, wasn't being picked up.

HCM Is it more difficult to digitize, to reproduce electronically, a female voice than a male voice?

AA Yes, although I didn't have any problems.

HCM I've heard your voice referred to as one that's "very trainable." Does that mean it's right for the synthesis process?

AA I think they meant that whenever my voice is played back to me through the computer, I can hear if there's anything wrong (like my tendency to pronounce "s" as "th"). Then I can try to shape my mouth differently or move the throat differently. That's what they meant by trainable—I learn really quickly what's wrong.

HCM Let's get into the recording process. What was it like?

AA Well there's a booth, and you just sit down in a chair and speak

into a microphone. They do all kinds of things; you should see the computer. They check the sound levels and try to get any distortion out, and then I just start reading words off the monitor right in front of me.

HCM Do you wear any headphones and do you hear yourself as you speak?

AA No, I just speak into the microphone, and they play it back and let me hear. Then I fix whatever is wrong the second time through.

HCM How long does one of these sessions last?

AA Well, it just depends. The first time, it didn't take too long, about 45 minutes. The second time it took longer—over an hour, I think. After that they got pretty quick. It

ing to take emotion out of the voice?

AA It depends on what the computer programmer asks for. If he wants to be very nasty or chiding, then I'll try to make it that way. And if they want it to be pretty monotone like a computer, then I'll try to do that.

HCM Did you record just for Parsec, or did you record a whole list or storehouse of words that could be used in many different contexts?

AA I just recorded for Parsec, but of course they keep everything on file so they can use it later.

HCM About how many words or phrases did you actually record for Parsec?

AA I'm not really sure—about a page. There were very few long

HCM Have you lived in Texas a long time? Obviously you don't have a southern accent.

AA I was born in North Carolina, but I left there when I was quite young and I've really been living in Texas ever since I was three. The reason I don't have an obvious southern accent is because my father was born and raised in California, and my mother was born and raised in Hawaii.

HCM How do you feel about computer games?

AA They're fun; I've always liked them. I've been playing them ever since I can remember. My father worked at Texas Tech; he had a few games on the computer there, and I used to play with them.

HCM Have you had a chance to play Parsec at all?

AA Yes, as a matter of fact I have. I only played it once. I didn't do very well; I didn't even make it to the refueling tunnel.

HCM How did it feel to hear your own voice in the game?

AA Well, it didn't sound so much like me.

HCM Are you a science fiction buff? Do you enjoy the movies or the books?

AA I am. I liked *The Empire Strikes Back* and also the *Star Trek* film, the first one.

HCM Now that you are the voice of Parsec, do you identify at all with the female computer voice of the Enterprise on *Star Trek*?

AA Well no, there's really almost a million variations. As I remember, on the second movie they even used a male voice.

HCM How do you feel about the fact that soon there may be hundreds of thousands of people who will hear your voice in their own living rooms?

AA I don't know, it's kind of neutral. Maybe if I walked into a house and heard somebody playing it, I'd say "Hey, that's neat."



"...On *Star Trek* there's always a female voice; and they thought maybe people would relate to it better."

took about two hours to record all the speech for Parsec.

HCM Do you have to do things over and over again to get it right for the computer?

AA Yes, you have to enunciate, especially the consonants. You have to pronounce them strongly, otherwise they don't pick up and you lose k's and t's and s's. I usually go through it once, just to hear what's wrong and then start trying to do it right after that. It takes a while; I used to do three or four tapes.

HCM When you record, do you put any emotion into it, or are you try-



ing to take emotion out of the voice?

HCM What did you think of your digital voice in the final implementation of the game?


AA Well it doesn't sound very much like me. They edited it quite a bit.

HCM Let's get into your background a little. Can you tell us something about yourself?

AA Well, I'm a junior at Texas Tech right now, and I'm a major in geology. I don't have anything to do with voices. I've never done oral interpretation or anything like that.



Texas Instruments




at the Winter
Consumer Electronics Show
January 6-9, 1983

Residents of Las Vegas have seen it all—the high rollers, the down-on-their-luck losers, the hype, and the scams. But the most exciting game in town this past January was *not* at the green-felt baccarat tables of the Sahara, the whirling roulette wheels at Caesar's Palace, or the bawdy, smoke-filled atmosphere of the infamous Palamino Club. . .

It was at the Las Vegas Convention Center where the *real* action took place: Over 80,000 eager spectators gathered in this mammoth arena during the week of January 6-9 to witness the clash of the consumer electronics titans. Here, at the Winter Consumer Electronics Show, one Titan clearly emerged victorious in the relentless battle for dominance in the home computer marketplace—receiving accolade upon accolade from the much-impressed crowd. . .

Rising from the convention floor's Aisle 700 was the jet-black, solid-state citadel of Texas Instruments—a magnificent structure over two stories high—a structure that had to be transported to the show on no less than six huge 18-wheelers.

Showgoers couldn't help but be attracted to the gigantic, ebony exhibit with its multi-colored, phosphorescent product displays and quadraphonic, 12-voice, TI-99/4A-driven music synthesizer projecting the theme from *Chariots of Fire*. And once there, they were treated to some astounding advances in consumer electronics technology. . .



At the show, we actually used the TI-99/4A and Personal Record Keeping Command Cartridge with the Wafertape drive.

Although the TI-99/4A Home Computer did not have a whole new line of peripherals introduced expressly for it, the announcement of a particular peripheral from the Milton Bradley Company astonished the trade and press alike. The Milton Bradley *Expander* is one revolutionary product that actually "speaks (and listens) for itself." This plug-in (via the joystick port) peripheral will, for the first time, make voice recognition available and affordable on a popular home computer—the TI-99/4A. The unit comes with a 64-position membrane keypad with overlays for various software Command Cartridges that Milton Bradley will be producing for Texas Instruments.

Included in the package (with a tentative retail price in the \$75–\$100 range!) are a headset microphone for the voice command function, as well as a precision, 3-axis analog joystick. This new peripheral also contains an additional connector for the second joystick, an expansion port for future add-on devices, and both speech synthesis and recognition via the 2-way "Magic Recognizer Chip."

Voice Command Steals Home


Although the TI exhibit contained Milton Bradley's *Expander* peripherals and had the 10 new Milton Bradley game cartridges up and running, it wasn't until we went to Milton Bradley's own exhibit across the aisle that we were able to actually witness human voice recognition in an interactive game. After "training" (repeating into the microphone twice) the *Expander* to recognize each player's pronunciation of the nine

baseball team positions, the player whose team is in the field can throw the baseball around the screen simply by voice commands. Both players simultaneously use the keypad and joystick to manipulate the pitching and hitting. Imagine shouting, "Right," and seeing your rightfielder chase after the ball; then on your verbal command of "Second," having him fire the ball into second base . . .

The Milton Bradley *Expander* and software cartridges are to be distributed exclusively by Texas Instruments. The ten initial game cartridges are: *Championship Baseball*, *Bigfoot*, *Sewer-mania*, *Honey Hunt*, *Soundtrack Trolley*, *Bug Hunt*, *Superfly*, *Meteor Belt*, *Space Bandit*, and *Terry Turtle's Adventure*. Of these ten, we felt that *Championship Baseball* and *Bigfoot* (a "climbing-and-obstacle-avoiding game" à la *Donkey Kong*) had the potential to become real video game hits.

A Spreadsheet Dragon Mix

We finally got to see the *Othello*™ (CBS Toys) and *Alpiner* game cartridges (suggested retail price of \$39.95); the *TI-Count* business software (with each of the six accounting, inventory, or mail list packages at \$99.95); Microsoft's *Multiplan*™ consisting of a cartridge, disk, and 326-page manual in 3-ring binder for \$99.95; and six new educational cartridges from DLM Academics (*Alligator Mix*, *Alien Addition*, *Minus Mission*, *Meteor Multiplication*, *Demolition Division*, and *Dragon Mix*). Texas Instruments also announced first-quarter availability of four Milken packages (*Number Readiness*, *Laws of Arithmetic*, *Equations*, and *Measurement Formulas*), and two new Scott Foresman packages (*Numeration I and II*). During the second quarter of 1983,



TI will add Addison-Wesley's *Computer Math Games* (I, III, IV) to the previously announced *Math Games* II and VI.

From Plato to the Stars


The PLATO educational software was finally demonstrated at the show. TI color monitors treated showgoers to a preview of the initial package, a Basic Skills survey (at a suggested retail price of \$49.95) that allows parents and teachers to help select appropriate courseware for individual needs and skill levels. [For a discussion of PLATO, see *99'er Magazine*, January 1983—Ed.]


TI also introduced (under license with Westinghouse Learning Corporation) a new software package for people who want to learn conversational Spanish. This package, *Key to Spanish*, consists of a 3-ring binder containing 4 Command Cartridges for the TI-99/4A, 4 audio cassettes, and an instruction manual. The audio cassettes are controlled by the cartridges, helping beginners to pronounce Spanish in conjunction with the lesson plans. The suggested retail price of the package is \$149.95.

We also saw a new peripheral that will prove useful with the above language cassettes, as well as with program and data files (both user-written and commercial products). The TI Program Recorder with suggested retail price of \$69.95 is optimized for use with the TI-99/4A and TI-99/2 computers. The recorder has color-coded input jacks and a digital tape counter, among other features. It comes with a computer interface cable for the TI-99/4A. (The TI-99/2 comes with its own interface cable.)

Although announced in the show's product literature, the two entertainment software packages that probably would have been the most interesting weren't ready in time for exhibition. We'll just have to wait a little longer to see if our friend, *ET*, actually goes home, or if the *Battlestar Galactica* ever finds Earth.

Watch for more detailed coverage of all of the new TI products starting with the March issue.






DEBUGS ON DISPLAY

99'er Program Bug

LISTING #1 (SEGMENTED) SCREEN DUMP PROGRAM FOR MINI-MEMORY BY PATRICIA SWIFT 99'ER VERSION 2.1.2

ADDR	LABEL	OPCODE	OPERANDS	COMMENTS
7D14		MOVB	@>9802,@S1	GET MSB OF GROM ADDR INTO S1
		SWFB	@S1	
		MOVB	@>9802,@S1	GET LSB OF GROM ADDR
		SWFB	@S1	
		DEC	@S1	CORRECT FOR AUTO-INCREMENT
		LI	0,>1D00	
		LI	1,FD	
		LI	2,36	
		BLWP	@>602B	WRITE PAB TO VDP RAM
		LI	6,>1D09	
		MOV	6,@>8356	POINT TO DEVICE NAME LENGTH
		BLWP	@>603B	DSRLNK TO OPEN PRINTER
		DATA	8	
		LI	10,>0400	<<*** changed instruction ***>>
		MOV	10,@>7DEA	<<*** changed instruction ***>> <<*** deleted instruction ***>>
7DS2		LI	0,>1D00	
.
.
.
7DD2	L1	INC	3	POINT TO NEXT INPUT BYTE
		SRA	6,1	/2
		JGT	L2	DO NEXT BYTE, IF MORE
		SWFB	4	PUT OUTPUT BYTE IN MSB OF R4
		MOVB	4,@DO(8)	STORE AT DO
		INC	8	POINT TO NEXT BYTE OF DO
		SRA	5,1	/2
		JGT	L3	CONSTRUCT NEXT OUTPUT BYTE
		LI	0,>1D05	
		LI	1,>0000	<<*** changed instruction ***>>
		BLWP	@>6024	PUT LENGTH OF 4 IN PAB
		LI	0,>1E00	
		LI	1,E1	
		LI	2,4	
		BLWP	@>602B	PUT ESC K SEQ. IN DATA BUFF
		LI	6,>1D09	
		MOV	6,@>8356	POINT TO DEVICE NAME LENGTH
		BLWP	@>603B	DSRLNK TO WRITE ESC K SEQ.
		DATA	8	
		LI	10,>0000	<<*** changed instruction ***>>
		MOV	10,@>7DEA	<<*** changed instruction ***>> <<*** deleted instruction ***>>
		LI	0,>1D05	
		LI	1,>0B00	
.
.
.
7E7B		LI	10,>0400	<<*** changed instruction ***>>
		MOV	10,@>7DEA	<<*** changed instruction ***>> <<*** deleted instruction ***>>
7EB2	L4	JMP	L0	DO NEXT SCREEN CHARACTER
		LI	0,>1D00	COME HERE WHEN FINISHED DUMP
.
.
.
7ED2	PD	DATA	>0012,>1E00,>FF00,>0000,>001A	
*			PAB DEFINITION	
		TEXT	'RS232.PA=0.DA=8.BA=9600.CR'<<***change***>>	
*			DEVICE NAME	
7EF6	CR	DATA	>0D0A	CR LF
7EF8	E1	DATA	>1B4B,>FF00	<<*** changed line ***>>
*			ESC K GRAPHICS SEQUENCE	
7EFC	S1	BSS	2	SAVE AREA
7EFE	E2	DATA	>0D1B,>410B	
*			CR AND ESC A VERT SPACING	
7F02		END		

A Screen Dump Utility



After working with **Super Language: A Screen Dump Utility—Part 2** in the November 1982 issue, we came up with an improvement that we just had to pass along. The changes shown here, in the segments of **Listing #1** from that November article, cause the screen dump program to write one full screen line at a time to the printer. This really speeds up the dump and reduces the printer-head motion.

The original DEBUGs for Screen Dump which appeared in the December 1982 issue on page 40 should be ignored. The File Descriptor *should* be:

RS232.PA=0.DA=8.BA=9600


That part of the Screen Dump corrections having to do with an error on page 24 of the November issue (column 2 under **Mini-Memory Considerations** Step 5) should read as follows:

5. Put the entry point for DUMP into the DEF/REF table by entering the following lines:

```
AORG >7FE8(CR)
TEXT 'DUMP' (CR)
DATA >7D14(CR)
```

Note: There are 2 spaces required following the word DUMP in the above TEXT directive for a total of 6 characters within the apostrophes.

Tex-Scribe



A DEBUG in the **Tex-Scribe** article occurred on page 16 of the December 1982 issue. Regarding **Table 2 "TI-99/4 Impact Printer Mode Commands,"** it was brought to our attention that the TI printer does not have an *Italics* mode. . . We designed that table using an *Epson MX-80 with Grafrax option* and mislabeled it. . . If you have the TI-99/4 Impact Printer, refer to your owner's manual for the available mode commands.



Vectors in LOGO: of Stars and Sprites

By Richard Bies

217 Park Entrance Dr, Pittsburgh, PA 15228

Vectors. Somewhere along the line toward an education—and certainly in the study of physics—the student encounters a mathematical concept called the vector. A vector is a quantity specified by magnitude and direction—as opposed to a quantity without direction, usually called *scalar*. An example of a vector is *velocity* (as the term is used in physics) which quantifies both speed and direction.

People analyze vectors intuitively while driving cars, hunting, or in other sports—but few apply mathematical solutions. For instance, when driving a car, you intuitively reduce speed as you change direction. The amount of speed reduction will depend on the amount of change in direction.

Our schools usually teach physics with the scalar approach until the second year of college, by which time the student may see vectors as strange and somewhat unworthy of belief. Nevertheless, vector analysis is the gateway to much of modern technology.

Within the traditional framework, schools were not necessarily remiss in postponing vector concepts. Most students would never have a need for formal vector analysis, which used to require trigonometry and/or pythagorean calculation.


Why are vectors so important? Simply, they are intrinsic to modern technology. They're what space travel is all about—the cornerstone of future developments.

Back to Basics?

We are at a profound turning point in human history. Our present explosion of electronically-processed information will have an impact comparable to that of the printing press in the Renaissance.

Unfortunately our capacity to meet technology's challenge is being threatened by a movement in education known as "back-to-basics." This movement, reduced to practice, defines the ideal of education as whatever was done thirty or more years ago. It seems both fitting and ironic that these educators, who are concerned with literacy but limited in vision, have chosen as their battle cry the old illiterate alliteration, "Readin', 'Ritin'" and "Rithmetic."

As computers take over more and more tasks in the workplace, we frequently hear the quip, "You can be replaced by a machine." It is the responsibility of the educational system to prepare students so they can work *within* this new technological environment. But if the back-to-basics bunch gets its way and only basic arithmetic is taught, our students will have already been replaced by machines! It is absurd to suggest that a "mathophobic"



Introduction

LOGO Times is an information resource for anyone interested in participating in the creation of their own *personal language*—one that will easily allow them to communicate with a computer in a totally new audiovisual realm of applied imagination, exploration, and self-discovery. The articles on these pages concern the use of the new TI LOGO language, but readers do not need any additional software or equipment (or even a computer) to understand and learn from the material presented here.

If readers want to actually *experience* a TI LOGO environment, they will need either a TI-99/4 or TI-99/4A computer, the Expansion Memory peripheral, and TI LOGO Command Cartridge. A disk drive, although convenient to have, is *not* required; a user's work may alternately be saved on cassette tape, printed out on the TI Thermal Printer, or hand copied into a notebook (for later re-keyboarding).

In each issue, one or more of the articles may reference or build upon the topics discussed in a previous article. It is therefore recommended that for maximum benefit and understanding, new readers obtain the appropriate back issues of *99'er Home Computer Magazine* containing *LOGO Times* articles.

NOTICE

LOGO Times is actively soliciting articles. Manuscripts should be typed double-spaced, and accompanied by a cassette tape or disk if containing any lengthy procedures or graphics.

Send all materials to:

LOGO Times Editorial Dept.
99'er Home Computer Magazine
1500 Valley River Dr., Suite 250
Eugene, OR 97401

All mail directed to the Letters-to-the-Editor column (*Letters on LOGO*) will be published in accordance with the conditions set forth on *99'er Home Computer Magazine's* Masthead page.

Our Contributing Editors

Henry Gorman, Jr.
Department of Psychology
Austin College
Box 1584
Sherman, TX 75090

Roger B. Kirchner
Department of Mathematics
Carleton College
Northfield, MN 55057

LOGO Times is a trademark of
Emerald Valley Publishing Co.

struggle through arithmetic is a necessary prerequisite to higher mathematical thinking. After all, Einstein dropped out of basic arithmetic, but he managed to grasp a few of the principles of higher mathematics!



Because we face this backlash in education,¹ I cannot overemphasize the usefulness of TI LOGO for students coping with today's problems. Let me clarify this point by showing how well LOGO uses vector concepts.

A vector can be perfectly represented by a sprite. It has a given speed, in a given direction. With sprites, the vector's properties are graphically displayed on the screen. Through the use of TI LOGO, students can handle vectors at an early age, instead of waiting for high school or college.

For perspective, let us retreat for a moment to pre-sprite days: As vectors are both quantity and direction, their manipulation requires accounting for both. It doesn't work just to add the quantities and the directions.

The use of a direction implies a frame of reference, or coordinate system, which defines the vector. Typically the coordinate system is Cartesian, with an origin (0,0) on x and y axes. In Figure 1, the vector is graphically represented as an arrow with its length as the quantitative value.

The first step in manipulating the vector is to break it into components V_x and V_y along the two axes, that is with V_x and V_y related to the vector V as the sides to the hypotenuse of a right triangle. In Figure 2, it can be seen that if V_x and V_y are rearranged, they do indeed form a closed triangle:



Alternatively the vector V is called the "resultant" of the two components. The tricky part is that getting the components from the vector requires the calculations:

$$V_y = V (\text{quantitative value}) \times \cos \theta$$

$$V_x = V (\text{quantitative value}) \times \sin \theta$$

or the vector from the components:

$$V = \sqrt{V_y^2 + V_x^2} \quad \arctan \frac{V_x}{V_y}$$

Note that I have used the angle from the y axis, rather than from the x axis as is often the case. I do this because the screen display defines "up" as North or 0°. Thus the angles in the LOGO display are measured from North, or the y axis. This may seem simple for engineers, but it's not elementary school arithmetic.

The LOGO Approach

Back to the present: What happens to these arcane calculations in TI LOGO? When you start a sprite, giving SETSPEED and SETHEADING you define the vector (quantity and direction). Then simply enter PRINT XVEL and PRINT YVEL and, there

you have it, the x and y components displayed! Enter SXV (quantity) and SYV (quantity) and the vector is defined, while PRINT SPEED returns the resultant, and PRINT HEADING returns the direction. The power of this advanced concept is made available to the child without all the arithmetic computations.

Furthermore, adding vectors by components is simple:

SXV (XVEL + (quantity))

SYV (YVEL + (quantity))

Not only does SPEED and HEADING then return the vector result of the addition, but the effect is seen on the screen as well.

To add vectors directly does require a procedure, but it can be a simple one. Give the speed and direction to a second higher-numbered sprite (perhaps transparent), name its XVEL and YVEL, and pass the parameters to the lower-numbered sprites:

```
TO ADD
CS
PRINT [X & Y COMPONENTS:]
PRINT NUMBEROF XVEL
PRINT NUMBEROF YVEL
MAKE "A XVEL
MAKE "B YVEL
VECTOR :A :B
END

TO RESOLVE
TELL 2
CARRY :BOX
SC 0
HOME
PRINT [ENTER THE SPEED AND HEADING]
PRINT [THEN ENTER ADD]
END
```

```
TO VECTOR :A :B
TELL 1
CARRY :BALL
SC :RED
HOME
SXV XVEL + :A
SYV YVEL + :B
PRINT [RESULT:]
PRINT [SPEED =] PRINT SPEED
PRINT [HEADING =] PRINT HEADING
RESOLVE
END
```

```
TO VECTORS
CALL 0 "A
CALL 0 "B
VECTOR :A :B
END
```

I will leave it to someone else to work out the multiplications (dot product and cross product).

Students who write programs in the *sprite mode*, will gain an intuitive understanding of vectors. These young people are growing up with the information-handling power of the computer at their fingertips, and they will live with a view of themselves from outside the world. They will have the power of the stars in their hands...

¹For a view of mathematics today, see a booklet entitled *Agenda for the 80's* published by the National Association of Teachers of Mathematics. This publication recognizes that calculators and personal computers do exist, and that skill in hand manipulation of large numbers is no longer "basic."

DAISIES:

Math Flowers With LOGO

By Roger B. Kirchner

Contributing Editor

TI LOGO is a powerful language. Although it does not have floating point arithmetic, that capability can always be simulated. TI LOGO can have SIN and COS. One need only take advantage of the sprites.

The graph of the polar equation $r = A \cos(n\theta)$ will serve as our example. The graph is obtained by interpreting PHI as degrees from the vertical measured clockwise, and R as the distance from the origin in the direction of heading PHI. The graph is a circle when $n = 1$, has n loops when n is odd, and $2n$ loops when n is even. When filled in, the loops look like petals of a daisy. One might not suspect that these daisies can be graphed in TI LOGO, but try the following:

```
TO DAISIES
CS
CB 1
MAKE "N RANDOM + 1
TELL TURTLE
SC RANDOM + 2
MAKE "SIZE 45
TELL 0 SS :SIZE
TELL 1 SS 100
TEST :N / 2 * 2 = :N
IFT MAKE "ST 360
IFF MAKE "ST 180
PETAL :N 0 :ST
WAIT 120
DAISIES
END
```

```
TO PETAL :N :PHI :STOP
TELL 0
SH :N * :PHI
MAKE "R YVEL
TELL TURTLE
HT
HOME
SH :PHI
FD :R
IF :PHI = :STOP THEN STOP
PETAL :N :PHI + 1 :STOP
END
```

Typing DAISIES will graph a randomly colored daisy with 1, 3, 5, 7, 9, 4, 8, 12, 16, or 20 petals. After a two-second display of the daisy, another will be started. The procedure must be stopped with FCTN 9. Then enter CB 7 to change the screen from a black color back to cyan. The value of

STOP will be 180 for :N odd, and 360 for :N even. (What if :STOP were equal to 360 for all cases? What would you observe?)

The value of R in DAISY is the y-component of the velocity of sprite 0, which had its speed set to 45 in DAISIES. (Different sized daisies can be graphed by changing the value of SIZE. But if :SIZE is much larger than 45, the daisies will wrap around to the top of the screen.) Since its heading is set to :N*PHI, the value of its y-component is $45 \cdot \cos(N \cdot \text{PHI})$. The daisy drawn thus has outline $R = 45 \cdot \cos(N \cdot \text{PHI})$.

The following procedures compute $A \cdot \cos(X)$ and $A \cdot \sin(X)$ (:X in degrees.)

```
TO COS :A :X
TELL 0
SS :A
SH :X
OUTPUT YVEL
END
```


```
TO SIN :A :X
TELL 0
SS :A
SH :X
OUTPUT XVEL
END
```

This method for computing SIN and COS can be understood by reviewing the LOGO commands having to do with motion.


SH n	sets heading of active sprite(s) (or turtle) to n degrees clockwise from the vertical.
HEADING	returns the heading of active object.
SS s	sets speed of active sprite(s).
SPEED	returns speed of active sprite(s).
SXV xv	sets x-component of velocity to xv.
XVEL	returns x-component of velocity.
SYV yv	sets y-component of velocity to yv.
YVEL	returns y-component of velocity.

The fundamental relationship is:

$$\text{SPEED}^2 = \text{XVEL}^2 + \text{YVEL}^2$$



Consider the case in which HEADING is between 0 and 90 degrees. Then XVEL and YVEL are positive, and we can visualize a triangle with hypotenuse SPEED and sides XVEL and YVEL:



From the definitions of COS and SIN, we see that:

$$\cos(\text{HEADING}) = \text{YVEL} / \text{SPEED},$$

$$\sin(\text{HEADING}) = \text{XVEL} / \text{SPEED}.$$

Thus:

$$\text{YVEL} = \text{SPEED} \cdot \cos(\text{HEADING}),$$

$$\text{XVEL} = \text{SPEED} \cdot \sin(\text{HEADING}).$$

SIN and COS are defined so that these relations are true for all values of HEADING. Indeed, the purpose of SIN and COS is to make these relations hold. (The math textbook definition looks a little different, but that is because it measures angles counterclockwise from the horizontal, and we are measuring them clockwise from the vertical.)

This method does have a restriction which must be kept in mind: the sprites can have a speed no greater than 127. In DAISIES, the speed of sprite 0 was set to 45, but could not have been greater than 127. This means that the maximum length a petal can be is 127.


After enjoying DAISIES for a while, the reader may want to review the construction of the DYNATURTLE (Vol. 1, No. 4, pp 66-67.) The secret of the TI Dynaturtle is the use of sprites to compute sine and cosine.

99'er

TENEX™ is

#1

The largest selection anywhere of software, hardware, and accessories exclusively for the Texas Instruments family of personal computers.



- Over 500 programs for entertainment, education, business, home management, etc. from TI and quality independent producers:

American Software
Dynamic Data
Easyware
EduCAitor
Futura
Extended
Harvey
Headwind
Instant
Pewterware
Prof. Microware
Program Design
Republic
Simulsoft

Kuhl
Letcher Offshore
Linear Aesthetic
Maple Leaf Microwave
Microcomputers Corp.
Micro-Ed
Norton
Not-Polyoptics
Oak Tree Systems
Softcom
Tomputer
W. R. Wilson
AND MORE!

- Dozens of hardware and accessory brands, including:

GE Data Recorder
WICO joysticks
Smith-Corona and Epson printers

Panasonic
Tandon Disk Drives
3M Recording Supplies

and more, plus TI's complete line!



- Useful accessories—covers, cables, furniture, graphic design pads, and more!

SOFTWARE AUTHORS:
Tap the huge
TI market thru TENEX.
You or we produce.

**BEST TECHNOLOGY!
GREAT PRICES!**

Modem
+
THE SOURCE
\$ 139.00

TENEX. P.O. Box 6578, South Bend, IN 46660, 219/277-7726

SEND FOR THE CATALOG TODAY



I WANT VARIETY WITH QUALITY AND PRICE!!!
Enclosed is \$2.00 for your catalog*

NAME _____
ADDRESS _____
CITY/ST. _____
ZIP _____

MAIL TO: **TENEX.**, Box 6578, South Bend, IN 46660
*add a \$3.00 Credit to my first order.

Adventuring... from p.26

ject is still present, then you haven't left the room. Conversely, if the object isn't present, *you are in another room!* By dropping a few more objects and moving around, you can probably get out. What if you weren't carrying anything when you entered the room? Just restart the game (you *did* save it, didn't you?) at a point before you got lost, and pick up as much inventory as possible.

Computer Messages as Clues

When you try things that don't work out, pay attention to the computer's messages. They themselves may be clues. For example, a response like "THAT'S BEYOND MY POWER TO DO" means the thing is impossible. On the other hand, a message of "I CAN'T DO THAT... YET" means that you are on the right track but are missing some vital object (where did you drop that shovel?...you need it now!), or you neglected to do something (did you feed the piranhas?), or maybe you are in the wrong room (where is that map anyway?). Figure out what's wrong and then try it again.

The wording of a response can be significant. If you say HIT door and get the message "I DON'T KNOW HOW TO 'HIT' SOMETHING," it means that HIT is not a good word. If the message is "ITS IMPOSSIBLE", or something like that, it means that the word HIT is good, but not in this context. Write it down because somewhere or other you will probably have to HIT something.

Two messages are essential for all Scott Adams adventures in which you search for treasure. The first one tells you how to score points for finding the treasure, where to bring the treasure and what to say when you find it. Until you see this message, just save any treasure in a convenient location. The second message tells you how many treasures you are supposed to find. Sometimes you are not told outright how many different treasures there are. You have to figure it out. When you score a treasure, you learn how many points it is worth. Each is usually worth 100 divided by the number of treasures, so a treasure worth 6 points means there are 16 in all.

These rules should help you survive, but in a truly good adventure game you will still need that razor-sharp intellect!

Writing Your Own

Now, for those of you who want to try writing an adventure, I have a few rules you might follow. Who knows, you may be able to get it published in *99'er Magazine!* Just pay attention—this could be the break you need to get into print!

First, think of your scenario. Decide where and in what time period the adventure will take place. Once you decide, stick to it! Don't do anything out of context for the time and place you selected—for example, no ray guns in 19th-century London.

Set up a theme. Decide what the adventurer is ultimately supposed to do. Is he to locate treasure? Maybe the idea is to catch Jack the Ripper? Perhaps to escape a locked building? Find a princess? How about saving a Mad Scientist's daughter?

Continued on p. 66

* CORONA DEL MAR, CA 92625
26 WHITEWATER
CORN SOFTWARE
FOR FREE CATALOG:
• ENTERTAINMENT
• EDUCATION
• BUSINESS
• APPLICATION
TURN YOU UPSIDE DOWN!
QUALITY SOFTWARE WILL
OUR LOW PRICED HIGH
SOFTWARE FOR TI-99/4(A)
© 1982 CORN SOFTWARE
SOFTWARE
CORN

Chuck-A-Luck . . . from p.27

version, and lines 2750-3020 in the Extended BASIC version. For TI BASIC, this consists of a simple loop which displays at LOC_X and LOC_Y the appropriate DICE_PIP for each of the nine pieces. After the character on the last die is displayed, I wait a little while and then leave the routine.

Notice that in order to highlight the dice roll routine, I changed the color of the screen and added a little music. My "music jar" of melody listings borrowed from other programs gave up only one piece that remotely matched up with gambling, the "call to the post" tune played at the track just before a race. Perhaps you have a more fitting musical phrase.

The sprite version of the display routine is more complex than the HCHAR version. I will go through it very carefully because Ron has some great ideas about controlling sprites. Note that this routine was written with multiple statements on each line. This has to be done to make your BASIC code run as fast as possible when handling sprites. Slow code at this point could make it very difficult to handle them smoothly.

Graphic Routines

If you have an interest in designing Extended BASIC programs with sprites, tracing through the following program will put you well on your way toward your own creative endeavors. All line numbers from this point on will refer to the Extended BASIC version only.

2750-2820 This code figures out the sprite number for each character of the die being displayed, and starts it out as a sprite with a random motion. Note that this motion can either be positive or negative so that we get them flying in all directions. We also set the LOC value for that character to zero, to show that we haven't yet moved the character back to its final location.

2840-2920 This routine uses a variable called CNT to keep track of the number of characters moved back to their starting locations. If this number is low enough, we

TI 99/4A Arcade Games

Laser-Blaster(X-BASIC)
Hit and Run
Super-Munch
Poultry Pusher (X-BASIC)
Crazy Kong (X-BASIC)
Air Combat (X-BASIC)

*\$17.50 each, plus \$1.50
postage and handling for
each order, pre-paid
(cassettes only, no disks)*

N S Y Software

141-20 70th Road
Flushing, N.Y. 11367

will randomly choose the character we work on. If CNT is 21 or greater, however, we won't choose the character randomly. We'll just look through the LOC array sequentially to find the first character that we haven't yet moved back to its location (i.e., its LOC has a zero in it).


Why is Ron going through the trouble of doing it this way? The answer requires a little thought. Suppose we just randomly kept choosing a figure. By the time 20 or so characters have been reset to the final location, the odds on randomly selecting a good character will then be 7/27 or 26%. The odds on the next selection being a good character will then be 6/27 and they keep getting smaller and smaller. With one character left, the odds on hitting it randomly are 1/27 or less than 4%. As you can see, it is very unlikely that you will hit a good character when only a few are left. To prevent a long wait until the computer randomly locates a good character, he set up his code so that the last 7 or so sprites will not be randomly chosen. Of course, he is also checking CNT to see if he has finished with all 27 characters.

2930-2980 This part of the routine takes the selected character, changes its color to black (to highlight it on the screen while we play with it) and freezes it momentarily. That is what the CALL MOTION(#1,0,0) is for. The major problem in sprite handling is that they keep moving at a pretty high speed, while BASIC keeps plodding along with old data. Ron prevents this problem by freezing the sprite before finding its location. This means that he gets accurate data via the CALL POSITION code.

After locating the sprite, he computes the velocities needed to move it back to its original (and final) location. The Extended BASIC reference manual talks about row velocities and column velocities, but what it doesn't explicitly tell you is that you can control the direction of the sprite. For example, to move at a 45 degree angle, both the row and column velocities must be equal. To move at a 30 degree angle, just make the column velocity equal to twice

Continued on p. 52

NORTHERN LIGHT SOFTWARE



KING TUT'S TOMB

3D color maze, 4 levels, hidden pitfalls, 7 full chambers, bonus coffins and TUT'S ghost. *(K/J)

JELLYBEANS

Can you put your patch in the conveyor belt's holes and keep the jellybeans from falling? 100 variations. *(K)

TRI-LIGHT

Combo computer/board game, 2 - 4 players (including computer), 3 levels, includes gameboard and 49 pieces. *(K)

AND MANY OTHERS

cassettes \$14.95 each


diskettes \$19.95 each

*Console basic **Extended basic
(K) Keyboard (J) Joystick
money orders or
certified cheques preferred

NORTHERN LIGHT SOFTWARE

P.O. BOX 11982
EDMONTON, ALBERTA
CANADA T5J 3L1

T.I.TOAD



Maneuver T.I.TOAD across 4 lanes of heavy traffic then through swift river currents to reach his home. But watch out! The river is full of surprises. Different colorful animated characters appear at each new level making this one of the most exciting games ever for the 99/4(a).

Written entirely in assembly language and comes complete with it's own high speed disk loader that's more than 10 times faster than the extended basic loader.

\$29.95

Full money back guarantee! If you are dissatisfied with this program for any reason, return it within 5 days for a full refund.


Equipment required: memory expansion, extended basic disk drive (joysticks optional).

Software Specialties, Inc.
Box 18051, Denver, CO 80218

* Ad placed this way on advertiser request.

FREE SPEECH SYNTHESIZER
FROM TI with purchase
of 6 MODULES!

TEXAS INSTRUMENTS



TI-99/4A

includes console, R.F. Modulator, and
Manuals

\$319.00 reg. price
-\$100.00 TI REBATE

\$219.00 FINAL COST

ASK ABOUT OUR

- **Dual RS232 Y-Cable**
- **Half Size P.E. Box Drives**
- **ARTHROPOD Assembly Language
Arcade Game**

Mastercard or Visa by mail or phone.
(add 3% charge fee)
Mail cash, check, money order.
Personal check (1 add'l. week to clear)
\$3.00 Shipping & Handling

Equipment subject to price change
and availability without notice.

Peripheral Box	199.97
Speech Synthesizer	109.97
Telephone Modem	164.97
RS 232 Interface Card	139.97
Disk Controller Card	199.97
Disk Memory Drive	369.97
32K Expansion Card	299.97
P-Code Card	199.97
10" Monitor	369.97
Joy Sticks (pair)	27.49
Mini-Memory	78.49
Expansion Box Disk Drive	299.97

Extended Basic	75.00
Household Mgmt.	31.49
Personal Rec. Keep	38.97
Early Learning Fun	23.49
Add Sub I or II	31.49
Video Chess	54.97
Tunnels of Doom	46.97
Car Wars	31.49
TI Invaders	31.49
Tombstone City	31.49
Munch Man	31.49
Yahtzee	19.49
Parsec	31.49
Adventure Cassette	38.97
Editor Assembler	77.97
Terminal Emulator II	38.97

TOLL FREE 1-800-441-7419

in Pennsylvania
1 - 412 - 935-2040

NORTH HILLS COMPUTER

— a subsidiary of DigiCom Systems Corporation —

1016 Madison Avenue, Pittsburgh, PA 15212

HERE'S ANOTHER
NEW GAME FROM

THE GREAT WHITE NORTH SOFTWARE COMPANY

Fly your supply transport
from base to SNOWBIRD VII and
return as Skalian drone ships
try to destroy you.
Become one of the.....

HOSERS IN SPACE

- ♦ Cassette software for your
TI-99/4A computer
- ♦ Play against the computer
or a friend?
- ♦ Extended Basic graphics
- ♦ Color, animation & sound
- ♦ Joystick controlled

YOURS FOR ONLY \$11.95 (U.S.)
IN CANADA SEND \$14.95

Ontario residents add 7% sales tax.
Send Cheque or Money Order to:
CJMF SERVICES
P.O. Box 2336, Station B,
Kitchener, Ontario
CANADA N2H 6M2

All orders are Post Paid.
No C.O.D. orders accepted.

★ SNOWBIRD VII program still
available - same low price! ★

Chuck-A-Luck... from p.51

the row velocity. Ron is using this fact in statement 2960 to figure out how far the sprite is, vertically and horizontally, from where it is supposed to go. He calculates this in MY and MX respectively. He then adds the two to get a value called TOT. The distances can be positive or negative depending on the sprite's location relative to its final position—left or right, above or below.

In order to get a good value of TOT, we have to ignore the signs of the distances. In other words, we don't care if the number is positive or negative, as long as we know its *absolute* value. We find it with the ABS function. By making the row and column velocities a function of both the distance it has to go (MY or MX) and the TOT value, the sprite can be directed to travel in the right direction. Take a look at the last statement in line 2960. It uses the MAX function available in Extended BASIC. TOT must be a reasonable size number, because we will divide MY and MX by TOT to get our velocities. Since it is possible for the sprite to be right where it should be, TOT can be zero. If you divide by 0, however, your program will stop with an error. To make sure that TOT has a value of at least one, you would normally code in something like this:

```
xxxxx TOT=ABS(MX)+ABS(MY)
yyyyy IF TOT<1 THEN TOT=1
zzzzz
```

This can be done just as easily with the MAX function which gives me the higher

of the two alternatives. If one is greater, it will return me a 1. On the other hand, if the result of the addition is greater than 1, it will return that number to me. Using the MAX function eliminates the need for an IF statement right in the middle of my code. MAX (along with its cousin, the MIN function) is a handy feature of Extended BASIC that can save you a lot of coding trouble. We now use the values that we just computed to set the sprite moving again using a CALL MOTION.


2990-3010 I have also set a new variable (my, we are collecting a whole slew of them now!) called CHK to be equal to zero. This counter will be used to make sure that we don't try the next lines of code more than 10 times before we give up and refigure a new MOTION command. If we haven't tried it more than 10 times, we do a CALL COINC to see if the sprite has reached its goal. If not (HIT=0) we go back and do it again. If the sprite has reached its final location, Ron stops it with a CALL MOTION, and does a CALL LOCATE to make sure it is being stopped exactly where he wants it. This is necessary because a sprite that keeps moving between the CALL COINC and the final CALL MOTION may no longer be in the right spot. He changes the color back to white.

3020-3920 This code checks to see if we finished all the characters, and restarts the process if we haven't. It then changes the screen back to green. It also issues a CALL DELSPRITE which clears the sprite characters from the screen.


Ask for our Free Brochure outlining these and many other exciting T199/4(A) compatible programs.




Colorado seems pretty easy.
But...
**CROSS COUNTRY
CAR RALLY**\$12.95




Where are the energy pellets
when you need them.
ATTACK-MAN\$12.95




Incorporate music into your own
programs easily.
MUSIC SYNTHESIZER ...\$12.95



The easy way to draw
hi-resolution graphics.
GRAPHICS PACKAGE ...\$16.95




Guaranteed to make you croak!
SUPER FROGGER\$14.95



"This is most illogical captain".
Save the Federation!
3-D STARTREK\$10.95



Abort, Abort, FCN = ...oops!
LUNAR LANDER\$10.95



Take your aggression out on the
computer or an opponent.
TANK\$10.95

ATTACK-MAN, CROSS COUNTRY CAR RALLY, SUPER FROGGER and GRAPHICS PACKAGE are available only in Extended Basic. All other programs are available in either console or Extended Basic. Joysticks are not needed for any program. You have the option in many programs to use Joysticks or the keyboard.

Please add \$2.00 shipping for orders
containing less than 3 programs.
Special offer 20%
discount for 3 or more programs.



Send cheque, money order or charge number
and expiry date to:
NORTON SOFTWARE
Box 575, Picton, Ontario
K0K 2T0

Save Shipping Charges, many dealers now
carry the full Norton Software line of products.

DEALER INQUIRIES WELCOME



Protection and Improvement

We have now finished the Extended BASIC version of the code. Our game gets a final debugging and is ready to go! The next step is just some administrative work to make sure that your effort will not be in vain. First, change the REM statement at the beginning of the program so that it says FINAL VERSION as well as the version number. Next, save it on cassette tape or disk. Label the tape or disk with the name of the program, the date, and the version number along with the words FINAL VER-

SION. Make two copies. If you are saving on tape, make one copy on each side and verify both. Then make another copy on a backup tape. You should always have a backup tape kept separately from your original master copies. Remove the tabs in the back of the tape to prevent accidental erasures. For disks, add the write-protect tab. Make a backup disk. Keep it separate from your regular disks. Then enjoy the fruits of your labor!



```
60 REM *** CHUCK-A-LUCK ***
70 REM * EXTENDED BASIC *
80 REM * BY SAM PINCUS *
90 REM 99'er VERSION 2.2.1XB*
100 DIM DICE_VALUE(3),PLAYER_NAME$(4),PLAYER_CASH(4),PLAYER_BET(4),
    ,PLAYER_DICE(4)
110 DIM DICE_FIP(9,9),LOC_X(27),LOC_Y(27)
120 DIM LOC(27)
130 RANDOMIZE
140 GOSUB 20000
170 REM BETTING LOOP
200 REM GET BET
210 GOSUB 1200
220 REM THROW DICE
230 GOSUB 2000
240 REM UPDATE CASH BALANCE
250 FOR I=1 TO PLAYERS
260 IF PLAYER_CASH(I)=0 THEN 760
280 PRINT "":PLAYER_NAME$(I);", YOU
    BET ON";PLAYER_DICE(I);"FOR";P
    LAYER_BET(I);"DOLLAR";
290 IF PLAYER_BET(I)<2 THEN 310
300 PRINT "S";
310 PRINT "."
320 WIN=0
330 FOR J=1 TO 3
```

```
540 IF PLAYER_DICE(I)<>DICE_VALUE(J)
    THEN 560
550 WIN=WIN+1
560 NEXT J
570 IF WIN=0 THEN 690
580 WIN=WIN*PLAYER_BET(I)
590 PRINT "YOU "; "WIN";WIN;"DOLLAR"
    ;
600 IF WIN<2 THEN 620
610 PRINT "S";
620 PRINT "."
630 PLAYER_CASH(I)=PLAYER_CASH(I)+W
    IN
640 PRINT "YOU NOW HAVE";PLAYER_CAS
    H(I);"DOLLAR";
650 IF PLAYER_CASH(I)<2 THEN 670
660 PRINT "S";
670 PRINT "."
680 GOTO 760
690 PRINT "YOU LOST";PLAYER_BET(I);
    "DOLLAR";
700 IF PLAYER_BET(I)<2 THEN 720
710 PRINT "S";
720 PRINT "."
730 PLAYER_CASH(I)=PLAYER_CASH(I)-P
    LAYER_BET(I)
740 IF PLAYER_CASH(I)>0 THEN 640
```

Continued on p. 54



Quality Software for your TI-99/4(A)

***Quest For The Sword**
TEXT ADVENTURE
Can you find the
lost sword of Aron?
basic \$18.00

***Assault Force**
Game for 2 players
Rescue the king
from your opponent's dungeon.
xbasic \$15.00

***Conquest in Space**
Game for 2 players.
Destroy your opponent's
space station to
control the galaxy.
xbasic \$18.00

***Balloon Voyage**
Fly across the city
avoiding buildings and birds.
Multiscreen game for 1 player.
xbasic \$17.00

Send SSA for Catalog

PPd. Send check or money order to:

PEGASUS SOFTWARE
1438 38th Avenue
Greeley, CO 80634

Harvey's Special of the Month An Informative Text Book and Disk

Programmers: The key to becoming a professional, in home or business applications, is to acquire the skill to create and maintain relative files. Whether you work as an employee, or as a free-lance programmer, the earnings potential for you in business applications is enormous.

My publication, "How to Create and Maintain Relative Files", was written for /4 and /4A programmers who want to sharpen their skills in this important area. The text is on 8½ x 11 inch sheets and covers 45 pages. Eleven pages are devoted to four example program listings. The disk contains the 4 programs, which provide hands-on experience using relative files. A printer is not required to use the programs. A disk system is not required if the publication is used as a text book. Functions include:

- How to create relative files.
- How to get around the 255 character record length barrier.
- How to bypass the record number operator input requirement.
- How to create and use multiple disk files.
- About 20 pages are devoted to file maintenance functions.

To use the disk, a minimal disk system is required.

PRICE: When not on special: \$50.00

Now through March 31:
\$45.00

Includes delivery in the U.S.
No sales to foreign countries.
Delivered by first class mail
right away if you send a bank
Money Order to:

James Harvey
159 Dover Road
Spartanburg, S.C. 29301

Write for free catalog

Now expanded to 61 pages
to add a sort utility program
to the text and disk.

Delivery and your satisfaction
guaranteed.

GAME SOFTWARE

FOR THE TI 99/4(A)

Six Arcade Type Games for Less Than the
Cost of a Single Command Module!

Vol. I (BASIC)

1. **ROAD RACE** - Race down an endless winding road, look out for trees. Fire your laser!

— Arcade Features —

2. **CHASE** - Clear off as many squares as possible before being eaten by Sam. The Sinister Smiley Face!

3. **BOMBARDMENT** - Run out the door before being hit, score points on the way!

Vol. II (X-BASIC)

1. **THIEF** - The ultimate, fully graphic quest/adventure game!

2. **THE CHICKEN** - Eat, jump and run - not just another road crossing game!

3. **SHOOT IT** - The endlessly challenging 1 or 2 person game of endurance!

Single Game - \$7.96

Single Volume - \$16.96

Both Volumes - \$27.96

ORDER NOW!

(Less than the cost of a
Single Command Module)

- Prices include postage and handling
- All games require joysticks
- All programs on cassette tape
- Full documentation

SEND CHECK OR MONEY ORDER TO:

Tomputer Software

"Quality Software at Reasonable Prices"

1550 Montgomery Drive
Deerfield, IL 60015



Chuck-A-Luck ... from p.53

```

750 PRINT "YOU ARE BANKRUPT!"
760 NEXT I
770 REM CHECK FOR END OF GAME
780 GOSUB 5000
790 IF NO_LEFT>1 THEN 970
800 INPUT "WANT TO PLAY AGAIN (Y/N)
    ?":A$
810 A$=SEG$(A$,1,1)
820 IF A$<>"Y" THEN 850
830 GOSUB 22000
840 GOTO 200
850 IF A$<>"N" THEN 880
860 PRINT "THANK YOU FOR PLAYING.":
    ""
870 STOP
880 PRINT PL$
890 GOTO 800
970 FOR I=1 TO 600
980 NEXT I
990 GOTO 200
1200 CALL CLEAR
1210 FOR I=1 TO PLAYERS
1220 IF PLAYER_CASH(I)=0 THEN 1500
1230 ON INT(RND*4+1)GOTO 1240,1260,
    1280,1300
1240 PRINT "NOW, ";
1250 GOTO 1350
1260 PRINT "OK, ";
1270 GOTO 1350
1280 PRINT "ALRIGHT, ";
1290 GOTO 1350
1300 PRINT "YOUR TURN, ";
1350 PRINT PLAYER_NAME$(I);", "
1360 PRINT "YOU HAVE";PLAYER_CASH(I)
    ;"DOLLAR";
1370 IF PLAYER_CASH(I)<2 THEN 1390
1380 PRINT "S";
1390 PRINT ".": "WHAT'S YOUR BET? "
1400 INPUT PLAYER_BET(I)
1410 IF PLAYER_BET(I)<1 THEN 1450
1420 IF PLAYER_BET(I)>PLAYER_CASH(I)
    THEN 1450
1430 IF PLAYER_BET(I)>50 THEN 1450
1440 IF INT(PLAYER_BET(I))=PLAYER_B
    ET(I)THEN 1470
1450 PRINT "THAT'S NOT POSSIBLE."
1460 GOTO 1230
1470 PRINT "WHAT NUMBER WILL YOU BE
    T ON?"
1480 INPUT PLAYER_DICE(I)
1490 IF INT(PLAYER_DICE(I))>PLAYER
    _DICE(I)THEN 1520
1500 IF PLAYER_DICE(I)<1 THEN 1520
1510 IF PLAYER_DICE(I)<7 THEN 1540
1520 PRINT "TRY AGAIN."
1530 GOTO 1470
1540 NEXT I
1550 RETURN
2000 REM
2010 CALL CLEAR
2020 CALL SCREEN(10)

```

ATTENTION PROGRAMMERS

If you have written (or plan to write) programs for the TI-99/4(A), we are interested in hearing from you. We will market your programs for you and pay royalties for each program sold. Please write for further details or send your program with user instructions to:

Complete Software Co.

P. O. Box 50886

Nashville, TN 37205

```

2030 FOR I=1 TO PLAYERS
2035 GOSUB 28000
2040 ROW=(I-1)*5+1
2060 DISPLAY AT(ROW,15):PLAYER_NAME
    $(I)
2160 DISPLAY AT(ROW+1,15):"BET $";
    STR$(PLAYER_BET(I))
2260 DISPLAY AT(ROW+2,15):"CASH $";
    STR$(PLAYER_CASH(I))
2350 DISPLAY AT(ROW+3,15):"DIE- ";
    STR$(PLAYER_DICE(I))
2370 NEXT I
2500 FOR I=1 TO 3
2510 DICE_VALUE(I)=INT(RND*6)+1
2520 NEXT I
2600 REM DISPLAY DICE
2610 FOR I=1 TO 3
2620 CHAR_NO=DICE_VALUE(I)
2630 IF CHAR_NO=1 THEN 2740
2640 IF CHAR_NO=4 THEN 2740
2650 IF CHAR_NO=5 THEN 2740
2660 IF RND<.5 THEN 2740
2670 IF CHAR_NO<>2 THEN 2700
2680 CHAR_NO=7
2690 GOTO 2740
2700 IF CHAR_NO=6 THEN 2730
2710 CHAR_NO=8
2720 GOTO 2740
2730 CHAR_NO=9
2740 REM DISPLAY A DIE
2750 FOR J=1 TO 9
2760 K=(I-1)*9+J
2780 CALL SPRITE(8K,96+DICE_PIP(CHA
    R_NO,J),16,LOC_X(K),LOC_Y(K),R
    ND*120-60,RND*120-60)
2800 LOC(K)=0
2820 NEXT J
2830 NEXT I
2840 CNT=0
2850 IF CNT<21 THEN 2900
2860 FOR I=1 TO 27 :: IF LOC(I)=0 T
    HEN 2920
2870 NEXT I :: GOTO 3800
2900 I=INT(RND*27)+1
2910 IF LOC(I)=1 THEN 2900
2920 LOC(I)=1 :: CNT=CNT+1
2930 CALL COLOR(8I,2):: CALL SOUND(
    -1,110,0,165,1,220,2)
2940 CALL MOTION(8I,0,0):: CHK=0
2950 CALL POSITION(8I,Y,X)
2960 MY=LOC_Y(I)-Y :: MX=LOC_X(I)-X
    :: TOT=MAX(1,ABS(MY)+ABS(MX))
2980 CALL MOTION(8I,MY*50/TOT,MX*50
    /TOT)
2990 CHK=CHK+1 :: IF CHK>10 THEN 29
    40
3000 CALL COINC(8I,LOC_Y(I),LOC_X(I)
    ,20,HIT):: IF HIT=0 THEN 2990
3010 CALL MOTION(8I,0,0):: CALL LOC
    ATE(8I,LOC_Y(I),LOC_X(I)):: CA
    LL COLOR(8I,16):: CALL SOUND(-
    1,1111,0)

```


ASPIC*

A LANGUAGE FOR TEACHERS

By Andrew Berner, Ph.D. and Kathleen Martin, Ph.D.

University of Dallas
Irving, TX 75061

*Amateur's Special Purpose Instructional Code

In last November's issue of *99'er Magazine*, we introduced ASPIC, a simple language for doing arithmetic and graphics. ASPIC was designed primarily for children, but it can be valuable for teachers as well. They will find it an easily accessible language for designing their own software.

In this issue we offer four more examples any teacher can program. First is a drill similar to multiplication drills found in commercial software packages.

DRILL

```
10 PRINT "HOW MANY PROBLEMS"
20 ASK FOR N
30 CLEAR
40 LET RIGHT = 0
50 LET A = 12
60 LET B = 12
70 REPEAT N
80 PRINT A
90 PRINT "X"
100 PRINT B
110 ASK FOR ANS
120 IF ANS = A*B THEN
130 PRINT "VERY GOOD!"
140 SOUND
150 LET RIGHT = RIGHT + 1
160 ELSE
170 PRINT "INCORRECT"
180 PRINT "THE ANSWER IS"
190 PRINT A*B
200 END
210 PRINT " "
220 LET A = A + 7
230 IF A > 12 THEN
240 LET A = A - 12
250 END
260 LET B = B + 7
270 IF B > 11 THEN
280 LET B = B - 11
290 END
300 END
310 PRINT "YOU CORRECTLY ANSWERED"
320 PRINT RIGHT
330 PRINT "OUT OF"
340 PRINT N
```

In lines 10-30, the user selects a number of problems from 1 to 132. If a number larger than 132 is put in, the problems will repeat. Lines 40-60 are used for RIGHT, which keeps track of the number of correct answers, and A and B, which will be the multiplier and multiplicand. Lines 80-100 print the problem. Lines 110-200 check the student's response and offer either a reward or a correction. Notice how the "IF...THEN...ELSE" construction makes the logic clear. Lines 210-300 prepare the next problem, and because ASPIC has no random number generator, we use a mathematical trick: The number 7 has no common factor with either 12 or 11, and therefore keeps the problems from repeating while making them seem in random order. The last few lines of the program give a score for the session.


The program certainly could be written in another language, and if copied verbatim in BASIC, it would be more attractive on the screen. The advantage of ASPIC is that a teacher with no previous programming experience could tailor the lessons

ASPIC In a Nutshell

Amateur's Special Purpose Instruction Code is a language designed for children, using a logic consistent with a child's way of thinking. Doctors Berner and Martin, in working to help schools find more effective ways of using computers in education, found the BASIC language too complex for children. It was a difficult language for young students to learn, and one which kept slipping away from those whose time at the computer was limited to a session or two per week. To overcome these obstacles, the two educators created ASPIC.

With a few simple commands such as MAKE and DRAW, the children can create shapes on the screen and assign colors to them. These programs help children understand concepts such as constants, variables, and plotting with a simple coordinate system.

ASPIC is easy for children to use, and easy for teachers to program—even teachers who have had virtually no experience with computers. For complete instructions, see *99'er Home Computer Magazine*, Nov. 1982, pp. 64-67.




to individual needs. For example, the teacher might want to limit the problems to the 1-through-6 times tables. Even simpler would be to change from multiplication to addition. The teacher might want to vary specific numbers to emphasize a single fact table. All these changes and more are easy with ASPIC.

ASPIC Graphics

Our second example shows how to exploit the graphics capabilities of ASPIC. This program distinguishes between even and odd numbers by grouping boxes in pairs. It also displays graphically the nature of even and odd numbers.


EVEN—ODD

```
10 MAKE LEFT
20 MAKE RIGHT
30 MAKE SQ
40 PRINT "HOW MANY NUMBERS?"
50 ASK FOR N
60 CLEAR
70 REPEAT N
80 ASK FOR NUM
90 DRAW (NUM ACROSS) SQ IN
  ROW#20 COL#3
```



```
100 DRAW (128 ACROSS) BL IN
  ROW#21 COL#1
110 LET C=3
120 REPEAT UNTIL NUM<2
130 DRAW LEFT IN ROW#20 COL#C
140 DRAW RIGHT IN ROW#20 COL#C+1
150 LET C=C+2
160 LET NUM=NUM-2
170 END
180 IF NUM=1 THEN
190 DRAW BL IN ROW#20 COL#C
200 DRAW SQ IN ROW#20 COL#30
210 END
220 END
```

The first three commands are used to make the shapes below; they are needed later in the program.



Lines 40-60 ask how many numbers you wish to examine. Lines 70-220 repeat the following procedure for each number examined:

The number is asked for in Line 80 and an equal number of squares drawn (Lines 90-100). Lines 110-170 place brackets around the boxes in groups of two. Lines 180-210 determine if there is an unbracketed box, i.e., if the number is odd. If so, it is "shot" to the far right of the screen.

At the end, it is easy to tell whether the sum of all entries is even or odd by mentally pairing up the "extras" on the right side of the screen. This program makes it easy to visualize the theorem that a sum is odd whenever there is an odd number of odd addends. Computer graphics make tangible a concept that is usually treated abstractly. The "shooting" of the extra box is an image that sticks with children and brings the mathematical concepts and theorems to life.

The power of ASPIC comes through in the structure of the program. The writing of the program reflects one way of thinking about even and odd numbers. No technical jargon or obscure symbolism distracts from the thought. The program's "chunks" correspond to thought patterns that clearly follow the problem.

The third example is another program that uses graphics to illustrate a concept—in this case, "square" numbers. However, the main purpose of this example is to show how the LOOK command can control the pace of instruction.

SQUARES

```

10 MAKE REDBOX
20 MAKE BLUEBOX
30 MAKE YELLOWBOX
40 COLOR REDBOX RED
50 COLOR BLUEBOX BLUE
60 COLOR YELLOWBOX YELLOW
70 DRAW BOX IN ROW#12 COL#16
80 LET LOOK=0
90 REPEAT UNTIL LOOK=1
100 LOOK
110 END
120 DRAW (2 DOWN) REDBOX IN
    ROW#12 COL#17
130 DRAW (2 ACROSS) REDBOX IN
    ROW#13 COL#16
140 LET LOOK=0
150 REPEAT UNTIL LOOK=1
160 LOOK
170 END
180 DRAW (3 DOWN) BLUEBOX IN
    ROW#12 COL#18
190 DRAW (3 ACROSS) BLUEBOX IN
    ROW#14 COL#16
200 LET LOOK=0
210 REPEAT UNTIL LOOK=1
220 LOOK
230 END
240 DRAW (4 DOWN) YELLOWBOX IN
    ROW#12 COL#19
250 DRAW (4 ACROSS) YELLOWBOX
    IN ROW#15 COL#16


```

Lines 10-60 simply construct and color the boxes used in the rest of the program. Line 70 draws a black box (a 1 x 1 square) in the middle of the screen (Notice that shapes are colored BLACK by default.) Lines 80-110 illustrate the use of LOOK. Nothing will happen on the screen until a key is pressed, and perhaps held for a

UNISOURCE

Your one source for all software and peripherals. Here are four good reasons why...

1 Encyclopedia/Catalog— Hot off the press! All TI software. All TI peripherals. Hundreds of third party software packages and accessories. You can order virtually anything you need for your TI-99/4A using the *TI Home Computer Encyclopedia/Catalog* from Unisource Electronics. Only \$6, refundable with your first order. And, you'll automatically get future updates. Order it today...from Unisource.



2 Price—We know you shop around before you buy, and we know price is important. You can be assured of a competitive price from Unisource. Ask about our discount program that applies to everything we sell—no minimum order. You can order using our toll free phone number, and there's no additional charge when you use MasterCard or Visa.

3 Special Mail Offers—Extra-special offers are often made available to those on our mailing list. All you have to do to be included is call our toll free line and give us your name and address. It's as simple as that. Call today! Unless you're a past customer (and already on our list) you've missed several extra-specials already.

4 Availability—Unisource Electronics is located only 3 miles from the TI warehouse in Lubbock, Texas. That's important in today's environment of limited supply on hot new products.

Simplify your shopping. Go with the one source that has it all—Unisource Electronics. And, order your copy of the *TI Home Computer Encyclopedia/Catalog* today. Just call us on our toll free hot line...

1-800-858-4580

(In Texas call 1-806-745-8835)

...and give us your name, address, Visa or MasterCard number, and we'll charge the \$6.00 plus \$1.50 shipping and handling to your account. Texas residents add 5% sales tax. For mail-in orders, send to P.O. Box 64240, Lubbock, Texas 79464.

Unisource Electronics, Inc.

CANADIANS!

Texas Instruments Home Computer CONSOLE

With RF Modulator and Manuals included



\$377



NEW ITEMS

- 899.95 PHP 2500 Dot Matrix Printer
- 164.95 PHM 3111 TI Writer
- 164.95 PHM 3113 Microsoft Multiplan
- 149.95 PHM 3109 LOGO II
- 64.95 PHM 3042 Tunnels of Doom (tape or disk)
- 24.95 PHA 2612 Editor/Assm. Manual
- 59.95 All Scott Foresman, Addison Wesley, Milliken & Scholastic Educational Modules
- 39.95 All MECC Disks
- 39.95 PHM 3056 Alpiner
- 39.95 PHM 3110 Chisholm Trail
- 39.95 PHM 3112 Parsec
- 39.95 PHM 3067 Othello
- 39.95 All Adventure Series on Cassette or Disk

PERIPHERALS

- 339.95 PHP 1200 Peripheral Expansion Box
- 169.95 PHP 1220 RS-232 Card
- 219.95 PHP 1240 Disk Controller Card
- 379.95 PHP 1250 Expansion Box Drive Card
- 259.95 PHP 1260 Memory Expansion Card (RAM)
- 219.95 PHP 1270 P-Code Card
- 125.95 PHP 1500 Solid State Speech™ Synthesizer
- 215.95 PHP 1600 Telephone Coupler (Modem)
- 499.95 PHA 4100 10" Color Monitor
- 19.95 PHP 1100 Wired Remote Controllers (Pair)
- 12.95 PHA 1950 Thermal Paper (2 Pack)
- 19.95 PHA 2000 Dual Cassette Cable
- 24.95 PHA 2010 Monitor Cable

ENTERTAINMENT

- 39.95 PHM 3009 Command Module
- 39.95 PHM 3018 Football
- 39.95 PHM 3023 Video Games I
- 39.95 PHM 3024 Hunt the Wumpus
- 39.95 PHM 3025 Indoor Soccer
- 39.95 PHM 3025 Mind Challenges
- 39.95 PHM 3030 A-Maze-Ing
- 39.95 PHM 3031 The Attack
- 39.95 PHM 3032 Blast
- 39.95 PHM 3033 Blackjack and Poker
- 39.95 PHM 3034 Hustle
- 39.95 PHM 3036 Zero Zap
- 39.95 PHM 3037 Hangman
- 39.95 PHM 3038 Connect Four
- 39.95 PHM 3039 Yahtzee
- 74.95 PHM 3041D Adventure (Pirate Adventure Diskette Game Included)
- 74.95 PHM 3041T Adventure (Pirate Adventure Cassette Game Included)
- 39.95 PHM 3052 Tombstone City 21st Century
- 39.95 PHM 3053 TI Invaders
- 39.95 PHM 3054 Car Wars
- 39.95 PHM 3057 Munch Man
- 31.95 PHD 5002 Ti-Trek (with speech)
- 31.95 PHD 5010 Mystery Melody
- 31.95 PHD 5015 Oldies But Goodies — Games I
- 31.95 PHD 5017 Oldies But Goodies — Games II
- 44.95 PHD 5025 Saturday Night Bingo
- 34.95 PHD 5037 Draw Poker
- 22.95 PHT 6010 Mystery Melody
- 22.95 PHT 6015 Oldies But Goodies — Games I
- 31.95 PHT 6017 Oldies But Goodies — Games II
- 44.95 PHT 6025 Saturday Night Bingo
- 34.95 PHT 6037 Draw Poker

GAMES

IN COMMAND MODULES

\$39.95

CANADIAN FUNDS

Home Management/Personal Finance

- 42.95 PHM 3006 Command Modules
- 42.95 PHM 3007 Home Financial Decisions
- 85.95 PHM 3016 Household Budget Management
- 69.95 PHM 3012 Tax/Investment Record Keeping
- 59.95 PHM 3013 Securities Analysis
- 85.95 PHM 3022 Personal Record Keeping
- 59.95 PHM 3022 Personal Real Estate
- 59.95 PHM 3044 Personal Report Generator
- 84.95 PHD 5001 Diskette
- 32.95 PHD 5003 Mailing List
- 32.95 PHD 5021 Personal Financial Aids
- 47.95 PHD 5022 Checkbook Manager
- 82.95 PHD 5024 Business Aids Library — Finance Management
- 82.95 PHD 5027 Business Aids Library — Inventory Management
- 64.95 PHD 5029 Business Aids Library — Invoice Management
- 72.95 PHD 5038 Business Aids Library — Cash Management

- 21.95 PHT 6003 Cassette
- 72.95 PHT 6038 Personal Financial Aids
- Business Aids Library — Lease/Purchase Decisions

OTHER APPLICATION PROGRAMS

- 44.95 PHM 3000 Command Modules
- 73.95 PHM 3014 Diagnostic
- 124.95 PHM 3026 Statistics
- 73.95 PHM 3035 Extended BASIC
- 124.95 PHM 3055 Terminal Emulator II
- 124.95 PHM 3058 Editor Assembler
- Mini-Memory
- 21.95 PHD 5004 Diskette
- 31.95 PHD 5005 Programming Aids I
- 41.95 PHD 5006 Programming Aids II
- 41.95 PHD 5008 Math Routine Library
- 31.95 PHD 5012 Electrical Engineering Library
- 31.95 PHD 5013 Programming Aids III
- 41.95 PHD 5016 Graphing Package
- 264.95 PHD 5044 Structural Engineering Library
- 213.95 PHD 5063 SMU Circuit Analysis I
- 129.95 PHD 5064 UCSD Pascal — Compiler
- 129.95 PHD 5065 UCSD p-System — Assembler/Linker
- 129.95 PHD 5066 UCSD p-System — Editor/Filter/Utilities
- TI PILOT
- 17.95 PHT 6004 Cassette
- 41.95 PHT 6006 Programming Aids I
- 41.95 PHT 6008 Math Routine Library
- Electrical Engineering Library

EDUCATION/PERSONAL ENRICHMENT

- 42.95 PHM 3002 Command Module
- 52.95 PHM 3003 Early Learning Fun
- 34.95 PHM 3004 Beginning Grammar
- 42.95 PHM 3005 Number Magic
- 69.95 PHM 3008 Video Graphs
- 51.95 PHM 3010 Video Chests
- 59.95 PHM 3015 Physical Fitness
- 59.95 PHM 3020 Early Reading
- 75.95 PHM 3021 Music Maker
- 59.95 PHM 3027 Weight Control and Nutrition
- 59.95 PHM 3028 Addition and Subtraction I
- 59.95 PHM 3029 Addition and Subtraction II
- 59.95 PHM 3043 Multiplication I
- 59.95 PHM 3059 Reading Fun
- 59.95 PHM 3060 Scholastic Spelling — Level III
- 59.95 PHM 3061 Scholastic Spelling — Level IV
- 59.95 PHM 3062 Scholastic Spelling — Level V
- 59.95 PHM 3064 Scholastic Spelling — Level VI
- Typing Tutor
- 49.95 PHD 5007 Diskette
- 39.95 PHD 5009 Teach Yourself BASIC
- 29.95 PHD 5011 Music Skills Trainer
- 29.95 PHD 5018 Computer Music Box
- 39.95 PHD 5019 Market Simulation
- 23.95 PHD 5020 Teach Yourself Extended BASIC
- 39.95 PHD 5023 Music Maker Demonstration
- 39.95 PHD 5026 Basketball Statistics
- 39.95 PHD 5030 Bridge Bidding I
- 39.95 PHD 5031 Speak & Spell™ Program
- 39.95 PHD 5039 Speak & Math™ Program
- 39.95 PHD 5041 Bridge Bidding II
- 39.95 PHD 5042 Bridge Bidding III
- 39.95 PHD 5042 Spell Writer
- 39.95 PHD 5067 Teach Yourself beginning BASIC
- 39.95 PHT 6007 Cassette
- 39.95 PHT 6009 Teach Yourself BASIC
- 22.95 PHT 6011 Music Skills Trainer
- 25.95 PHT 6018 Computer Music Box
- 29.95 PHT 6019 Market Simulation
- 39.95 PHT 6026 Teach Yourself Extended BASIC
- 39.95 PHT 6031 Bridge Bidding I
- 39.95 PHT 6039 Speak & Math™ Program
- 39.95 PHT 6041 Bridge Bidding II
- 39.95 PHT 6042 Bridge Bidding III
- 39.95 PHT 6042 Spell Writer
- 39.95 PHT 6067 Teach Yourself Beginning BASIC

second or two. Lines 120 and 130 draw boxes around the edge to make a 2x2 square. The rest of the program alternates between waiting (Lines 140-170 and Lines 200-230) and drawing the next "square" number by adding an odd number of boxes around the edges (Lines 180-190 and 240-250).

Notice the word "LOOK" has two meanings in ASPIC. In Lines 80 and 90, it is a variable. In Line 100, it is a command that checks whether a key is down; if so, the variable LOOK is assigned 1; otherwise the variable LOOK is assigned 0. Thus the loop in Lines 90-110 (and in corresponding places later in the program) is executed until a key is pressed. When the loop is finished, LOOK has the value 1. Thus it must be re-assigned 0 (Lines 140 and 200) in order to use the procedure again.

Making Math Concepts Concrete

This program's overlapping boxes help children to see that "square" numbers are the sums of consecutive odd numbers. To make the next larger "square" number, you add one to the number in the side of the current square; then double that (for the row and the column) and subtract one (the overlapping box).

$$1 = 1$$

$$1 + 3 = 4$$

$$1 + 3 + 5 = 9$$

$$1 + 3 + 5 + 7 = 16$$

Another way to enlarge the square is to add the next larger row, but fill in the column without the overlap. The odd number is then seen as the sum of two consecutive numbers. What advantage does the computer program have over some tangible device—such as a flannel board or graph paper? Because the squares on the screen are not physical objects, the children must use their imagination to switch back and forth between the two ways of looking at the odd numbers (e.g., 5 is both $2 \times 3 - 1$ and $3 + 2$). Such a program helps students to see one idea from different points of view.

The extensive use of string variables in the translation from ASPIC to BASIC causes ASPIC programs to run slowly. In *Even—Odd* and *Squares*, this slowness is not problematic. Rather, it allows time to point things out and to discuss the concepts involved. It lets the children observe the process by which the concepts were built and the illustrations drawn. Were the language not slow, delays would have to be built into the programs. This raises a question of programming: When should computer assisted instruction focus on process and when on product? *Even—Odd* and *Squares* teach by calling attention to the process, so it is important to slow it down. *Drill* (above) and *Nines* (following) are more concerned with product. Therefore, slowness is not inherently valuable.

Nines is a program that allows school children to use the computer as a data-gathering device. The research is directed toward solving the question:

How long a string of 9's do you need before a number is divisible by a given quantity? For example, 999 is divisible by 37, and 999999 is divisible by 7. Is there

PAYMENT & DELIVERY: All prices quoted are in Canadian Funds. For faster delivery, pay by certified cheque or money order. Personal cheques take two weeks to clear. At these prices, we do not provide Credit Card sales. We can provide all items on the TI Canadian price list. Add \$5.00 per order for postage & handling. Do not remit sales tax. All prices subject to change. Answering service: 403 426 2152; we'll call back collect. No direct sales.

Canadian Micro Works

3724 91 Street Edmonton Alberta Canada T6E 5M3

ASSEMBLY LANGUAGE IS HERE AT INTERSOFT

Powerful assembly language unleashes all the might and speed of 99/4 and 4A. Assembly language is now made possible on disk or cassette by Mini Memory Module. This all Assembly program provides the fastest speed ever.

DEFEND THE CITIES II — Enemy aliens are attacking the five most important cities of the planet Earth. An alien ship orbits overhead dropping bombs on the city. You must destroy the bombs before they reach the skyline of the city and you must destroy the ship to end the attack. Your ship rotates 360° enabling you to fire or accelerate in any direction. After successfully defending one city, you move on to the next, which has increased difficulty and point values. Spectacular arcade action, graphics, and sound effects.

This is a full 4K of Assembly Language and requires either MMM, console and cassette or Editor/Assembler, 32K, disk system and console.

Cassette \$19.95, Disk \$21.95

DEFEND THE CITIES - Extended BASIC Version
Cassette \$19.95

COMING SOON FOR MMM THEON RAIDERS A TOTAL 3-D EXPERIENCE

Send for free catalog.

Quality
Software By:

Intersoft
5407 Salem Hill
Austin, TX 78745

SUPER DISK SPECIALS

TI-99/4A Disk Drives

single-sided drive

\$215.00

double-sided drive

\$270.00

With Case and Power Supply add... \$65.00

Memorex Diskettes

25.95

**2 Disk Drive Kits also available
for Peripheral Expansion Box:**

With 2 single-sided drives

\$430

With 2 double-sided drives

\$540

Shipping included for pre-paid
VISA/M.C./C.O.D. 5% handling

WMS

2760 S. Havana #5
Aurora, CO 80014

Tel. 303-337-5909 or 800-641-3885



Reach for MICRO-ED!

Over 100
Educational
Programs for

• Texas
Instruments
99/4A

Dealer
Inquiries
Invited

Send for **FREE CATALOG**

Please Send me your
FREE CATALOG
For TI

Name _____

Address _____

City _____

State _____

Zip _____

Micro-Ed, Inc.
P.O. Box 24156
Minneapolis, MN 55424

You can call
us at
612-926-2292

BLOCKADE ... from p.39

```
1000 GOTO 940
1010 GOSUB 2560
1020 GOSUB 2410
1030 CALL KEY(KBD,KEY,STAT)
1040 IF STAT<>0 THEN 1080
1050 GOSUB 2660
1060 CALL KEY(KBD,KEY,STAT)
1070 IF STAT=0 THEN 750
1080 IF (KEY=32)*(SHOTS=0) THEN 1050
1090 IF KEY=32 THEN 1030
1100 CALL SOUND(90,-7,16)
1110 IF (KEY<13)+(KEY>159) THEN 1030
1120 IF (KEY>13)*(KEY<33) THEN 1030
1130 REM ***IMPACT GRAPHIC
1140 CALL GCHAR(R(KEY),CL(KEY),CODE)
1150 CALL HCHAR(R(KEY),CL(KEY),136)
1160 CALL HCHAR(R(KEY),CL(KEY),CODE)
1170 GOSUB 2220
1180 IF (CODE>33)*(CODE<38) THEN 1240
1190 SHOTS=SHOTS+1
1200 IF SHOTS<LIM THEN 1030
1210 GOSUB 2510
1220 GOTO 750
1230 REM ***TEST FOR HIT
1240 IF CODE=34 THEN 1340
1250 IF CODE=35 THEN 1400
1260 IF CODE=36 THEN 1460
1270 REM **SHIP DESTRUCTION
1280 CALL HCHAR(T4,D,GRF(1))
1290 CALL HCHAR(T4,D-2,GRF(2),5)
1300 GOSUB 2130
1310 CALL HCHAR(T4,1,32,32)
1320 D=3
1330 GOTO 750
1340 CALL HCHAR(T1,A,GRF(1))
1350 CALL HCHAR(T1,A-2,GRF(2),5)
1360 GOSUB 2130
1370 CALL HCHAR(T1,1,32,32)
1380 A=3
1390 GOTO 750
1400 CALL HCHAR(T2,B,GRF(1))
1410 CALL HCHAR(T2,B-2,GRF(2),5)
1420 GOSUB 2130
1430 CALL HCHAR(T2,1,32,32)
1440 B=3
1450 GOTO 750
1460 CALL HCHAR(T3,C,GRF(1))
1470 CALL HCHAR(T3,C-2,GRF(2),5)
1480 GOSUB 2130
1490 CALL HCHAR(T3,1,32,32)
1500 C=3
1510 GOTO 750
1520 END
1530 REM ***INCREMENT SHIPS
1540 RANDOMIZE
1550 A=A+INT(2*RND)+1
1560 B=B+INT(3*RND)+1
```

```
1570 C=C+INT(3*RND)+1
1580 D=D+INT(3*RND)+1
1590 IF (A>28)+(B>28)+(C>28)+(D>28)
    THEN 1700
1600 ON INT(5*RND)+1 GOTO 1610,1620,1640,1660,1680
1610 RETURN
1620 A=A+1
1630 GOTO 1590
1640 B=B+INT(2*RND)+1
1650 GOTO 1590
1660 C=C+1
1670 GOTO 1590
1680 D=D+1
1690 GOTO 1590
1700 IF A>28 THEN 1750
1710 IF B>28 THEN 1770
1720 IF C>28 THEN 1790
1730 D=3
1740 GOTO 1800
1750 A=3
1760 GOTO 1800
1770 B=3
1780 GOTO 1800
1790 C=3
1800 ESC=ESC+1
1810 GOTO 1590
1820 REM ***DISPLAY SHIPS
1830 CALL HCHAR(T1,1,32,A-2)
1840 CALL HCHAR(T1,A+1,33)
1850 CALL HCHAR(T1,A,34)
1860 CALL HCHAR(T1,A-1,38)
1870 CALL HCHAR(T1,A+2,32,31-A)
1880 IF (A<5)+(A>28) THEN 1900
1890 CALL HCHAR(SCP1,SCP(A),GRF(13))
1900 CALL HCHAR(T2,1,32,B-2)
1910 CALL HCHAR(T2,B+1,33)
1920 CALL HCHAR(T2,B,35)
1930 CALL HCHAR(T2,B-1,39)
1940 CALL HCHAR(T2,B+2,32,31-B)
1950 IF (B<5)+(B>28) THEN 1970
1960 CALL HCHAR(SCP2,SCP(B),GRF(13))
1970 CALL HCHAR(T3,1,32,C-2)
1980 CALL HCHAR(T3,C+1,33)
1990 CALL HCHAR(T3,C,36)
2000 CALL HCHAR(T3,C-1,40)
2010 CALL HCHAR(T3,C+2,32,31-C)
2020 IF (C<5)+(C>28) THEN 2040
2030 CALL HCHAR(SCP3,SCP(C),GRF(13))
2040 CALL HCHAR(T4,1,32,D-2)
2050 CALL HCHAR(T4,D+1,33)
2060 CALL HCHAR(T4,D,37)
2070 CALL HCHAR(T4,D-1,41)
2080 CALL HCHAR(T4,D+2,32,31-D)
2090 IF (D<5)+(D>28) THEN 2110
2100 CALL HCHAR(SCP4,SCP(D),GRF(13))
2110 RETURN
2120 REM ***EXPLOSION
2130 CALL SCREEN(7)
2140 CALL SCREEN(11)
```

Continued on p. 60

DESTINY

COMPUTER SERVICES

NO NONSENSE SOFTWARE for the TI 99/4A. All software comes in disk or cassette form with an audio cassette and written instructions.

Special Introductory Offer. Buy any software package and get a second package of the same or lower price at a 50% discount. Example: Buy BUSINESS PACK for \$189.95 (A great deal — BUS. PACK includes all five \$49.95 programs — INVENTORY, ORDER ENTRY, SALES, MAIL LIST and PMS SORT. — \$249.75 if purchased separately) and get RECORD KEEPER at 50% off. Total cost, \$284.93. You save twice, \$59.80 on the BUS. PACK and \$94.98 on the discount! Check out these program titles and order yours today!

INVENTORY * ORDER * SALES * MAIL LIST * PMS SORT * BUSINESS PACK (includes all five of the above) * BILLING DOCTOR M.D. * BILLING DOCTOR D.D.S. * BILLING LAWYER * BILL MASTER * RECORD KEEPER * JOB COST * SPELLER-ENGLISH * SPELLER ENGLISH TO SPANISH * SPELLER-SPANISH TO ENGLISH.

All software is serialized, unlocked and updatable by the user. Destiny Computer Services specializes in writing custom software programs not covered by those listed above. In addition, Destiny carries a complete line of Direct Market Software. Write for details.

"Software of the future... NOW!"

Destiny Computer Services • 432 Edgehill Lane, Suite 35 • Oceanside, CA 92054

DESTINY


COMPUTER SERVICES

Name
Address
City State Zip
Send me the software packages checked below

☐ INVENTORY \$ 49.95 ☐ BILL MASTER \$189.95
☐ ORDER ENTRY \$ 49.95 ☐ BILL DR. M.D. \$189.95
☐ SALES \$ 49.95 ☐ BILL DR. D.D.S. \$189.95
☐ MAIL LIST \$ 49.95 ☐ BILL LAWYER \$189.95
☐ PMS SORT \$ 49.95 ☐ SPELLER*ENGLISH ... \$ 49.95
☐ BUSINESS PACK \$189.95 ☐ SPELLER*ENGLISH
(includes all 5 of above) TO SPANISH \$ 49.95
☐ RECORD KEEPER \$189.95 ☐ SPELLER*SPANISH TO
ENGLISH \$ 49.95
☐ JOB COST \$189.95
☐ DISK ☐ CASSETTE

One package at list price, second package of same or lower price 50% off (third package at list, fourth package of same or lower price — 50% off, etc.). Payment must accompany order. Make check or money order payable to: Destiny Computer Services. California residents add 6% sales tax.

Destiny Computer Services
432 Edgehill Lane, Suite 35 • Oceanside, CA 92054



DATA RESCUE

Extended BASIC and Joysticks Required.

Can you recover the stolen data bank modules from the Meapzorp spacecraft and return to earth all of the knowledge accumulated over the last 3000 years?

Or will the evil Meapzorps use this knowledge to rule the universe? The future is in your hands.

Dealer Inquiries Invited

THIS GAME FEATURES:

- Arcade Action
- 3-D Perspective
- Multiple Screens
- 3 Skill Levels



To order, send check or money order to:
KUHL SOFTWARE
412 SW 15th Avenue, Rochester, MN 55901

Only \$10.95 on Cassette
(Minnesota residents add 5% sales tax)

BLOCKADE ... from p.59

```
2150 CALL SCREEN(5)
2160 CALL SOUND(100,-7,12,110,24,12
0,26,140,28)
2170 CALL SOUND(800,-7,22,110,28)
2180 CALL SCREEN(2)
2190 TOTAL=TOTAL+1
2200 RETURN
2210 REM ***FLASH
2220 CALL SCREEN(7)
2230 CALL SCREEN(2)
2240 CALL SOUND(50,-7,26)
2250 RETURN
2260 REM ***SET UP SCREEN
2270 CALL CLEAR
2280 CALL SCREEN(2)
2290 GOSUB 2460
2300 GOSUB 2560
2310 CALL HCHAR(21,1,42,128)
2320 PRINT "firing*****LOA
DING*"
2330 PRINT "mode*****
*****"
2340 PRINT "engaged*****
*****"
2350 PRINT : : : :
2360 CALL HCHAR(19,1,42,192)
2370 CALL VCHAR(13,2,42,12)
2380 CALL VCHAR(13,31,42,12)
2390 RETURN
2400 REM ***FIRING SIGN ON
2410 FOR SET=9 TO 11
2420 CALL COLOR(SET,2,14)
2430 NEXT SET
2440 RETURN
2450 REM ***FIRING SIGN OFF
2460 FOR SET=9 TO 11
2470 CALL COLOR(SET,2,2)
2480 NEXT SET
2490 RETURN
2500 REM ***LOADING SIGN ON
2510 FOR SET=5 TO 7
2520 CALL COLOR(SET,12,2)
2530 NEXT SET
2540 RETURN
2550 REM ***LOADING SIGN OFF
2560 FOR SET=5 TO 7
2570 CALL COLOR(SET,2,2)
2580 NEXT SET
2590 RETURN
2600 REM ***RADAR SCOPE
2610 FOR N=12 TO 21
2620 CALL VCHAR(15,N,159,8)
2630 NEXT N
2640 RETURN
2650 REM ***RADAR SCAN
2660 CALL SOUND(190,356,16)
2670 CALL COLOR(16,12,13)
2680 CALL COLOR(16,16,13)
2690 CALL COLOR(16,12,13)
2700 CALL COLOR(16,11,13)
```

```
2710 CALL COLOR(16,4,13)
2720 CALL COLOR(16,3,13)
2730 CALL COLOR(16,13,13)
2740 GOSUB 2560
2750 RETURN
2760 REM ***INSTRUCTIONS
2770 CALL CLEAR
2780 GOSUB 2510
2790 CALL COLOR(3,9,1)
2800 CALL COLOR(6,12,1)
2810 CALL COLOR(8,12,1)
2820 CALL SCREEN(2)
2830 PRINT "PRESS": "<ENTER> FOR M
ENU AND SCORE": "<SPACE> FOR
FIRING MODE": "<ALPHANUMERIC
KEYS> TO FIRE": :
2840 PRINT "RELEASE ALL KEYS FOR DE
FENSE": : :
2850 PRINT "<<WITH 99\4A CTRL AND F
CTN": "KEYS EXTEND RANGE OF F
IRE": :
2860 PRINT "AND ALPHALOCK SHIFTS AI
M OF": "LETTER KEYS> <TO SHIF
T AIM ": "OF NON ALPHA KEYS D
EPRESS ": :
2870 PRINT "BOTH SHIFT KEY AND NON
ALPHA": "KEY TOGETHER>>":
2880 IF DIS=1 THEN 2910
2890 INPUT A$
2900 GOTO 610
2910 RETURN
2920 REM **TITLE/SCORE/MENU
2930 CALL CLEAR
2940 CALL COLOR(3,7,1)
2950 CALL COLOR(8,12,1)
2960 GOSUB 2510
2970 PRINT "NIGHT BLOCKADE":
: "BY ANTS REIGO": : :
2980 PRINT " ";TOTAL;"SUNK": " A
CCURACY";INT(TOTAL/TOTSHT*100)
;"PERCENT": :
2990 PRINT "PRESS NUMBER": " -1
- NEW GAME": " -2- CONTINUE"
:
3000 PRINT : " -3- END": " -4- IN
STRUCTIONS":
3010 CALL KEY(0,K,S)
3020 IF S=0 THEN 3010
3030 IF (K<49)+(K>52) THEN 3010
3040 SLXN=K-48
3050 RETURN
3060 REM ***REDEF 99/4 KEYS
3070 R(46)=11
3080 CL(46)=26
3090 R(13)=11
3100 CL(13)=29
3110 GOTO 710
3120 REM ***MISSILE IMPACT
3130 FOR T=1 TO 4
3140 CALL SOUND(100,600,0,700,0,-2,
0)
3150 CALL SOUND(100,110,28)
```

COMPUTER CASSETTES



BASF
-DPS

THE WORLD'S FINEST
Data media for all microcomputers.
Used nationwide by software manufac-
turers, hobbyists, schools and busi-
nesses. Premium 5-screw shell with
leader fits all standard recorders.

SATISFACTION GUARANTEED OR MONEY BACK.

ITEM	1 DOZ.	2 DOZ.
C-05	11 7.50 13.50	
C-10	11 8.00 14.40	
C-20	11 10.00 18.00	
Hard Box	11 2.50 4.00	

FOR IMMEDIATE SHIPMENT
USE YOUR VISA OR MASTERCARD CALL 213/710-1430

YORK 10™ Computerware
24573 Kittridge St., 99 Canoga Park, CA 91307

WINCHESTER DISK PRODUCT ANNOUNCEMENT

MYARC, INC. announces its Winchester Disk and Controller, the WDS/100, which brings hard disk capacity and reliability to your TI 99/4 microcomputer. Our "Unix"-like "directory manager" features robust file management and MYARC's error correction coding provides excellent program and data file integrity. Available in 5 or 10 Megabyte models, the easily installed WDS/100 can grow as you grow to accommodate a total of 4 hard disks. That's 40 Megabytes of on-line storage!

MYARC packs this and much more into its WDS/100 system at a competitive price.

IT OFFERS:

- Direct interface with the TI 99/4 operating system
- Upward compatibility with TI's floppy disk system
- Complete array of disk utilities
- Flexible configuration
- Easy installation
- Reliable backup
- State-of-the-art ECC
- Customized directory management
- Winchester reliability and high speed performance
- Special "time of day" clock option

Write for additional product
and pricing information to:

MYARC, INC.

Dealer
Inquiries Welcome

P.O. BOX 35 ■ EAST HANOVER, NJ 07936

BLOCKADE

```
3160 NEXT T
3170 CALL SCREEN(10)
3180 CALL SCREEN(2)
3190 CALL SOUND(500,-7,0)
3200 CALL SCREEN(7)
3210 CALL SOUND(500,-7,15)
3220 CALL SOUND(500,-7,26)
3230 CALL SCREEN(16)
3240 CALL SCREEN(11)
3250 CALL SCREEN(2)
3260 IF SM=0 THEN 920
3270 CALL CLEAR
3280 CALL SOUND(900,20000,28)
3290 CALL SOUND(1,20000,28)
3300 GOSUB 2410
3310 GOSUB 2510
3320 DAM=INT(RND*2)+1
3330 IF DAM=LIM THEN 3870
3340 PRINT "      damage report": :
: : "MISSILE IMPACT HAS WIPED
OUT": : INT(DAM/LIM*100); "PERC
ENT"
3350 PRINT "OF REMAINING FIRE POWER
"
3360 PRINT : : : :
3370 LIM=LIM-DAM
3380 MIS=MIS+1
3390 CALL SOUND(3000,20000,28)
3400 CALL SOUND(1,110,28)
3410 CALL CLEAR
3420 GOSUB 2560
3430 GOTO 730
3440 REM ***DEFEAT MESSAGE
3450 CALL CLEAR
3460 GOSUB 2510
3470 PRINT " THE BLOCKADE IS BROKE
N": : " THE WAR IS LOST":
: : : :
3480 CALL SOUND(3000,20000,28)
3490 CALL SOUND(1,20000,28)
3500 GOTO 610
```

```
3510 REM ***MISSILE LAUNCH
3520 CALL HCHAR(T1,1,32,A-2)
3530 CALL HCHAR(T1,A+1,33)
3540 CALL HCHAR(T1,A,34)
3550 CALL HCHAR(T1,A-1,38)
3560 CALL HCHAR(T1,A+2,32,31-A)
3570 IF (A<5)+(A>28) THEN 3580
3580 CALL VCHAR(T1-1,A-1,136)
3590 CALL VCHAR(T1-2,A-1,63)
3600 CALL GCHAR(T1-3,A-1,CD)
3610 CALL VCHAR(T1-3,A-1,136)
3620 CALL SCREEN(7)
3630 CALL VCHAR(T1-1,A-1,32)
3640 CALL VCHAR(T1-4,A-1,43)
3650 GOSUB 2220
3660 CALL VCHAR(T1-4,A-1,32,4)
3670 CALL VCHAR(T1-3,A-1,CD)
3680 RETURN
3690 CALL HCHAR(T2,1,32,B-2)
3700 CALL HCHAR(T2,B+1,33)
3710 CALL HCHAR(T2,B,35)
3720 CALL HCHAR(T2,B-1,39)
3730 CALL HCHAR(T2,B+2,32,31-B)
3740 IF (B<5)+(B>28) THEN 3750
3750 CALL VCHAR(T2-1,B-1,136)
3760 CALL VCHAR(T2-2,B-1,63)
3770 CALL GCHAR(T2-3,B-1,CD)
3780 CALL VCHAR(T2-3,B-1,136)
3790 CALL SCREEN(7)
3800 CALL VCHAR(T2-1,B-1,32)
3810 CALL VCHAR(T2-4,B-1,43)
3820 GOSUB 2220
3830 CALL VCHAR(T2-4,B-1,32,3)
3840 CALL VCHAR(T2-3,B-1,CD)
3850 RETURN
3860 REM ***DEFEAT MESSAGE
3870 CALL CLEAR
3880 GOSUB 2510
3890 LIM=0
3900 PRINT " THIS GUN EMPLACEMENT
": : " HAS BEEN DESTROYED"
: : :
3910 GOTO 3480
```

THE 99/4(A) PROGRAM EXCHANGE

- ★ our prices are lower
- ★ our service is faster

- Selection from hundreds of programs in our rapidly expanding user written and translated software catalog - only \$2.00 per program!
- For those who submit programs the exchange rate is 5 for 1!
- Newsletter, 3rd party and T.I. hardware & software and much, much more.

SEND YOUR *ONE TIME*
MEMBERSHIP FEE OF \$5 to
THE 99/4(A) PROGRAM EXCHANGE
P. O. BOX 3242
Torrance, CA 90510

Send in your Photos and Anecdotes

Do you have a favorite photograph (color or black and white) featuring an unusual application of your Home Computer? Would you like to share your unusual or amusing anecdotes relevant to Home Computing? 99'er Home Computer Magazine will pay \$25 for items it publishes. Material chosen

will be subject to the same copyright treatment as "Letters to the Editor" as set forth on the Masthead page. No submissions can be returned. Send anecdotes and copies of photos to: Pot Pourri Editor, 99'er Home Computer Magazine, 1500 Valley River Drive, Suite 250, Eugene, Oregon 97401.



Have you ever forgotten on which disk a particular program is located? Imagine being able to determine in just a few seconds which disk contains the program you're searching for! **SUPER CATALOGER** accepts up to 500 filenames from as many as 63 disks and produces a sorted catalog on any printer. And it's fast too! an Assembly Language subroutine sorts 200 filenames in six seconds! Requires: TI-Extended-BASIC, memory expansion, disk drive and printer. **Special Introductory price: \$19.95 postpaid.** Virginia residents add 4% sales tax.

Printers On Review...from p.19

If you are going to connect the 83A to the TI-99/4A computer, you will need to alter the RS232 cable connecting the printer to the TI RS232 interface card. The wires to pins 11 and 20 must be interchanged on one end, or the computer will keep writing to the 83A even after the buffer is full, resulting in incorrect or lost information.

Graphics

The 83A comes standard with a fixed set of block graphics characters. These characters are accessible with ASCII values 128 through 191, and repeated again at ASCII 192 to 255. The same type-styles for characters (such as condensed, or enlarged) can be assigned to block graphics, expanding their range of graphic effects.

Documentation

The 83A includes a 75-page user's manual, and 7-page instruction manual. Both are informative, but finding specific information can be time consuming. The information presented could have been better formatted. Some of the explanations are too technical for the average consumer and are geared more for the hobbyist and serious programmer.

Olive-1™

If you already own an Olivetti PRAXIS electronic typewriter—or are thinking of purchasing one—correspondence-quality printing with your Home Computer is now possible with the addition of the Olive-1 RS232 interface kit. If you do not own an Olivetti PRAXIS typewriter, the Olive-80™ typewriter/printer package is available from The Olive Branch Association, Ltd. for a suggested retail price of under \$750.00. The Olive-1 interface alone sells for a suggested retail price of \$249.00.

Special Features

The Olive-1 is a serial communications interface (RS232), compatible with the TI-99/4A. The Olive-1 lets you convert the Olivetti PRAXIS typewriter into a powerful letter-quality printer. If you have completed one of the more complex *HeathKit*™ projects (such as a stereo amplifier) you can probably install this interface yourself. If you lack the necessary skills, Olive Branch will install the interface for \$50.00.

The Olive-1 is a grey box measuring 1.5" x 5" x 5.25". It has three connections. The first is a 9-volt cable supplied from a calculator-type power supply. (Note: Two AC wall outlets will be required, one for the PRAXIS and one for the Olive-1). The second is a flat ribbon cable which you must install in the PRAXIS typewriter. The third is the RS232 cable which connects to the RS232 interface card in the TI Peripheral Expansion Box.


One feature really sets this printer apart from the others: You can, at any time, stop sending information from the computer and type right on the paper from the typewriter keyboard. Olive Branch has not, however, made provisions for transmission from the keyboard back to the computer.

The PRAXIS typewriter is capable of printing up to 165 characters per line at a speed of 12 characters per second. Used as a typewriter, it contains a 10-character buffer with automatic correction. The Olive-1 gives the PRAXIS a 165 character buffer, and can accept three baud rates: 110, 300 and 1200 bps. The PRAXIS also features an interchangeable daisy-wheel printing element.

The following is an example of the PRAXIS type:

Olive-1™

At the time
format will
MANUAL will
registered
comes off
the initial
testing o



Documentation

The Olive-1 comes with two separate manuals. The installation manual is very clear and must be read completely if you decide to do the installation yourself. Our feeling is that an ex-

Who Needs A Printer?!...from p.17

single character or changing the margin alignment? These capabilities are luxuries for some users, necessities for others.

After the Honeymoon

Looking ahead, think about operating costs and maintenance—especially in terms of the two major consumables: (1) ribbons and (2) print-heads or daisy-wheels. Before choosing between two similar printers, compare the costs of replacing these items. Find out the estimated life of each, in terms of total characters printed. How convenient is it to replace a ribbon? Can you replace the print-head, or is that a service center procedure?

If you follow these guidelines in making your purchase, you will easily learn to live with, and even love, your new printing partner.

perienced technician should do the job—to ensure proper operation and to avoid damage to the PRAXIS.

At the time of our evaluation, the user's guide was in a provisional format with the attached statement "The forthcoming OLIVE-80 USER'S MANUAL will cover in depth what the present text can only hint at. Every registered OLIVE-80 owner will receive the user's guide as soon as it comes off the press."

The 18-page provisional manual covers the initial connection and testing of the installation. This guide lacks information on utilizing the super-fancy printing capabilities of the system, but much of this can be figured out by most users. Besides, the system is very useful without all the "bells and whistles."

General Comparison of Printers

Now let's make some general comparisons so that you can better choose a printer that will fit your needs.

If, for example, type-styles are a major concern, the Gemini-10 has an outstanding selection. It is also capable of dot-graphics, as are the TI 99/4 Impact Printer and Print Mate 99 printer. If speed is of the utmost importance, the Microline 83A will finish first at 120 cps, although the Print Mate 99 and Gemini-10 are not far behind at 100 cps.

Three printers have wide carriages—the Microline 83A, a wide-carriage model of the Gemini-10 (the Gemini-15) and the wide-carriage model of the PrintMate 99 (the PrintMate 150).

For quality of print, the Olivetti is in a class by itself. It is a relatively slow printer with single-sheet feed only, but its daisy-wheel provides letter-quality characters.

Now down to the money. It is misleading to make quick comparisons of suggested retail prices without considering hidden costs. You have to consider the cost of ribbons: \$2-\$5 for the spool-type used on the Microline 83A and Gemini-10, and \$8-\$16 per cartridge for the others. Also, the cost of different paper types may be a consideration.

These many factors make your decision a complex one, but it is worth the effort to take the necessary time in selecting the printer that will best fit your requirements.

For Further Information:

On the Gemini-10 Printer contact:
Star Micronics, Inc.
Suite 216
1120 Empire Central Place
Dallas, TX 75247

On the Microline 83A contact:
Okidata Corp.
111 Gaither Drive
Mt. Laurel, NJ 08054


On the Olive-1 Kit contact:
The Olive Branch
Association, Ltd.
26291 Production Ave., Ste. 205
Hayward, CA 94545

On the PrintMate 99 Printer
contact:
Micro Peripherals, Inc.
4426 South Century Drive
Salt Lake City, UT 84107

On the TI 99/4 Impact Printer
contact:
Texas Instruments
Consumer Relations Dept.
P. O. Box 53
Lubbock, TX 79408

Olive-1 and Olive-80 are trademarks of The Olive Branch Association, Ltd. Print-Mate is a trademark of the Micro Peripheral, Inc. HeathKit is a trademark of the Heath Company.

RENEW TODAY—DON'T MISS A SINGLE ISSUE!

<div style="text-align: center;">  <h2 style="margin: 0;">Subscription</h2> </div> <p> <input type="checkbox"/> NEW SUBSCRIPTION <input type="checkbox"/> SUBSCRIPTION RENEWAL <small>(Allow 6-8 wks for your first issue)</small> </p> <table style="width: 100%; border-collapse: collapse;"> <tr> <th style="text-align: left;">Term</th> <th style="text-align: center;">U.S.A</th> <th style="text-align: center;">Canada & Mexico</th> <th style="text-align: center;">Foreign Surface</th> <th style="text-align: center;">Foreign Air</th> </tr> <tr> <td>1-yr (12 Issues)</td> <td style="text-align: center;">\$25</td> <td style="text-align: center;">\$32</td> <td style="text-align: center;">\$43</td> <td style="text-align: center;">Inquire</td> </tr> <tr> <td>2-yr (24 Issues)</td> <td style="text-align: center;">\$45</td> <td style="text-align: center;">\$52</td> <td colspan="2" rowspan="2" style="text-align: center; vertical-align: middle;">Please enclose payment in U.S. FUNDS or Credit Card billing information as indicated below.</td> </tr> <tr> <td>3-yr (36 Issues)</td> <td style="text-align: center;">\$63</td> <td style="text-align: center;">\$70</td> </tr> </table> <p>BACK ISSUES AVAILABLE WHILE SUPPLIES LAST</p> <p>Circle Issues Desired Vol. 1 No. 6 Nov. '82 Dec. '82 Jan. '83</p> <p>Postpaid \$3.95 ea. USA \$5.50 ea. Foreign Surface \$4.50 ea. Canada & Mexico \$7.50 ea. Foreign Air Mail</p> <div style="text-align: right;"> TOTAL </div>	Term	U.S.A	Canada & Mexico	Foreign Surface	Foreign Air	1-yr (12 Issues)	\$25	\$32	\$43	Inquire	2-yr (24 Issues)	\$45	\$52	Please enclose payment in U.S. FUNDS or Credit Card billing information as indicated below.		3-yr (36 Issues)	\$63	\$70	<p style="text-align: center;">RENEWAL SUBSCRIBERS PLEASE INCLUDE INFORMATION BELOW FROM PREVIOUS MAILING LABEL:</p> <p>Subscriber Code Number (line above your name on mailing label)</p> <p>NAME _____ PLEASE</p> <p>ADDRESS _____ PRINT</p> <p>CITY _____ STATE _____ ZIP _____</p> <p style="text-align: center;">Please indicate below any change in name or address.</p> <p>NAME _____ PLEASE</p> <p>ADDRESS _____ PRINT</p> <p>CITY _____ STATE _____ ZIP _____</p> <p> <input type="checkbox"/> Check enclosed MUST BE IN U.S. FUNDS DRAWN ON A U.S. BANK </p> <p> Address shown is <input type="checkbox"/> Business <input type="checkbox"/> Home </p>
Term	U.S.A	Canada & Mexico	Foreign Surface	Foreign Air															
1-yr (12 Issues)	\$25	\$32	\$43	Inquire															
2-yr (24 Issues)	\$45	\$52	Please enclose payment in U.S. FUNDS or Credit Card billing information as indicated below.																
3-yr (36 Issues)	\$63	\$70																	

Bill my: ☐ VISA ☐ Master Card

▶
Expiration Date



Account No. _____

Tel. No. _____ Signature _____

PLACE
STAMP
HERE



P.O. Box 5537
Eugene, OR 97405


<div style="text-align: center;">  </div> <p style="text-align: center; font-size: small;">*U.S. ONLY—FOR SHIPMENT OUTSIDE THE U.S. INQUIRE SEPARATELY</p> <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">QTY</th> <th style="text-align: left;">ITEM</th> <th style="text-align: right;">PRICE</th> <th style="text-align: right;">TOTAL AMOUNT</th> </tr> </thead> <tbody> <tr> <td></td> <td>99'er FINDER - BINDER</td> <td style="text-align: right;">\$10.95</td> <td></td> </tr> <tr> <td></td> <td style="text-align: right;">SHIPPING—\$3.00 ea.*</td> <td></td> <td></td> </tr> <tr> <td></td> <td>6—DIGITAL COMPUTER CASSETTES</td> <td style="text-align: right;">\$7.00</td> <td></td> </tr> <tr> <td></td> <td style="text-align: right;">SHIPPING—2.00 ea.*</td> <td></td> <td></td> </tr> <tr> <td></td> <td colspan="3">SPECIAL: 99'er Finder - Binder</td> </tr> <tr> <td></td> <td>•with 6 blank cassettes for only</td> <td style="text-align: right;">\$16.95</td> <td></td> </tr> <tr> <td></td> <td>•with 12 blank cassettes for only</td> <td style="text-align: right;">\$21.95</td> <td></td> </tr> <tr> <td></td> <td style="text-align: right;">SHIPPING—\$4.00 ea.*</td> <td></td> <td></td> </tr> <tr> <td></td> <td>TEX - SETTE ADAPTOR</td> <td style="text-align: right;">\$4.95</td> <td></td> </tr> <tr> <td></td> <td style="text-align: right;">SHIPPING—\$1.00 ea.*</td> <td></td> <td></td> </tr> <tr> <td></td> <td colspan="3">DUST COVERS: See prices on page 68. Indicate choices below.</td> </tr> <tr> <td></td> <td style="text-align: right;">SHIPPING—\$2.00 for 1st COVER, 50¢ ea. add.*</td> <td></td> <td></td> </tr> <tr> <td></td> <td style="text-align: right;">TOTAL</td> <td></td> <td></td> </tr> </tbody> </table>	QTY	ITEM	PRICE	TOTAL AMOUNT		99'er FINDER - BINDER	\$10.95			SHIPPING—\$3.00 ea.*				6—DIGITAL COMPUTER CASSETTES	\$7.00			SHIPPING—2.00 ea.*				SPECIAL: 99'er Finder - Binder				•with 6 blank cassettes for only	\$16.95			•with 12 blank cassettes for only	\$21.95			SHIPPING—\$4.00 ea.*				TEX - SETTE ADAPTOR	\$4.95			SHIPPING—\$1.00 ea.*				DUST COVERS: See prices on page 68. Indicate choices below.				SHIPPING—\$2.00 for 1st COVER, 50¢ ea. add.*				TOTAL			<div style="text-align: center;">  </div> <p style="text-align: center; font-size: small;">Circle tapes desired</p> <p> E1, G2X, M1/5, M1/6, M2/1, M2/2, M2/3 MAGAZINE ON TAPE </p> <p> SHIPPING—\$1.00 for 1st TAPE, 50¢ ea. add. Foreign Orders Shipped Airmail— \$3.00 for 1st TAPE, 75¢ ea. add. </p> <p style="text-align: right;">TOTAL</p> <table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">QTY</th> <th style="text-align: left;">TITLE</th> <th style="text-align: right;">PRICE</th> <th style="text-align: right;">TOTAL AMOUNT</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table> <p> No. C.O.D. orders accepted. Add. \$1.50 postage & handling for 1 book, \$2.00 for 2 books, or \$2.50 for 3 or more books. </p> <p style="text-align: right;">POSTAGE TOTAL</p> <p>Bill my: <input type="checkbox"/> VISA <input type="checkbox"/> Master Card</p> <p> ▶ Expiration Date </p> <p>Account No. _____</p> <p> Tel. No. _____ Signature _____ </p> <p>NAME _____ PLEASE</p> <p>ADDRESS _____ PRINT</p> <p>CITY _____ STATE _____ ZIP _____</p> <p> <input type="checkbox"/> Check enclosed MUST BE IN U.S. FUNDS DRAWN ON A U.S. BANK </p> <p> Address shown is <input type="checkbox"/> Business <input type="checkbox"/> Home </p>	QTY	TITLE	PRICE	TOTAL AMOUNT				
QTY	ITEM	PRICE	TOTAL AMOUNT																																																														
	99'er FINDER - BINDER	\$10.95																																																															
	SHIPPING—\$3.00 ea.*																																																																
	6—DIGITAL COMPUTER CASSETTES	\$7.00																																																															
	SHIPPING—2.00 ea.*																																																																
	SPECIAL: 99'er Finder - Binder																																																																
	•with 6 blank cassettes for only	\$16.95																																																															
	•with 12 blank cassettes for only	\$21.95																																																															
	SHIPPING—\$4.00 ea.*																																																																
	TEX - SETTE ADAPTOR	\$4.95																																																															
	SHIPPING—\$1.00 ea.*																																																																
	DUST COVERS: See prices on page 68. Indicate choices below.																																																																
	SHIPPING—\$2.00 for 1st COVER, 50¢ ea. add.*																																																																
	TOTAL																																																																
QTY	TITLE	PRICE	TOTAL AMOUNT																																																														

PLACE
STAMP
HERE



P.O. Box 5537
Eugene, OR 97405

RENEW TODAY—DON'T MISS A SINGLE ISSUE!

		Subscription	
<input type="checkbox"/> NEW SUBSCRIPTION <small>(Allow 6-8 wks for your first issue)</small>		<input type="checkbox"/> SUBSCRIPTION RENEWAL	
Term	U.S.A.	Canada & Mexico	Foreign Surface Foreign Air
1-yr (12 Issues)	\$25	\$32	\$43 Inquire
2-yr (24 Issues)	\$45	\$52	Please enclose payment in U.S. FUNDS or Credit Card billing information as indicated below
3-yr (36 Issues)	\$63	\$70	
BACK ISSUES AVAILABLE WHILE SUPPLIES LAST			
Circle Issues Desired	Vol. 1 No. 6	Nov. '82	Dec. '82 Jan. '83
Postpaid	\$3.95 ea. USA	\$5.50 ea. Foreign Surface	
	\$4.50 ea. Canada & Mexico	\$7.50 ea. Foreign Air Mail	
TOTAL			<input type="text"/>
Bill my: <input type="checkbox"/> VISA <input type="checkbox"/> Master Card			
<input type="text"/>		Expiration Date	
Account No.			
Tel. No.		Signature	

RENEWAL SUBSCRIBERS PLEASE INCLUDE INFORMATION BELOW FROM PREVIOUS MAILING LABEL:	
Subscriber Code Number (line above your name on mailing label)	
NAME _____	PLEASE
ADDRESS _____	PRINT
CITY _____ STATE _____	ZIP _____
Please indicate below any change in name or address.	
NAME _____	PLEASE
ADDRESS _____	PRINT
CITY _____ STATE _____	ZIP _____
Check enclosed	MUST BE IN U.S. FUNDS DRAWN ON A U.S. BANK
Address shown is <input type="checkbox"/> Business <input type="checkbox"/> Home	

PLACE
STAMP
HERE



P.O. Box 5537
Eugene, OR 97405

YCAN Systems, Inc.

Texas Instruments Software

INVENTORY.....\$49.95	BILLING MEDICAL...\$189.95	JOB COST.....\$189.95
ORDER ENTRY...\$49.95	BILLING DENTAL...\$189.95	RECORD KEEPER...\$189.95
SALES.....\$49.95	BILLING LAWYER...\$189.95	
MAIL LIST.....\$49.95	BILLING MASTER...\$189.95	
PMS SORT.....\$49.95		

All programs on disk.
Extended Basic required.

Other Products

We have software for the Atari, Apple, Kaycomp Eagle, most CP/M based computers and many others. Call or write for more information.

Ask about SOLID WOOD computer furniture. Custom designed by **Gee! Rogers Wood.**

Master card, Visa, check or money order.
California orders add 6% sales tax.

YCAN Systems, Inc.
4037 Johnson Drive
Oceanside, Ca. 92056

(619) 758-1633

Want to Get Published?

99'er Home Computer Magazine is looking for articles in all areas of interest that concern Texas Instruments personal computers. Here are the kinds of articles that we want you to write for us:

- Are you a businessman, professional, hobbyist, scientist, or engineer with an interesting microcomputer application? Tell us how it works, what problems you've had to overcome, and what recommendations you have for others. We're especially interested in sharing user-written software with our readers.
- Have you recently purchased a piece of hardware or software that hasn't quite come up to your expectations, or has, on the other hand, impressed you with its performance? We're looking for comprehensive product and book reviews from different perspectives.
- Are you an educator or parent with something to contribute to computer-assisted instruction (CAI)? We're always looking for new ideas and fresh approaches to educational problems.
- Have you created any unusual computer games or simulations? Let our readers experience your excitement and pleasure.
- Perhaps you've modified your microcomputer or have interfaced it with some unique or useful hardware. Send us your how-to-do-it story.

These are just some ideas. Perhaps you have others. Don't worry if you're not a professional writer. Our editorial staff stands ready to help polish up your manuscripts. And we'll be more than happy to send you a copy of our author's guidelines.

Please send your double-spaced typed manuscripts, plus disks or cassettes (recorded on both sides) if the article includes program material, to:

99'er Home Computer Magazine
Editorial Dept
1500 Valley River Drive, Suite 250
Eugene, OR 97401

Adventuring... from p.50

All of these have been done. Try to come up with something original.

Set up a sequence that will support the theme. For example, if the theme is to escape a burning building, maybe the adventurer should pour water on a key (otherwise too hot to handle). If the adventure takes place in Darkest Africa, maybe you should have the hero meet up with a lion, which he must face with a bow and arrow. Now let him find a bow, but make him fashion his own arrows.

Make up a list of objects that are in keeping with the sequence. To pour water, you will need a source and some kind of container. To kill the lion, you'll have to add a lion, a bow, a knife, a bowstring, and a tree branch (for the arrows). You may want to add a tree and make the hero cut a branch.

Make up a list of verbs your program can understand. To kill that lion, you will need words like cut (branch), whittle (branch), tie (bowstring), fire (arrow or bow), and kill (lion). Don't make the list too long, and provide alternative words that will be legal: (e.g., "hack" for "cut.")

Draw up a map. First enter the usual connections. Then add the more devious ones that require the player's imagination. Start adding objects to the rooms. Spread the objects around so that, for example, the knife, the bow, and the bowstring are not in the same or adjoining rooms.

Write a list of room descriptions. Try to describe everything visible but don't give too many details. You could chew up too much memory for the adventure to fit in to your computer.

Now you can begin writing that great adventure epic that you have been dreaming of. After it has been written and debugged, ask a friend (or enemy) to give it a try. Accept any constructive criticism. The game may be too hard or too easy. Maybe it has some illogical events. Listen to your critics carefully. You can never tell how difficult your adventure is, because *you* created it. You know that he has to make an arrow to kill the lion, but unfortunately no one else may think of it. Having completed your adventure, you can congratulate yourself on joining the illustrious ranks of adventure creators, just like Scott Adams!

99'er

DON'T LET ANYONE GIVE YOU A BUM STEER

When it Comes to Marketing
Your Software . . .

For Expert Advice Call the Professionals!



Index to Advertisers

Aerocomp.....	37	Millers Graphics.....	33
American Software Design & Distribution Co.....	33	Moonbeam Software.....	3
Bach Company, The.....	21, 35, 37	MYARC, Inc.....	61
BeeJay Funware.....	21	NSY Software.....	51
Canadian Micro Works.....	58	North Hills Computer.....	52
Cintronics.....	23	Northern Light Software.....	51
Complete Software Co.....	54	Norton Software.....	53
Computer Peripheral Resources.....	23	Not Polyoptics.....	17
Control Data Corp.....	28, 29	Novadata Systems Incorporated.....	23
Corn Software.....	51	Oak Tree Systems.....	39
Cumberland Technology.....	55	Pablo Diablo.....	38
Denali Data Design.....	62	Pegasus Software.....	53
Destiny Computer Services.....	60	Pewterware.....	37
Dhein's True Value.....	10, 34	Practical Software.....	63
Dollard, Walter J.....	55	Republic Software.....	19
Dow, John T.....	38	Scotch Marketing Inc.....	12, 20
Dynamic Data & Devices.....	39	Scott, Foresman and Company.....	2
Eastbench Software Products.....	38	Software Specialties, Inc.....	51
Ehninger Associates Inc.....	16	Software Support.....	32
Elek-Tek, Inc.....	13	Star Micronics.....	15
Ermware.....	55	TENEX.....	50
Extended Software Co.....	63	Texas Instruments, Inc.....	8, 70, 72
FFF Software.....	33	Tex-Comp Users Supply Division.....	24, 62
Great White North Software Co., The.....	52	Tex-Soft.....	37
Hardin's Computer Solutions, Inc.....	14	Textiger.....	39
Harvey, James.....	54	Tomputer Software.....	54
Headwind Software.....	33	Unisource Electronics, Inc.....	57
Hi-Tech Systems.....	35	WMS.....	59
Intersoft.....	59	Western Ware Inc.....	38
J & K H Software.....	61	YCAN Systems, Inc.....	66
Kuhl Software.....	60	York 10 Computerware.....	60
LOGIX.....	18	99/4A Program Exchange.....	61
Micro-80 Inc.....	21	99'er Bookstore.....	36
Micro-Ed, Inc.....	59	99'er Magazine.....	65
Micro Peripherals, Inc.....	71	99'er-ware.....	68, 69

ATTENTION: BOOKSTORES, DEALERS, & DISTRIBUTORS

CALL OR WRITE
US ABOUT
SELLING SINGLE
COPIES OF



ASPIC... from p.58

any pattern that will let us predict how many 9's we need?

NINES

```

10 CLEAR
20 PRINT "WHAT IS THE DIVISOR"
30 ASK FOR DIV
40 REPEAT UNTIL DIV = 0
50 PRINT "THE REMAINDERS ARE:"
60 LET REM = 9
70 REPEAT UNTIL REM < DIV
80 LET REM = REM / DIV
90 END
100 PRINT REM
110 LET COUNT = 1
120 REPEAT UNTIL REM = 0
130 LET REM = 10 * REM
140 LET REM = REM + 9
150 REPEAT REM / DIV
160 LET REM = REM - DIV
170 END
180 PRINT REM
190 LET COUNT = COUNT + 1
200 END
210 PRINT "THE NUMBER OF RE-
    MAINDERS WAS"
220 PRINT COUNT
230 PRINT "WHAT IS THE DIVISOR"
240 ASK FOR DIV
250 END

```

Nines performs divisions for children, who might otherwise produce errors that would spoil the patterns. Of key interest here is the sequence of remainders obtained in dividing strings of 9's. The number of re-

mainders needed to get a 0 remainder is the number of 9's we are looking for:

0 2 7	
37 999	
0	
99	9 was the first remainder
74	
259	25 was the second remainder
259	
0	0 was the third remainder

In *Nines*, the successive remainders are displayed until the remainder is 0, then the number of remainders is displayed. Lines 20-30 ask for the first divisor. Lines 60-110 calculate, print and count the first remainder. Lines 120-200 handle the rest of the sequence as follows: Lines 130-140 "bring down the next 9" as we do in the long division process. Lines 150-170 compute the remainders (Note that Lines 70-90 and 150-170 have the same effect. Either can be used in both places if you wish!) Line 180 prints the remainder. COUNT, which keeps track of the number of remainders, is increased in Line 190. Lines 210-220 print the total number of remainders needed. Lines 230-240 ask for the next divisor, and Line 250 returns control to Line 40. To stop the program, enter 0 as a divisor.

Nines happens to bring up a typical mathematical question: How do we know if the division will come out even? If we use a divisor of 6, for example, it won't

work! This will cause an infinite loop in Lines 120-200. The program will keep printing out remainders "forever" or until the number of remainders gets too large for the computer to handle. (It will certainly seem like forever.) To stop the program, you must use the ASPIC break key, which is the '?'. (You may have to hold it down for a second). Part of the research then becomes the question: "For which divisors will I get an infinite sequence of remainders?" The process of gathering data to answer one question raises new questions! This is very common in creative mathematical work.

The programming in *Nines* shows the value of the REPEAT UNTIL command in ASPIC. The loop structure in BASIC (FOR...NEXT) would require us to know how many remainders we will need. But this is precisely what we are trying to find out! The use of an IF statement is necessary in BASIC. This illustrates the difficulty a beginner faces in trying to express thought patterns clearly in a computer language like BASIC. In ASPIC, all groups of commands that are to be repeated are labeled REPEAT! (It should be noted for those who know the Pascal language that REPEAT UNTIL in ASPIC is an entry-checking loop. There is no exit-checking loop).

The four programs given here show different ways a computer can be used in the classroom. We hope that teachers will be able to take these as models for designing and writing their own programs in ASPIC.



Keep Your Magazines & Tapes Together With a 99'er FINDER-BINDER™



- Big enough to hold 6 magazines and 12 tapes
- Uses wire straps to hold magazines so that no hole punching is necessary
- Attractive and Durable

—Only \$10.95*

(magazines and tapes not included)

FREE 99'er Master Index with each 99'er Finder-Binder order

(will be mailed when available in 2nd Quarter, 1983)



*Only \$10.95 without cassettes, plus \$3.00 shipping & handling.
6 High-Quality 99'erware C-10 Digital Computer Cassettes
(with special BASE tape and 5-screw housing for data integrity)
Available separately for \$7.00 plus \$2.00 shipping & handling.

• SPECIAL: 99'er Finder-Binder that is packed:

- with 6 of the above blank cassettes for only \$16.95.
- with 12 of the above blank cassettes for only \$21.95.

Add \$4.00 shipping & handling to either order.




The TEX-SETTE™ Adapter

Cassette Compatibility At Last!

If The TI-99/4A Will Not Control Your Cassette Recorder Through Its Remote Jack, We Have The Solution For You...



- Low cost — Only \$4.95 plus \$1.00 each for postage and handling.



DUST COVERS Features:

- Equipment Protection
- Handsome Appearance
- Custom-Fit
- Antistatic Treated
- Quality Construction



A	10" Color Monitor Cover	\$10.95
	13" Color Monitor Cover (not shown)	\$12.95
B	Peripheral Expansion Box Cover	\$12.95
C	TI's 99/4 Matrix Printer Cover (same as Epson MX-80 Cover)	\$9.95
D	Cassette Recorder Cover (1 size fits up to 10" x 6")	\$4.95
E	TI-99/4A Console Cover	\$8.95
F	Speech Synthesizer Cover	\$3.95
G	Peripheral Box Cover (Specify: 32K Memory Expansion, RS232 Interface, or Disk Controller)	\$5.95
H	Thermal Printer Cover	\$8.95
I	Disk Memory Drive Cover	\$5.95

DEALER INQUIRIES INVITED

Add \$2.00 shipping/handling for the first dustcover; 50 cents for each additional cover.

99'erware™



INNOVATIVE PRODUCTS FOR TMS9900-BASED PERSONAL COMPUTING

P.O. Box 5537
Eugene, Oregon 97405
Tel. (503) 485-8796



Selected Programs from 99'er Are Now Available on Cassette Tape

Note: Programs in this issue will be available on a future tape release.

Use the blind-in card in the back of the magazine for your convenience in ordering.

Shipping—\$1.00 for 1st tape, 50 cents each additional. Foreign Orders Shipped Airmail—\$3.00 for 1st tape, 75 cents each additional.

PACKAGE #M1/6

From Vol. 1, No. 6

Verbose (TI BASIC with Speech)
Color Mapping (TI BASIC)
County Fair Derby (TI BASIC)
Battle Star (Extended BASIC)
N-VADER (Extended BASIC)
Pre-School Block Letters
(TI BASIC)

\$12/sub; \$20/non-sub

PACKAGE #M2/3

From Vol. 2, No. 3

Close Encounters of the Simon Kind
(TI BASIC)
Learning the Alphabet (TI BASIC)
Cyber-Dice (Extended BASIC)
Electrical Engineering Resistance
(TI BASIC)

\$12/sub; \$20/non-sub

PACKAGE #M2/2

From Vol. 2, No. 2

Termite (TI BASIC)
Tex-Scribe (Extended BASIC)
Gold Rush (Extended BASIC)
Plotting Routines (Assembly
Object Code for Mini-Memory
Loader)

\$12/sub; \$20/non-sub

PACKAGE #M1/5

From Vol. 1, No. 5

Tex-Thello (TI BASIC)
San Francisco Tourist (TI BASIC)
Name That Bone (TI BASIC)
Space Patrol (Extended BASIC)
Force 1 (Extended BASIC)
Spriter (Extended BASIC)

\$12/sub; \$20/non-sub

PACKAGE #M2/1

From Vol. 2, No. 1

Up Scope! (Extended BASIC)
Micro Jaws (Extended BASIC)
Knight's Tour (TI BASIC)
Screen Dump (Assembly Object
Code for Mini-Memory Loader)
ASPIC (TI BASIC)

\$12/sub; \$20/non-sub

PACKAGE #G2X

Extended BASIC

Interplanetary Rescue (Vol. 1, No. 4)
Dogfight (Vol. 1, No. 3)
Sprite Chase (Vol. 1, No. 2)
Dodge'em (Vol. 1, No. 4)

\$10/sub; \$16/non-sub

PACKAGE #UI

TI BASIC

Electronic Home Secretary (Vol. 1, No. 2)
Micro Bartender (Vol. 1, No. 4)
Interactive Forms Generator (Vol. 1, No. 3)
Music Text Editor & File Player (Vol. 1, No. 1)

\$10/sub; \$16/non-sub

PACKAGE #EI

TI BASIC

Typing for Accuracy (Vol. 1, No. 3)
Let's Learn Notes (Vol. 1, No. 3)
Mystery Words (Vol. 1, No. 4)
Homework Helper: Fractions (Vol. 1, No. 1)
Homework Helper: Division (Vol. 1, No. 4)

\$12/sub; \$20/non-sub

■ All purchasers of these packages are responsible for obtaining the individual documentation and program instructions in the indicated back issues of the magazines. When an issue goes out-of-print, copies of the program articles will be made available for purchase.

■ If programs have been updated/enhanced since original publication, a printed copy of documentation changes will be provided with the tapes.

■ Both subscriber & non-subscriber prices are indicated. To be eligible for the lower subscriber prices, you must be a current, paid magazine subscriber. All orders will be verified prior to shipment.

■ Authors of these and future programs distributed on tape and disk will receive Bonus Payments based on the number of tapes sold; so in fairness to them, please observe the Copyright laws, and report any incidents of "piracy" to our office.

■ Recognized TI User Groups should contact us for special bulk terms & rates — No dealers, please.

Back Issues of 99'er are Still Available . . . but quantities are limited so ORDER TODAY!

ISSUE #1
ISSUE #2
ISSUE #3
ISSUE #4
ISSUE #5

OUT OF PRINT

Each Only
\$3.95 postpaid

ISSUE #6 (Partial Contents)

• How to Produce Sound Effects • Debugging a Game Program • How to Start a Users' Group • Verbose: A Speech Vocabulary Expansion Aid • Color Mapping • Dynamic Manipulation of Screen Character Graphics • The Beginner's Guide to Cassette Operation With the Home Computer • Pre-School Block Letters and Data Compaction • Picking the Ponies in TI BASIC • Battle Star Space Game • 3-D Animation on the Home Computer • Programming Tips • Who is LOGO For? • Tower of Hanoi in TI LOGO • A Review of the TI Lesson-Development Software • An Interview with a Game Designer • Learning Assembly Language with a Magic Crayon • and much, much more.

NOVEMBER 1982 ISSUE (Partial Contents)

• Chatting with Your Micro: Languages for the Home Computer • A Review of the Smith Corona TP-1 Daisy Wheel Printer • The Micro Jaws Arcade Game • A Review of the TI Extended BASIC Language • A Knight's Tour in TI BASIC • LOGO Has Style • ASPIC: A

Language for Children • A p-System Beginner's Tutorial • An Interview with a p-System Pioneer • A Mini-Memory Screen Dump to the Home Computer Printer • Up Scope!—An Exciting Undersea Combat Game • Strategy for Munch Man • A Brief Encounter with a TI Hand-Held Computer • 99'er Shopping Bus • A Pocket Battleship • Sub-Programs in Extended BASIC • Arcade & Adventure Game Reviews • and much, much more.

DECEMBER 1982 ISSUE (Partial Contents)

• Tex-Scribe: A Text Editor for the Home Computer • A Christmas Computer Carol • Managing a Mailing List the Future Way • Parsec: The Arcade Game • Plotting With the Home Computer—Pixel by Pixel • Preventing the Situation—Oh No! Memory Full • A Colorful Tour of TI-Fest: The Home Computer Show • Santa's Workshop: The Making of a Home Computer • The Turtle Arcade: Movies & Video Games in LOGO • Controlling a BASIC Termite • The 99'er Gold Rush—An Arcade/Adventure in the Home • 99'er Digest of News & Happenings in the TI World • Plus Games, Reviews, and much, much more.

January 1983 (Partial Contents)

• Computer Assisted Instruction for the Handicapped • P-system Basics • Debugging in LOGO • The Dow-4 Gazelle Flight Simulator • Note Whiz and Pitch Master Musical Game Reviews • Learning With the PLATO Computer Library • Strategies for Adventure Gaming • Death Grones • Using the Line-By-Line Assembler • Close Encounters of the Simon Kind • Electrical Engineering Education Program • Interview With an Arcade Game Designer • TI Invaders • Programming With Pascal • Cyber-Dice • News and Happenings in the Home Computer World • Arcade Game Reviews • The Thief Adventure Game • Programming Tips • and much, much more.





TI's new Compact Computer. It takes over your work, not your desk.

The ordinary personal computer occupies too much of the ordinary desk.

Now Texas Instruments brings you a cordless compact computer that solves the same sort of problems as the Apple™ or IBM™ personal computer. It has enough memory and power for complex problems in business and science, yet the whole thing is smaller than a magazine page.

Sophisticated software is available right now for finance, statistics, production planning, graphics—and spreadsheet and wordprocessing are just around the corner.

For most personal computer tasks, its 6K RAM and 34K ROM are ample. The system is easily, economically expanded.

The TI Compact Computer 40 has peripherals that make it even more useful:

a 4-color printer/plotter; an RS-232 interface for talking with other computers or running a larger printer; and TI Wafertape™ drive for program or data storage. TI Solid State Software™ cartridges offer you a choice of convenient, foolproof programs.

Its built-in language is TI Enhanced BASIC, which allows you to write programs in everyday words. The integrated liquid crystal display shows 31 characters, which can be scrolled to show up to 80 per line. It operates on four AA alkaline batteries that give up to 200 hours of service.

The TI Compact Computer 40 offers solutions anywhere you go. Yet it retails for less than 1/3* the price of Apple™ or IBM™ personal computers. The TI Compact Computer—compact in price and size, but not in power. See it soon at your Texas Instruments retailer.

Creating useful products
and services for you.



TEXAS INSTRUMENTS

Copyright © 1983 Texas Instruments

*Based on published manufacturer's suggested retail price.
Apple is a registered trademark of Apple Computer, Inc. IBM is a registered trademark of International Business Machines Corp.





PrintMateTM 150

THE MOST ADVANCED PRINTER IN ITS CLASS.

Good news for microsystem and personal computer users! MPI offers four wide carriage printers with excellence in price and performance. The two "A" versions of PrintMateTM 150 feature a factory installed "SoftSwitch"TM front panel keypad, with a 4K buffer on PrintMateTM 150 model A1 and a 16K buffer on model A2. PrintMateTM 150 models B1 and B2 are factory equipped with a 2K and 16K buffer, respectively. PrintMateTM 150 models have an exceptional set of outstanding graphics and font capabilities, optional expansion, and other advanced features that differentiate the PrintMateTM 150 from its competitive rivals as the superior performer. A bold claim? The strong and widespread acceptance of the excellent PrintMateTM 150 is based on outstanding user features:

HIGH SYSTEM THRUPUT—150 characters per second advanced logic seeking, impact printing with an accelerated print head slew rate and turnaround makes PrintMateTM 150 a high speed performer.

WIDE CARRIAGE VERSATILITY—The PrintMateTM 150's wide carriage can accommodate print lines from 136 to 231 characters in length and can easily handle forms from 3 to 15 inches wide and as long as 31 inches.

LARGE SELECTION OF PRINT CAPABILITIES—The 7x9 dot matrix allows user selection

of 10, 12, 15 or 17 characters per inch or the 11x9 serif font provides document quality printing at 10 characters per inch.

"SoftSwitch"TM FRONT PANEL CONTROL—

The PrintMateTM 150 A models have SoftSwitchTM front panel keypads for externally changing forms length, print density, horizontal and vertical tabs, baud rate and character set. A simple "SoftSwitch"TM entry will display the operating mode you have selected and PrintMateTM 150 responds to every entry with a pleasant tone of confirmation. With the "SoftSwitch"TM, you can turn off the printer—even unplug it—and PrintMateTM 150 will retain every detail in its non-volatile memory. The "SoftSwitch"TM may be added to the PrintMateTM B models.

EXPANDABLE PRINT BUFFER—PrintMateTM 150 models A2 and B2 have a factory installed 16K buffer. Both the 4K buffer model A1 and the standard 2K buffer model B1 are optionally expanded in increments to 16K. The PrintMateTM 150's expanded buffer allows application extensions for high speed interleaved printing and spooling, greatly improving the host computer's performance in applications that are print bound.

DOWNLINE LOADABLE FONTS—The powerful microprocessor based command set of the PrintMateTM 150 allows a custom character set to be developed in the host computer and downloaded to any Print-

MateTM 150 model with a 4K or larger buffer.

GRAPHICS—The standard graphics capabilities of all PrintMateTM 150 models allow printing of up to 6,120 individually addressable dots per square inch giving exceptional resolution for graphics and special characters.

PrintMateTM APPLICATIONS PACKAGES—

Turn-key graphics and display fonts can be implemented with an extensive line of MPI supported and maintained AP-PAKTM applications packages providing specialized fonts, custom graphs, tables, and picture graphics. Specialized characters such as logos may be easily defined and edited for printing directly from your computer.

CONSIDER THE FEATURES—Only PrintMateTM 150 offers so many ways to get your message across: graphics; display fonts; downline loadable character sets; high print speed; advanced logic seeking; 15 inch wide carriage; a variety of forms and paper capabilities and; friendly "SoftSwitch"TM interaction. The PrintMateTM 150 is the responsive performer that perfectly mates with your microsystem or personal computer. With prices beginning at \$995, it is evident that the PrintMateTM 150 is the superior performer in function and price.



Micro Peripherals, Inc.
4426 South Century Drive
Salt Lake City, UT 84107
Phone 1-800-821-8848



TI LOGO: It opened a door they thought was locked.

It opened a door to their minds.

The key: a Texas Instruments Learning Computer and TI LOGO, a programming language developed by TI and MIT.

In his inner-city, New York junior high classroom, teacher Steve Siegelbaum explains why it works so well.

"When they use it, they think they're teaching the machine. In reality, it's teaching them how to

learn. It definitely improves their attitude toward their other courses. Written and verbal expression improve—they're eager to show you, to tell you, what they've done."

Another teacher, Pete Rentof, adds, "What it fights is fear of failure—a mistake becomes a starting point. The whole learning process turns into a positive experience. It works."

The TI Learning Computer,

with TI LOGO and many other educational programs, is equipped to help open doors in any classroom. Including yours. For information on this remarkable system, contact: Texas Instruments Customer Relations, P.O. Box 53 Lubbock, Texas 79408.



TEXAS INSTRUMENTS

© 1981 Texas Instruments